

PROJECT INFORMATION

Project Title	LDSF Fuelbreak/Flat Top Biomass
Brief Description	<p>The LaTour Demonstration State Forest (LDSF) Fuelbreak/Flat Top Biomass project site is located on LaTour Demonstration State Forest, which is located approximately 45 miles east of Redding, in Shasta County and managed by the CA Department of Forestry and Fire Protection. The project consists of creating a 400 foot wide fuelbreak (200 feet on each side of four road segments) located on LDSF covering 199 acres. In addition, a biomass thinning operation is planned on Table Top Mountain which encompasses 104 acres. In total, the Fuelbreak/ Table Top Biomass operation covers 303 acres on LDSF.</p> <p>One fuelbreak segment is located along a portion of the McMullen Mountain Road which is located on a main ridgeline that transects from east to west near the center of LDSF. This segment is 12,500 feet long and covers 100 acres. Another segment is located on the Cutter Road which is located in the northeastern portion of LDSF. This segment is 6,178 feet long and covers 57 acres. The last two fuelbreak segments are located on the Rim Road, another main ridgeline located in the southeastern portion of LDSF. The combined Rim Road segments are 4,544 feet long and will create 42 acres of fuelbreak. The 104 acre Table Top Biomass thinning operation is located on the eastern Forest boundary, covering the area from the south side of Flat Top Mountain west to the Rim Road and south to the Huckleberry Road. Each treatment area will consist of harvesting small trees 3 to 12 inches in diameter at breast height (DBH) to achieve a desired spacing of approximately twenty feet between retained residuals. Harvesting will take place by means of mechanical sheers, skidding the resulting raw material referred to as "doodles" to nearby landings, chipping and blowing the material into chip vans, and transporting the chips to a co-generation plant.</p>

	<p>located either in Redding or Burney.</p> <p>PAGE 2 OF 3</p> <p>The areas surrounding LDSF have a long history of devastating fires occurring on a regular basis, with significant fires occurring most recently in 1968, 1978, 1987, and 2003. The project will reduce the risk of catastrophic wildfire and potential for post-fire sediment runoff into area waterways, while improving stand vigor and tree growth by thinning overstocked and/or Cytospora infected trees. LDSF is the headwater source of two major streams, Old Cow Creek and South Cow Creek. A tributary to the North Fork of Battle Creek and South Fork of Bear Creek drain small portions of the south side of LDSF.</p> <p>Cal Fire is providing \$14,000 worth of in-kind support to the project.</p>
Total Requested Amount	90,000.00
Other Fund Proposed	14,000.00
Total Project Cost	104,000.00
Project Category	Site Improvement/Restoration
Project Area/Size	303
Project Area Type	Acres
Have you submitted to SNC this fiscal year?	No
Is this application related to other SNC funding?	No

Project Results
Resource protection

Project Purpose	Project Purpose Percent
Natural Disaster Risk Reduction (Fire)	
Water Quality	

County
Shasta

Sub Region
North

PROJECT CONTACT INFORMATION

Name	Mr. Dave Loveless,
Title	Forest Manager
Organization	California Department of Forestry and Fire Protection
Primary Address	875 Cypress Avenue, , , Redding, CA, 96001
Primary Phone/Fax	530-225-2505 Ext.
Primary Email	dave.loveless@fire.ca.gov

PROJECT LOCATION INFORMATION

Project Location

Address: LaTour Demonstration State Forest, Portions of T32N, R2E, Sections 1, 19 & 11 and T32N, R3E, Sections 6 and 17, MDB&M, , , n/a, CA, n/a United States
Water Agency: Bella Vista Water District
Latitude: 40.607176
Longitude: -121.7031
Congressional District: n/a
Senate: n/a
Assembly: n/a
Within City Limits: No
City Name:

ADDITIONAL INFORMATION

Grant Application Type

Grant Application Type: Category One Site Improvement
--

Grant Application Type: Category One Conservation Easement Acquisition

PROJECT OTHER CONTACTS INFORMATION

Other Grant Project Contacts

Name:	Mr. Dave Loveless,
Project Role:	Day-to-Day Responsibility
Phone:	5302252505
Phone Ext:	
E-mail:	dave.loveless@fire.ca.gov

UPLOADS

The following pages contain the following uploads provided by the applicant:

Upload Name
Completed Application Checklist
Table of Contents
Full Application Form
Authorization to Apply or Resolution
Narrative Descriptions
Detailed Budget Form
Regulatory Requirements or Permits
CEQA Documentation
Letters of Support
Project Location Map
Parcel Map Showing County Assessors Parcel Number
Topographic Map
Photos of the Project Site
Land Tenure- Only for Site Improvement Projects

Site Plan - Only Site Improv. or Restoration Proj.

Site Plan - Only Site Improv. or Restoration Proj.

Site Plan - Only Site Improv. or Restoration Proj.

Site Plan - Only Site Improv. or Restoration Proj.

Site Plan - Only Site Improv. or Restoration Proj.

CEQA Documentation

CEQA Documentation

CEQA Documentation

CEQA Documentation

CEQA Documentation

CEQA Documentation

CEQA Documentation

CEQA Documentation

CEQA Documentation

CEQA Documentation

CEQA Documentation

CEQA Documentation
CEQA Documentation
CEQA Documentation
CEQA Documentation

To preserve the integrity of the uploaded document, headers, footers and page numbers have not been added by the system.

Appendix B1

Full Application Checklist

Project Name: LDSF Fuelbreak/Table Top Biomass

Applicant: California Department of Forestry and Fire Protection,
Latour Demonstration State Forest

Please mark each box: check if item is included in the application; mark "N/A" if not applicable to the project. "N/A" identifications must be explained in the application. Please consult with SNC staff prior to submission if you have any questions about the applicability to your project of any items on the checklist. All applications must include a CD including an electronic file of each checklist item, if applicable. The naming convention for each electronic file is listed after each item on the checklist. (Electronic File Name = EFN: "naming convention". file extension choices)

Submission requirements for all Category One and Category Two Grant Applications

1. ☒ Completed Application Checklist (EFN: Checklist.doc,.docx,.rtf, or .pdf)
2. ☒ Table of Contents (EFN: TOC.doc,.docx,.rtf, or .pdf)
3. ☒ Full Application Project Information Form (EFN: SIform.doc, .docx, .rtf, or .pdf)
4. ☒ Authorization to Apply or Resolution (EFN: authorization.doc, .docx, .rtf, or .pdf)
5. ☒ Narrative Descriptions - Submit a single document that includes each of the following narrative descriptions (EFN: Narrative.doc, .docx, .rtf)
 - a. ☒ Detailed Project Description (5,000 character maximum)
 - ☒ Project Description including Goals/Results, Scope of Work, Location, Purpose, etc.
 - ☒ Project Summary
 - ☒ Environmental Setting
 - b. ☒ Workplan and Schedule (1,000 character maximum)
 - c. ☒ Restrictions, Technical/Environmental Documents and Agreements(1,000 character maximum)
 - d. ☒ Organizational Capacity(1,000 character maximum)
 - e. ☒ Cooperation and Community Support (1,000 character maximum)
 - f. ☒ Long Term Management and Sustainability (1,000 character maximum)
 - g. ☒ Performance Measures (1,000 character maximum)
6. Supplemental and Supporting documents
 - a. ☒ Detailed Budget Form (EFN: Budget.xls, .xlsx)
 - b. Restrictions, Technical/Environmental Documents and Agreements, as applicable
 - N/A ☐ Restrictions / Agreements (EFN: RestAgree.pdf)
 - ☒ Regulatory Requirements / Permits (EFN: RegPermit.pdf)

- ☒ California Environmental Quality Act (CEQA) documentation (EFN: CEQA.pdf)
- N/A ☐ National Environmental Policy Act (NEPA) documentation (EFN: NEPA.pdf)
- c. Cooperation and Community Support
- ☒ Letters of Support (EFN: LOS.pdf)
- d. Long-Term Management and Sustainability
- N/A ☐ Long-Term Management Plan (EFN: LTMP.pdf)
- e. Maps and Photos
- ☒ Project Location Map (EFN: LocMap.pdf)
- ☒ Parcel Map showing County Assessor's Parcel Number(s) (EFN: ParcelMap.pdf)
- ☒ Topographic Map (EFN: Topo.pdf)
- ☒ Photos of the Project Site (10 maximum) (EFN: Photo.jpg, .gif)
- f. Additional submission requirements for Conservation Easement Acquisition applications only
- N/A ☐ Acquisition Schedule (EFN: acqSched.doc,.docx,.rtf,.pdf)
- N/A ☐ Willing Seller Letter (EFN: WillSell.pdf)
- N/A ☐ Real Estate Appraisal (EFN: Appraisal.pdf)
- N/A ☐ Conservation Easement Language (EFN: CE.pdf)
- g. Additional submission requirements for Site Improvement / Restoration Project applications only
- ☒ Land Tenure Documents – attach only if documentation was not included with Pre-application (EFN: Tenure.pdf)
- ☒ Site Plan (EFN: SitePlan.pdf)
- N/A ☐ Leases or Agreements (EFN: LeaseAgmnt.pdf)

I certify that the information contained in the Application, including required attachments, is accurate.

Signed _____
(Authorized Representative)

Date

David J. Loveless, Forest Manager – Forester II
Name and Title (print or type)

TABLE OF CONTENTS

Completed Application Checklist.....	1
Table of Contents.....	3
Full Application Project Information Form.....	4
Authorization to Apply.....	6
 5. Narrative Description.....	 7
a. Detailed Project Description Narrative.....	7
• Project Description.....	7
Location	7
Scope of Work	7
Goals/Results	8
• Project Summary.....	9
• Environmental Setting	9
b. Workplan and Schedule	11
• Workplan.....	11
• Schedule.....	13
c. Restrictions, Technical / Environmental Documents and Agreements	13
• Restrictions	13
• Agreements	13
• Regulatory Requirements/Permits	14
• California Environmental Quality Act (CEQA)	15
d. Organizational Capacity.....	15
e. Cooperation and Community Support	17
f. Long-Term Management and Sustainability	17
g. Performance Measures.....	18
• Number of People Reached	18
• Dollar Value of the Resources Leveraged for the Sierra Nevada.....	19
• Number and Type of Jobs Created.....	19
• Number of New, Improved or Preserved Economic Activities	19
• Kilowatts of Renewable Energy Production Capacity Maintained or Created.	20
• Tons of Carbon Sequestered or Emissions Avoided.....	20
• Acres of Land Improved or Restored.....	21
 6. Supplemental and Supporting Documents.....	 23
Budget.....	24
Regulatory Requirements / Permits.....	25
CEQA Documentation.....	37
Letters of Support.....	40
Project Location Map.....	41
County Assessors Parcel Numbers Map.....	42
Topographic Map.....	43
Photos of Project Sites.....	44
Land Tenure Documents.....	51
Site Plan Maps.....	57

Appendix B2

Note: You can only save data in this form if you are using Adobe Acrobat Pro. If you are not using Adobe Acrobat Pro, [click here](#) for a Microsoft Word version of this form, which you can fill out and save.

SIERRA NEVADA CONSERVANCY PROPOSITION 84 - PROJECT INFORMATION FORM		Rev. August 2011
PROJECT NAME LDSF Fuelbreak/Flat Top Biomass		
APPLICANT NAME <i>(Legal name, address, and zip code)</i> California Department of Forestry and Fire Protection, LaTour Demonstration State Forest (LDSF) 875 Cypress Avenue, Redding, CA 96001		
PERSON WITH FISCAL MANAGEMENT RESPONSIBILITY FOR GRANT CONTRACT/INVOICING <div style="display: flex; justify-content: space-between;"> <i>Name and title – type or print</i> <i>Phone</i> <i>Email Address</i> </div> <div style="display: flex; justify-content: space-between; margin-top: 5px;"> <div> <input checked="" type="checkbox"/> Mr. David J. Loveless <input type="checkbox"/> Ms. </div> <div> (530) 225-2505 </div> <div> dave.loveless@fire.ca.gov </div> </div>		
COUNTY ADMINISTRATOR OR PLANNING DIRECTOR CONTACT INFORMATION <i>(At least one entry is required)</i> <div style="display: flex; justify-content: space-between; margin-top: 10px;"> <i>Name:</i> Russ Mull, Director, Shasta County Planning Division <i>Phone Number:</i> (530) 225-5532 </div> <div style="margin-top: 10px;"> <i>Email address:</i> None </div> <div style="display: flex; justify-content: space-between; margin-top: 10px;"> <i>Name:</i> <i>Phone Number:</i> </div> <div style="margin-top: 10px;"> <i>Email address:</i> </div>		
NEAREST PUBLIC WATER AGENCY (OR AGENCIES) CONTACT INFORMATION <i>(At least one entry is required)</i> <div style="display: flex; justify-content: space-between; margin-top: 10px;"> <i>Name:</i> Bella Vista Water District <i>Phone Number:</i> (530) 241-1085 </div> <div style="margin-top: 10px;"> <i>Email address:</i> None </div> <div style="display: flex; justify-content: space-between; margin-top: 10px;"> <i>Name:</i> <i>Phone Number:</i> </div> <div style="margin-top: 10px;"> <i>Email address:</i> </div>		
Please identify the appropriate project category below and provide the associated details <i>(Choose One)</i> <div style="display: flex; justify-content: space-between; margin-top: 5px;"> <div> <input checked="" type="checkbox"/> Category One Site Improvement <input type="checkbox"/> Category One Conservation Easement Acquisition </div> <div> <input type="checkbox"/> Category Two Pre-Project Activities </div> </div>		
<input checked="" type="checkbox"/> Site Improvement/Conservation Easement Acquisition Project area: <u> LDSF </u> Total Acres: <u> 303 </u> SNC Portion (if different): <u> </u> Total Miles (i.e. river or stream bank): <u> </u> SNC Portion (if different): <u> </u>	Select <u>one</u> primary Site Improvement/Conservation Easement Acquisition deliverable <div style="margin-top: 5px;"> <input type="checkbox"/> Restoration <input type="checkbox"/> Enhancement <input checked="" type="checkbox"/> Resource Protection <input type="checkbox"/> Infrastructure Development / Improvement </div>	

<p>For Conservation Easement Acquisitions Only</p> <p><input type="checkbox"/> Appraisal Included</p> <p><input type="checkbox"/> Will submit appraisal by _____</p>	<p><input type="checkbox"/> Conservation Easement</p>								
<p><input type="checkbox"/> Pre-Project Activities</p>	<p>Select <u>one</u> primary Pre-Project deliverable</p> <table border="0"> <tr> <td><input type="checkbox"/> Permit</td> <td><input type="checkbox"/> Condition Assessment</td> </tr> <tr> <td><input type="checkbox"/> CEQA/NEPA Compliance</td> <td><input type="checkbox"/> Biological Survey</td> </tr> <tr> <td><input type="checkbox"/> Appraisal</td> <td><input type="checkbox"/> Environmental Site Assessment</td> </tr> <tr> <td><input type="checkbox"/> Plan</td> <td></td> </tr> </table>	<input type="checkbox"/> Permit	<input type="checkbox"/> Condition Assessment	<input type="checkbox"/> CEQA/NEPA Compliance	<input type="checkbox"/> Biological Survey	<input type="checkbox"/> Appraisal	<input type="checkbox"/> Environmental Site Assessment	<input type="checkbox"/> Plan	
<input type="checkbox"/> Permit	<input type="checkbox"/> Condition Assessment								
<input type="checkbox"/> CEQA/NEPA Compliance	<input type="checkbox"/> Biological Survey								
<input type="checkbox"/> Appraisal	<input type="checkbox"/> Environmental Site Assessment								
<input type="checkbox"/> Plan									



DEPARTMENT OF FORESTRY AND FIRE PROTECTION

Shasta Trinity Unit
875 Cypress Avenue
Redding, California 96001
(530) 225-2418
Website: www.fire.ca.gov



December 5, 2011

Sierra Nevada Conservancy
11521 Blocker Drive, Suite 205
Auburn, CA 95603

RE: LDSF FUELBREAK/FLAT TOP BIOMASS GRANT APPLICATION

I, Rick Kyle, whereby holding the position of CAL FIRE Shasta-Trinity Unit Chief and having authority to administer and approve operations on LaTour Demonstration State Forest, hereby authorize this application for grant funding through the Sierra Nevada Conservancy for the "LDSF Fuelbreak/Flat Top Biomass" project.

Sincerely,

Rick Kyle
Shasta-Trinity Unit Chief

cc: Bruce Beck, Unit Forester
Dave Loveless, LaTour State Demonstration Forest Manager

CONSERVATION IS WISE-KEEP CALIFORNIA GREEN AND GOLDEN

PLEASE REMEMBER TO CONSERVE ENERGY. FOR TIPS AND INFORMATION, VISIT "FLEX YOUR POWER" AT WWW.CA.GOV.

TABLE OF CONTENTS

Completed Application Checklist.....	1
Table of Contents.....	3
Full Application Project Information Form.....	4
Authorization to Apply.....	6
 5. Narrative Description.....	 7
a. Detailed Project Description Narrative.....	7
• Project Description.....	7
Location	7
Scope of Work	7
Goals/Results	8
• Project Summary.....	9
• Environmental Setting	9
b. Workplan and Schedule	11
• Workplan.....	11
• Schedule.....	13
c. Restrictions, Technical / Environmental Documents and Agreements	13
• Restrictions	13
• Agreements	13
• Regulatory Requirements/Permits	14
• California Environmental Quality Act (CEQA)	15
d. Organizational Capacity.....	15
e. Cooperation and Community Support	17
f. Long-Term Management and Sustainability	17
g. Performance Measures.....	18
• Number of People Reached	18
• Dollar Value of the Resources Leveraged for the Sierra Nevada.....	19
• Number and Type of Jobs Created.....	19
• Number of New, Improved or Preserved Economic Activities	19
• Kilowatts of Renewable Energy Production Capacity Maintained or Created.....	20
• Tons of Carbon Sequestered or Emissions Avoided.....	20
• Acres of Land Improved or Restored.....	21
 6. Supplemental and Supporting Documents.....	 23
Budget.....	24
Regulatory Requirements / Permits.....	25
CEQA Documentation.....	37
Letters of Support.....	40
Project Location Map.....	41
County Assessors Parcel Numbers Map.....	42
Topographic Map.....	43
Photos of Project Sites.....	44
Land Tenure Documents.....	51
Site Plan Maps.....	57

5. Narrative Description

a. Detailed Project Description Narrative

• Project Description

The LDSF Fuelbreak/Flat Top Biomass project site is located on LaTour Demonstration State Forest (LDSF), which is located approximately 45 miles east of Redding, in Shasta County. The project consists of creating a 400 foot wide fuelbreak, 200 feet on each side, along a series of four road segments located on LDSF covering 199 acres. In addition, a biomass thinning operation is planned on Table Top Mountain which encompasses 104 acres. In total, the Fuelbreak/ Table Top Biomass operation covers 303 acres on LDSF.

Location

One fuelbreak segment is located along a portion of the McMullen Mountain Road which is located on a main ridgeline that transects from east to west near the center of LDSF. This segment is 12,500 feet long and covers 100 acres. Another segment is located on the Cutter Road which is located in the northeastern portion of LDSF. This segment is 6,178 feet long and covers 57 acres. The last two fuelbreak segments are located on the Rim Road, another main ridgeline located in the southeastern portion of LDSF. The combined Rim Road segments are 4,544 feet long and will create 42 acres of fuelbreak. The 104 acre Table Top Biomass thinning operation is located on the eastern Forest boundary, covering the area from the south side of Flat Top Mountain west to the Rim Road and south to the Huckleberry Road.

Scope of Work

Both the fuelbreak and the biomass thinning operations have similar treatment criteria. In general, each treatment area will consist of harvesting small trees 3-12 inches in diameter at breast height (DBH) to achieve a desire spacing of approximately twenty feet between retained residuals. Harvesting will take place by means of mechanical sheers, skidding the resulting raw material referred to as doodles to nearby landings, chipping and blowing the material into chip vans, and transporting the chips to a co-generation plant located either in Redding or Burney.

All treatment area boundaries will be designated with florescent orange flagging. Sample treatment areas will be leave-tree marked in order to key equipment operators into tree selection and spacing criteria to allow completion of the operation using operator selection. With the exception of lodgepole pine and those infected trees, both criteria described below, those live trees that are larger than 12 inches in DBH shall be retained.

Those trees that are smaller than 14 inches to be retained to meet stocking and spacing criteria shall be those dominant trees that exhibit the best phenotype (physical characteristics) based on the immediately surrounding trees. Retained species in order of preference shall be Douglas-fir, sugar pine, ponderosa pine, western white pine, white fir and red fir. Where sufficient stocking exists in the preferred species to meet the twenty-foot spacing criteria, lodgepole pine smaller than 18 inches at DBH, based on ocular estimate, shall not be retained.

While similar in treatment criteria and objectives, the Table Top biomass thinning treatment is also targeted and intended to provide more than a fuelbreak and expanded growing space. The red fir in this area is infected with *Cytospora abietis*, a fungus widely found in California's true fir stands and commonly found in association with dwarf mistletoe. Therefore, this planned treatment covers a broader geographic area than those treatment areas specifically designed to create fuelbreaks. While this fungus can attack white fir and other tree species it is more specific to and prominent in the red fir in this stand and elsewhere on LDSF. Typical visible symptoms include increasing brick-red to brown flagging (needle die-back) in the crowns of infected trees, eventually leading to branch death and eventual tree mortality. Infected overstory trees also spread the disease to the understory, which perpetuates the infection cycle. In this area, those trees larger than 12 inches at DBH whose crowns exhibit *Cytospora* flagging greater than 50% and those trees that have succumbed to this disease shall be removed. Snags to be saved for wildlife purposes shall be marked (painted) with a "W" at DBH prior to operations. Trees in the 3-12 inch DBH range will be selected for removal based on spacing, species and the above described visible signs of infestation. The desired residual spacing for this area is also twenty feet.

Goals/Results

The objectives (goals/results) in each treatment area are also similar, and two-fold:

- 1) Resource protection by reducing the fuel loading in strategic areas, and thereby reducing the risk of and from catastrophic fire. This will be accomplished by reducing the number of conifer stems per acre in the smaller DBH classes. This will also reduce the ladder fuels that can allow ground fires to climb into the tree canopies resulting in catastrophic crown fires.
- 2) While a secondary by-product of the fuels reduction/biomass thinning, the operation will also serve to improve forest health and tree vigor by expanding growing space and reducing inter-tree competition for nutrients, moisture and sunlight.

- 3) Specific to the Table Top Biomass treatment area, an additional goal is to reduce the prevalence, impact and spread of the Cytospora fungus infection in the current and future crop of trees.

- **Project Summary**

The areas surrounding LDSF have a long history of devastating fires occurring on a regular basis, with significant fires occurring most recently in 1968, 1978, 1987, and 2003. The LDSF Fuelbreak/Flat Top Biomass project will create 303 acres of fuelbreak on LDSF (deliverable) which will reduce the risk of catastrophic wildfire while improving stand vigor and tree growth by thinning overstocked and/or Cytospora infected trees. In the event of fire on or approaching LDSF, these strategic fuelbreaks will act as natural barriers that will reduce the fire intensity, the potential for crown fire, the rate of spread, and provide logistical areas from which fire suppression efforts may more safely and successfully be undertaken. Additionally, the Flat Top biomass operation will improve the current and future stand health by removing much of the existing source of the ongoing Cytospora infection.

- **Environmental Setting**

The California Department of Forestry and Fire Protection (CAL FIRE) manages approximately 71,000 acres of Demonstration State Forests (DSFs), on behalf of the public. LaTour Demonstration State Forest (LDSF), a 9,033-acre mixed conifer forest located in the northern Sierra Nevada/southern Cascades is the second largest DSF. LDSF is located in eastern Shasta County in Townships 32 and 33 North, Ranges 2 and 3 East M.D.B & M. It ranges in elevation from 3,800 feet to over 6,700 feet with 80 percent of LDSF above 5,000 feet. The nearest community is Whitmore, eleven miles to the west.

LDSF is the headwater source of two major streams, Old Cow Creek and South Cow Creek. A tributary to the North Fork of Battle Creek and South Fork of Bear Creek drain small portions of the south side of LDSF.

The Board of Forestry and Fire Protection establishes policy which governs LDSF and other State Forests. Board policy states that the primary purpose of the state forest program is to conduct innovative demonstrations, experiments, and education in forest management. The entire LDSF has been zoned as a Timberland Production Zone (TPZ). This means the land is devoted to and used for growing and harvesting timber and compatible uses. Compatible use is defined as any use that does not significantly detract from the use of the land for, or inhibit, growing and harvesting timber. Compatible uses include watershed management, fish and wildlife habitat management, hunting and fishing, and grazing. No change in current land uses on or surrounding the project

areas are proposed or anticipated. The following is a list of management goals for LDSF (major goals synonymous with SNC mission and goals are underlined):

1. Maintain and strive to improve the research and demonstration program to provide valuable information regarding timber production, wildlife habitat requirements for various species that inhabit LDSF, and road management practices that result in reduced sediment. This information should be made available to the general public, small forest landowners, resource professionals, timber operators, and the timber industry. Research and demonstration projects will be aimed at providing practical information for forest landowners who need to manage a host of forest resources, including but not limited to, wildlife, water, soil, sensitive plants, and timber. Due to limited staff resources, cooperative research projects will be sought with other public and private researchers who share a common interest and direction in forest management. Staff will seek opportunities to disseminate to landowners and educate the public information on regarding Best Management Practices (BMPs) to maintain a healthy forest ecosystems. Continue research into forest-based carbon sequestration and forest management techniques to promote forest adaptation and resiliency to climate change.
2. Maintain a timber inventory for purposes of estimating growing stock by species and site class. The timber inventory data will be used to calculate timber growth and future sustained yield calculations. The timber inventory will also be used to estimate the quantity of certain wildlife habitat attributes such as snag retention and stand structure. The collection of this data will assist managers in evaluating wildlife use and habitat condition on LDSF.
3. Provide low impact recreational opportunities for forest visitors. Work toward expansion and improvement of existing facilities and the development of new recreational opportunities in suitable areas.
4. Harvest timber under sustained yield management (PRC 4513), methods and levels of harvest which permit continuous production of timber achieves maximum sustained production of high quality timber products (PRC 4513) without degrading the productivity and health of the forest, and contributes to local employment and tax revenue. Timber production will be conducted to provide local job opportunities, consistent with the overall objective of providing for recreation, wildlife, fisheries, aesthetic enjoyment, protection of soil resources, and protection of water quality.
5. Improve and maintain watershed protection through forest practices and erosion control efforts. Continue operating under the existing road management plan to maintain public access and prevent contamination of watercourses from road water runoff.
6. Continue an aggressive pest management program to help prevent the spread of insects and disease to keep tree mortality at a minimal level.

Harvest salvage material where feasible and compatible with the management of other forest resources.

7. Continue the fire prevention and hazard reduction programs and construct fuel breaks in critical areas to help keep the damage from wildfires at a minimum. Begin an aggressive prescribed burn program or other non-fire vegetation management program to help reduce the hazard associated with uncontrolled wildfires.

8. Work toward maintaining the widest possible diversity of managed forest stands in different successional stages, in order to foster ecosystem resiliency and adaptability to climate change, and develop a laboratory of representative forest conditions for research. Seek opportunities to maintain or increase functional wildlife habitat within the planning watersheds.

9. Prevent site degradation by using erosion controls and soil conservation practices in all management activities.

10. Continue to provide safe conditions for employees and visitors, identifying potentially hazardous situations, and where appropriate provide for safety guidelines, procedures, and equipment.

The surrounding property ownership includes private and National Forest lands. All adjacent lands are managed for timber production. Land to the north is administered by Beaty and Associates (Beaty) with Sierra Pacific Industries (SPI) owning a portion of the land. Property to the east is administered by Lassen National Forest and Beaty. SPI owns and administers lands to the south. Lands to the west are administered by Beaty and SPI.

b. Workplan and Schedule

• Workplan

The workplan, describing details and deliverables (underlined), necessary to successfully implement this project are included in the following outline and summarized in the “Schedule” table:

I. Prepare CAL FIRE Contract and Bid Package

- a. As a State Agency, CAL FIRE is required to prepare a contract, subject to review through the Department of General Services (DGS) for services in excess of \$5,000, and solicit competitive bids through the CAL FIRE Business Services Office. The contract approval process typically requires several months to complete the internal review and must be approved prior to disseminating the bid package to potential bidders.

II. Prepare & Submit Harvest Exemption

- a. As described below under “Regulatory Requirements/Permits”, a harvest exemption will be required in order to conduct operations

for those portions of the project area not already covered under existing approved Timber Harvest Plans (THPs).

- b. The exemption must be submitted to CAL FIRE at least five days prior to commencement of operations.
- c. The exemption is only valid for one year from the date it is accepted for filing.
- d. The exemption will be prepared and submitted by October 31, 2012.

III. Solicit Bids for Work

- a. The bid package, or notice, is sent to perspective bidders well in advance of the specified due date. It contains maps and project specifications including the bid due date and the contract expiration/project completion date. It also contains a schedule for a site visit with interested perspective bidders to visit the project site and ask pertinent questions prior to bid submission.
- b. The tentative date for the bid solicitation, mailing the bid package to perspective bidders, is October 31, 2012.

IV. Flag/Sample Mark Project Areas

- a. A sample mark has been prepared for the Fuelbreak along McMullen Mountain Road. Additional sample marks will be done in each of the treatment areas.
- b. Snags to be retained for wildlife purposes will be marked in the Table Top biomass treatment area prior to operations.
- c. Sample marking and flagging will be completed by the end of October, 2012.

V. Open/Award Bid

- a. Due to the projects elevation and lack of winter access the tentative bid due date is December 3, 2012 to allow perspective bidders to visit the project site prior to submitting bids.

VI. Project Work Commencement/Completion

- a. Upon awarding the bid, and approval of the contractor by CAL FIRE Contracting, the contractor may commence work.
- b. Tentative commencement date June 1, 2013, depending upon the successful bidders schedule and production rates. However, the contract will contain an expiration final completion date of October 31, 2013.
- c. Assuming a production rate of five acres per day, the project could conceivably be completed by the first of October, 2013. However, given the uncertainties with regard to the contract approval process as well as weather conditions and access, and to avoid the need to extend the contract, the contract will specify a completion date of October 31, 2013.

- **Schedule**

<u>PROJECT DELIVERABLES</u>	<u>TIMELINE</u>
Prepare CAL FIRE Contract & Bid Package	July 30, 2012
Prepare & Submit Harvest Exemption	October 31, 2012
Solicit Bids for Work	October 31, 2012
Flag/Sample Mark Project Areas	Summer- Fall , 2012
Open/Award Bid	December 3, 2012
Project Work Commencement/Completion	June 1, 2013 – October 31, 2013

c. Restrictions, Technical / Environmental Documents and Agreements

- **Restrictions**

Purchase of the property by the California Division of Forestry was made possible with the enactment of Chapter 1465 Statutes, dated July 17, 1945. Therein the legislature encumbered the sum of \$100,000 from the State Treasury for the purchase of the Cow Creek Unit by the Division of Forestry from the State Lands Commission. The patent deed to the property known as “LaTour State Forest” was executed on January 8, 1946. LDSF was the first sizable state forest acquired.

LDSF has no property restrictions, leases and/or encumbrances that could adversely impact the proposed Fuelbreak/Table Top Biomass project completion. (See Checklist – Restrictions/Agreements N/A)

- **Agreements**

As describe above under the “Workplan”, as a State Agency, CAL FIRE is required to prepare a contract, subject to review through the Department of General Services (DGS) for services in excess of \$5,000, and solicit competitive bids through the CAL FIRE Business Services Office. The contract approval process typically requires several months to complete the internal review and must be approved prior to disseminating the bid package to potential bidders. As per the Forest Practice Rules (FPRs), only Licensed Timber Operators (LTO) may conduct timber operations in the State of California. Upon awarding the project to the successful bidder both parties (CAL FIRE and contractor) will sign and receive a copy of the signed contract agreement and bid package. As this project is dependent upon the availability of grant funds, the contract will be prepared and submitted to CAL FIRE for review once SNC grant funding is approved in July, 2012. A copy of the contract agreement will be provided to SNC as a deliverable once it has been approved by CAL FIRE. (See Checklist – Restrictions/Agreements N/A)

- **Regulatory Requirements/Permits**

The Forest Practice Rules require that an environmental impact assessment be prepared as a part of and prior to harvesting timber in California. Portions of the proposed project area are covered under existing Timber Harvest Plans (THPs), a permitting process guided by statutes and implemented through policies established by the Board of Forestry as the functional equivalent of an EIR. Specifically, the entire 104 acre Table Top Biomass project area is covered under approved THP #2-09-084-SHA. A portion of the 42 acre Fuelbreak along the Rim Road is covered under approved THP #2-09-054-SHA. A portion of the McMullen Mountain Fuelbreak is also covered under an approved THP, #2-10-049-SHA. Portions of these documents are attached (See Supplemental and Supporting Documents and RegPermit.pdf)

For the balance of the Fuelbreak project areas, a timber harvest exemption will be required in order for timber operations to occur, and will be submitted to CAL FIRE, the lead review agency, prior to operations. Unlike a timber harvest plan (THP), which is a permitting process typically required prior to commercially harvesting timber in California, an exemption is a notification. Exemptions are allowed for timber operations that meet certain conditions and criteria, including the harvesting of dead, dying, or diseased trees and fuelwood products in amounts of less than 10% of the average volume per acre and operations that are limited to those trees that eliminate the vertical continuity of vegetative fuels and the horizontal continuity of tree crowns, for the purpose of reducing the rate of fire spread, duration and intensity, fuel ignitability, or ignition of tree crowns, as per Forest Practice Rules, 14 CCR §1038 (b) and (i) and the Forest Practice Act, Public Resource Code 4582. The exemption must be submitted at least five days prior to commencement of operations. As this project is dependent upon the availability of grant funds, the attached exemption notice (See Supplemental and Supporting Documents and RegPermit.pdf) will not be submitted to CAL FIRE for review until after grant funding is approved in July, 2012. Also, as an exemption is only valid for one year after submission, and as actual work is planned to commence in 2013, the exemption will be submitted to CAL FIRE in October of 2012. The SNC will receive a final copy of the Exemption, as a deliverable, once it has been submitted and accepted for filing by CAL FIRE.

In addition to existing, approved THPs and an Exemption to be prepared for this project, the LDSF staff operates under a Board of Forestry approved Management Plan. This plan provides general objectives and goals, and lays out the planned on-the-ground management on LDSF for the next five to ten years with an emphasis on forest demonstration, research, recreation, maintenance of wildlife habitat, and water quality protection. It serves as a guide to Forest managers as well as a public

disclosure of the management direction at LDSF. The plan is required pursuant to Public Resources Code (PRC) §4645 and Article 8 of the California Board of Forestry and Fire Protection (Board) policy.

- **California Environmental Quality Act (CEQA)**

While projects conducted on Latour Demonstration State Forest are not subject to review under the provisions of NEPA (See Checklist - NEPA N/A), as required on federal lands, they do require CEQA analysis and documentation. In general, the California Environmental Quality Act (CEQA) requires that an analysis of the potential environmental impacts be conducted, submitted, and approved prior to undertaking projects that are subject to a permitting process. The LDSF Management Plan, discussed above, is subject to review and approval by the California Board of Forestry, and therefore requires an environmental assessment. This requirement is fulfilled by a Negative Declaration CEQA document that has been approved for the LDSF Management Plan. That is, this project is covered by and in compliance with LaTour Demonstration State Forests' (LDSF) Management Plan and accompanying Mitigated Negative Declaration (State Clearinghouse #2008062009), both revised and approved by the California State Board of Forestry in August, 2008. This approved CEQA document, Notice of Determination attached to the application (See Supplemental and Supporting Documents and CEQA.pdf) contains the analysis necessary to conclude that projects such as the proposed Fuelbreak/ Biomass operation, combined with the past, present, and reasonably foreseeable probable future projects will not have a reasonable potential to cause or add to significant adverse cumulative impacts to the watershed, soil productivity, biological, recreation, visual, traffic, or other resources.

- d. Organizational Capacity**

Latour Demonstration State Forest has a full-time staff of three and a seasonal staff of two to six Forestry Aides. Full-time staff includes the following:

Dave Loveless, Forest Manager, RPF #2220 (Registered Professional Forester). Dave has a BS Degree in Forestry from Humboldt State University (HSU), has been working in the forest industry for 37 years and has been an RPF since 1984. He was an Associate with W.M Beaty & Associates, Inc., a land and timber Management Company located in Redding, for 24 years, and has been with CAL FIRE for seven years. Prior to becoming Forest Manager at LDSF, he held the position of Review Team Chair with CAL FIRE, heading an inter-agency interdisciplinary team tasked with reviewing all timber harvest plans (THPs) in inland northern California.

Ben Rowe, Assistant Forest Manager RPF #2686. Ben has a BS Degree in Wildlife Management from HSU, and has been working in the forest industry since 1993 and has been an RPF since 2000. He was a forester for Louisiana Pacific, a private consultant for wildlife and forestry, and also worked for W. M. Beaty and Associates until 2005. Ben started with CAL FIRE in 2005 and has been at LDSF since 2006.

Shannon Johnson – Forestry Assistant II. Shannon has a BS Degree in Conservation Biology from California State University Sacramento (CSUS). She has been working with CAL FIRE since 2004, starting as a Student Assistant at Sacramento Headquarters and also worked on LDSF for three seasons as a Forestry Aide while completing her degree. Prior to returning to LDSF in 2011 she was a Forestry Assistant II in the San Diego Unit and also at Jackson Demonstration State Forest (JDSF). She has recently taken the RPF examination.

Forestry Aides are hired each summer for two to nine months to assist staff with timber inventory, timber sale preparation, and other projects and tasks on LDSF. LDSF intends to hire four Forestry Aides for the 2012 and 2013 field seasons.

Also, as described above under “Agreements”, this project will be contracted to and executed by a licensed timber operator (LTO), as required under the Forest Practice Rules. There are several LTOs in the area who specialize in and have the appropriate equipment to conduct a biomass thinning operation. The contract will be administered and the operation supervised by LDSF Staff to ensure that the work is completed in compliance with the contract specifications.

In addition to the experienced and well rounded workforce, LDSF has a track record of undertaking and completing numerous projects on an annual basis. Staff prepares THPs and administers timber sales, typically harvesting 2-4 million board feet of timber annually. Approximately 900 acres are re-inventoried annually to maintain a database for timber and wildlife management. Sixty acres of brush was cleared, under contract, and an additional twenty acres broadcast burned last year in preparation for planting. Road contracts were prepared both last year and this year and the projects were completed on-time. The road projects are intended to improve and disconnect the road drainage system to reduce run-off and discharge into watercourses in order to enhance the watershed. As part of this year’s timber sale, fifty-five acres of brush was cleared under a variable retention silvicultural prescription in preparation for planting. Many of these projects are similar in nature and objective to this fuelbreak/biomass project; reduce fuel loading, improve stand vigor, forest health, improve wildlife habitat and diversity, and watershed enhancement.

Other fuelbreaks have also being established along high use roads such as the Bateman and Huckleberry Roads. These projects were completed, under contract, by LDSF Staff and have been maintained through the use of inmate fire crews or by means of contracts to control vegetation.

e. Cooperation and Community Support

The Cow Creek Watershed Management Group (CCWMG) is an organization comprised of local ranchers, timber companies, small landowners and other involved citizens interested in protecting and managing the Cow Creek drainage and other surrounding watersheds. As a major landowner/manager in this watershed, CAL FIRE is involved in this organization, and the LDSF Manager is a member of the Board. In general, the CCWMG is supportive of any activities that serve to protect or enhance these watersheds and their resources from which many derive their livelihood as well as recreational enjoyment. (See attached letter of support from the CCWMG).

In addition, the LDSF Management Plan, discussed above, is revised and presented to the Board of Forestry every five years. As described, this plan provides general objectives and goals, lists past projects, and lays out the planned on-the-ground management on LDSF. This process is transparent, open and available to the public for comment. The LDSF staff also has the opportunity to interact on a regular basis with recreational users where we have the opportunity to solicit feedback as to their general perception of LDSF. While anecdotal, comments received through these cursory contacts and conversations with the general public indicate overwhelmingly positive support for the management practices conducted on LDSF. Work to be conducted under this grant will not only serve to protect and further enhance the resources, but will also demonstrate to the public the commitment to obtain these goals through intensive forest management on LDSF.

f. Long-Term Management and Sustainability

A critical factor in establishing fuelbreaks includes a commitment to maintain them in order to preserve and capitalize on the original investment so that, should the need arise, they serve their intended purpose. CAL FIRE is committed to managing the LDSF for the long-term by investing in forest management as well as infrastructure, and by maintaining those assets and investments. As described under “Organizational Capacity”, other fuelbreaks have been established along high use roads such as the Bateman and Huckleberry Roads and have been maintained through the use of inmate fire crews and contract work to control brush and manage ingrowth. This year inmate crews cleared brush and trees along approximately three miles of roads on LDSF, including portions of existing Bateman fuelbreak. The work was

accomplished this fall and winter by hand clearing, piling, and burning. These crews, stationed at the Sugar Pine Camp near Ingot and Hwy 299, work on LDSF on an annual basis as available, typically after fire season.

The maintenance frequency and intensity for fuelbreaks are dependent upon how rapidly undesirable vegetation may begin to re-occupy the site and how much of this vegetation, ladder fuels, litter, and down material, is acceptable before the fuelbreak begins to lose functionality. Concentrations of heavy fuels created from falling limbs and snags, and removed during the original treatment are much slower to build up to the point where they create a fire hazard. However, ladder fuels, often a key contributor in stand replacing fires, must be removed before they provide that component and opportunity. Established fuelbreaks on LDSF are treated on an as-needed basis with follow-up thinning and brush removal occurring roughly every ten years. For the long-term management of this project, fuelbreaks established under this grant project will be inspected annually and maintained on a similar ten-year or as-needed schedule utilizing inmate crews. Guided by these essential management and maintenance standards, no additional supplemental and supporting documents are requisite for the management of these fuelbreaks (See Checklist – Long-Term Management Plan N/A).

g. Performance Measures

The following is a list and discussion of potential performance measures that may apply to this fuelbreak/biomass project. The first four quantitative performance measures listed are required, if applicable, to all projects, as per SNC Grant Guidelines. The subsequent three are proposed project-specific performance measures selected from the pre-approved list developed by the SNC:

- **Number of People Reached**

As described above under “Cooperation and Community Support”, those members of the Cow Creek Watershed Management Group and other interested parties who attend the meetings are familiar with management activities that take place on LDSF. In addition, LDSF accommodates over 6,000 recreational visitors and campers annually. Uses include camping, fishing, hunting, picnicking, sightseeing, hiking, horseback riding, nature walks, ATV, winter recreation, firewood and Christmas tree cutting. Each of these visitors are exposed to management activities that have and are occurring on the Forest. We have also been working with Shasta College, a local community college, to develop a MOU which would allow the college to use facilities and to conduct summer classes for those interested or majoring in natural resource fields. This program will provide further outreach and opportunities to expose and educate the community about management activities on LDSF.

- **Dollar Value of the Resources Leveraged for the Sierra Nevada**

Grant funds provided for this project through the Sierra Nevada Conservancy will be leveraged in two fundamental ways:

- The biomass material produced from this operation will be sold by the contractor to substantially offset the cost of operations. The remaining cost of the operation in excess of revenue, primarily attributable to the haul distance and resulting cost, will be supplemented by grant funds to subsidize the extended haul cost. Based on a projected yield of 4,500 tons of biomass from the operation, an estimated cost of \$64 per bone-dry ton delivered to market, and a current quoted spot price of \$44 per bone-dry ton delivered, the operation will yield revenues, approximately \$198,000, that will offset nearly 69% of the cost, approximately \$288,000. Actual costs and revenues will not be known until the contract bid is awarded, the exact amount of biomass material is known, and the harvested material is sold. These figures will be provided at the conclusion of the operation.
- LDSF staff In-kind contribution. Those costs associated with preparing the application, permits, environmental documents, contracts, field preparation and layout, flagging, marking, contract administration, and subsequent reports. See “Budget” for all projected cost estimates and the estimated dollar value of in-kind contributions from the grantee that extend, or leverage, SNC grant funds.

- **Number and Type of Jobs Created**

The LaTour Fuelbreak/Flat Top Biomass project is a significant undertaking that will take several months to complete. During this time, it will employ numerous personnel not only to accomplish the specific project, but indirectly as a result of the trickle down effect as well. While it is uncertain whether this project may result in creating new jobs in the community as a whole, it will contribute to maintaining and perpetuating existing jobs in the timber industry, co-generation energy production industry, and the community as well.

- **Number of New, Improved or Preserved Economic Activities**

This performance measure pertains to the fuelbreak/biomass project in that significant revenues will be generated through the sale of the biomass material to a co-generation plant by the contractor, which will be used to cover much, but not all, of the cost of the operation. The balance of the operating costs are intended to be subsidized under this SNC grant program (See “Budget”). The influx of wages spent by individuals directly and indirectly involved in this project into the community will contribute to and can only serve to stimulate economic activity both locally and beyond.

- **Kilowatts of Renewable Energy Production Capacity Maintained or Created**

The raw materials, all renewable by-products, harvested from the fuelbreak/biomass operation will be used to generate energy. Based on conversion tables available at <http://rsbiomass.com/woodfuels.html>, softwood chips at 30% moisture content can produce approximately 3.5 kWh of electricity per Kg of fuel. Also, based on an estimated total production of 4,500 tons of biomass material, predominantly composed of softwood chips, the estimated amount of renewable energy production capacity maintained by this project is calculated to be 14.288 million kilowatt-hours ($4,500 \text{ tons} = 4,082,331 \text{ Kg} * 3.5 \text{ kWh/Kg} = 14.288 \text{ megawatt-hours}$). This translates into enough energy to supply 2,381 homes with electricity for a year, based on an average household consumption of 6,000 kWh per year (<http://www.physics.uci.edu/~silverma/actions/HouseholdEnergy.html>).

- **Tons of Carbon Sequestered or Emissions Avoided**

In 2007 the State of California passed the Global Warming Solutions Act (AB 32), which set targets to reduce greenhouse gas emissions to 1990 levels by 2020 and 80 percent below 1990 levels by 2050. The California Air Resources Board was tasked with obtaining compliance with the cap through regulatory and market approaches. Planning is currently underway and definitive decisions by the Board have not yet been taken, however, it appears that forests will play a significant role in non-regulated strategies to meet targets. This is anticipated to occur both as offsets within a cap and trade system and through voluntary measures.

Recognized strategies to mitigate GHG emissions and enhance terrestrial sequestration include reforestation, forest management and fuels treatments to avoid catastrophic losses. LDSF will contribute to the targets of AB32 by increasing the resiliency of the Forest to catastrophic mortality by improving the general health of stands, pre-fire implementation of shaded fuel breaks and maintenance of firefighting infrastructure such as roads, signage and water sources. The long-term carbon stocks of the Forest are anticipated to increase over time. For example, the LDSF Long-Term Management Plan (Option A Plan) indicates that the timber inventory on the Forest will increase from about 22.7 MBF per acre in 2005 to 34.4 MBF per acre in 2105.

Forest products produced from LDSF will sequester carbon during their life cycle. Biomass fuels produced on the Forest also provide an opportunity to replace fossil fuels with an alternative energy source that is close to carbon neutral.

LDSF, in cooperation with WESTCARB, is currently conducting a Carbon Sequestration Project designed to demonstrate various methods to

improve carbon sequestration in forested environments and the protocols in carbon registration. A total of seven units encompassing 281 acres were established between 2007 and 2009 and treated by various means including clearing brush using tractor & brush rake or masticator, controlling brush with spray treatments to release existing conifers, and planting tree seedlings.

Annually across the country, millions of tons of carbon are emitted into the atmosphere as a result of the environment and typical nature of the fuels consumed under wildland fire conditions. By implementing this fuelbreak/biomass project on LDSF, potentially thousands of tons of emissions may be avoided in the event of a fire. The material harvested during this operation will be dried and burned at one of several surrounding co-generation plants under environmentally controlled conditions. While there are alternative opinions, current Federal EPA regulations have accepted the premise that facilities fueled by woody waste are "carbon-neutral". That is, it is considered a process that simply speeds up the carbon cycle that would otherwise naturally occur as plants decompose. Therefore, emissions produced by converting the material from this project to energy in licensed wood-burning co-generation plants are considered to be "carbon neutral" according to the EPA.

Alternatively, based on extrapolation of information contained in Forest Carbon Emissions Model (FCEM) Report No. 2 for four California Fires, prepared by Thomas M. Bonnicksen, Ph.D., March 12, 2008, a catastrophic fire on LDSF may conservatively have the potential of emitting 50 tons of CO₂ per acre produced from combustion, and 185 tons of CO₂ per acre produced from combustion and decay over a 100-year period. Expanded forest wide, these estimates amount to approximately 452 thousand tons and 1.671 million tons, respectively, of potential CO₂ emissions that may be avoided from a catastrophic fire on LDSF.

In this report, the author states: "The immensity of greenhouse gas emissions illustrated in Table 7 from just these four wildfires is a warning. Clearly, we must make every effort to reduce the amount of excess biomass in forests to prevent catastrophic wildfires. That means thinning trees to restore the natural health and diversity of forests and to make them more resistant to crown fires. Reducing wildfires may be the single most important action we can take in the short-term to reduce greenhouse gas emissions and fight global warming."

- **Acres of Land Improved or Restored**

The Fuelbreak/Flat Top Biomass project will improve the productivity of the forest land by removing dense brush and the overstocked smaller conifer trees (ladder fuels) that are currently competing with crop trees for

limited resources, moisture, nutrients and sunlight, as well as creating hazardous and potentially catastrophic fire conditions. This project proposes treatment of 303 acres of timberland. Actual acres treated will be reported upon completion of the project.

Appendix B3

Sierra Nevada Conservancy Proposition 84 - Detailed Budget Form

Project Name: **LDSF Fuelbreak / Flat Top Biomass**

Applicant: **CAL FIRE - Latour Demonstration State Forest**

SECTION ONE DIRECT COSTS	(2012) Year One	(2013) Year Two	Year Three	Year Four	Year Five	Total
Fuelbreak/Biomass Operations		90,000				\$90,000.00
(Includes skidding, chipping, and haul costs)						\$0.00
						\$0.00
						\$0.00
						\$0.00
						\$0.00
						\$0.00
DIRECT COSTS SUBTOTAL:	\$0.00	\$90,000.00	\$0.00	\$0.00	\$0.00	\$90,000.00

SECTION TWO OPERATIONS AND MAINTENANCE	Year One	Year Two	Year Three	Year Four	Year Five	Total
						\$0.00
						\$0.00
						\$0.00
MAINTENANCE SUBTOTAL:	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00
PROJECT TOTAL:	\$0.00	\$90,000.00	\$0.00	\$0.00	\$0.00	\$90,000.00

SECTION THREE Administrative Costs (Description - <i>Not to exceed 15% of Project Categories</i>):						
						\$0.00
						\$0.00
						\$0.00
						\$0.00
						\$0.00
ADMINISTRATIVE TOTAL:	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00
SNC TOTAL GRANT REQUEST:	\$0.00	\$90,000.00	\$0.00	\$0.00	\$0.00	\$90,000.00

SECTION FOUR OTHER PROJECT CONTRIBUTIONS	Year One	Year Two	Year Three	Year Four	Year Five	Total
List other funding or in-kind contributors to project						
CAL FIRE In-Kind Contribution	9,000	5,000				\$14,000.00
(Includes preparing the application, permits, environmental documents, contracts, field preparation and layout, flagging, marking, contract administration, and subsequent reports)						\$0.00
						\$0.00
						\$0.00
						\$0.00
TOTAL OTHER CONTRIBUTIONS:	\$9,000.00	\$5,000.00	\$0.00	\$0.00	\$0.00	\$14,000.00

NOTE: The categories listed on this form are examples and may or may not be an expense related to the project. Rows may be added or deleted on the form as needed. Applicants should contact the SNC if questions arise.

FOR ADMIN. USE ONLY
Amendments-date & S or M

1. TGU 7. NSO
2. FGI Fall line 8. Buck Butte
3. WQ5 Boone 9. CGS
4. LNF 10. _____
5. SHU-PW 11. _____
6. RT 12. _____

TIMBER HARVESTING PLAN
STATE OF CALIFORNIA
DEPARTMENT OF FORESTRY
AND FIRE PROTECTION
RM-63 (02-03)

THP Name: Buck Butte

(In the CDF FPS, this is "THP Description")

If this is a Modified THP, check box: ☐ []

FOR ADMIN. USE ONLY

THP No. 2-09-059-SHA ⁵ (A)

Dates Rec'd AUG 31 2009

Date Filed SEP 10 2009

Date Approved NOV 12 2009

Date Expires NOV 11 2012

Extensions 1) ☐ [] 2) ☐ []

This Timber Harvesting Plan (THP) form, when properly completed, is designed to comply with the Forest Practice Act (FPA) and Board of Forestry and Fire Protection rules. See separate instructions for information on completing this form. NOTE: The form must be printed legibly in ink or typewritten. The THP is divided into six sections. If more space is necessary to answer a question, continue the answer at the end of the appropriate section of your THP. If writing an electronic version, insert additional space for your answer. Please distinguish answers from questions by *font change* bold or underline.

SECTION I - GENERAL INFORMATION

This THP conforms to my/our plan and upon approval, I/we agree to conduct harvesting in accordance therewith. Consent is hereby given to the Director of Forestry and Fire Protection, and his or her agents and employees, to enter the premises to inspect timber operations for compliance with the Forest Practice Act and Forest Practice Rules.

1. TIMBER OWNER(S) OF RECORD: Name: **California Department of Forestry and Fire Protection**

Address **875 Cypress Avenue**

City **Redding** State **CA** Zip **96001** Phone **(530) 225-2505**

Signature Bruce W. Beck Date 8-26-09

NOTE: The timber owner is responsible for payment of a yield tax. Timber Yield Tax information may be obtained at the Timber Tax Section, MIC: 60, State Board of Equalization, P.O. Box 942879, Sacramento, California 94279-0060; phone 1-800-400-7115; BOE Web Page at <http://www.boe.ca.gov>.

2. TIMBERLAND OWNER(S) OF RECORD: Name: **California Department of Forestry and Fire Protection**

Address **875 Cypress Avenue**

City **Redding** State **CA** Zip **96001** Phone **(530) 225-2505**

Signature Bruce W. Beck Date 8-26-09

TIMBERLAND OWNER(S) OF RECORD: Brooks Walker et al. C/O W. M. Beaty & Associates (Water drafting only)

Address: P.O. Box 990898

City Redding State CA Zip 96099-0898 Phone (530) 243-2783

Signature: See attached letter Section V Date: _____



DEPARTMENT OF FORESTRY AND FIRE PROTECTION
NORTHERN REGION HEADQUARTERS-REDDING
6105 Airport Road
Redding, CA 96002
(530) 224-2445
Website: www.fire.ca.gov



November 12, 2009

Timber Harvesting Plan
No. 2-09-059-SHA
BUCK BUTTE

CA DEPT OF FORESTRY & FIRE PROTECTION
875 CYPRESS AVE
REDDING, CA 96001

Dear Gentleperson(s):

Enclosed is a true copy of your Timber Harvesting Plan identified by date and file number shown above. The Director of Forestry finds that the plan conforms with the rules and regulations of the Board of Forestry pursuant to the provisions of the Z'Berg-Nejedly Forest Practice Act of 1973. Conformance is indicated by the facsimile signature of his duly constituted representative being shown on the attached copy of the plan.

You may begin the timber operations proposed in the plan according to the conditions specified therein, and subject to the Forest Practice Act, Forest Practice Rules of the Forest District in which the operations will take place, related Board of Forestry regulations and other applicable laws, regulations and ordinances.

The Forest Practice Act requires the filing of the two reports listed below for each timber harvesting operation undertaken:

1. Timber operations after completion of work described in a Timber Harvesting Plan, excluding work for stocking, a report shall be filed by the timber owner or his agent with the Director that all work, except stocking, has been completed.
2. Report of Stocking - within five (5) years after completion of timber operations covered by a Timber Harvesting Plan, a report of stocking shall be filed by the timber owner or his agent with the Director.

The Timber Harvesting Plan will expire on **November 11, 2012**. Any request for an extension must be received ten (10) days prior to the expiration date shown above.

The effective period of this Timber Harvesting Plan is up to three years from the date the Director's representative signed the plan as being in conformance with the Forest Practice Act and Rules unless extended pursuant to **Public Resources Code 4590**.

In future correspondence, please refer to the number in the box in the upper right corner of the plan.

Sincerely,



WILLIAM E. SCHULTZ, RPF #1974
Deputy Chief
Forest Practice

Enclosure

cc: TGU-Unit/Inspector-Darley
RPF-Schultz
TLO/TO - CAL FIRE, Brooks Walker et al, Davis
Board of Equalization
Shasta Public Works
F&G 1
WQ 5

FOR ADMIN. USE ONLY

Amendments-date & S or M

1. SHU 7. RT
 Stanis 2. FGI 8. W
 + 3. WQ5 9. Brook
 Boone 4. LNF 10. Barley
 5. PW-SHA 11.
 6. CGS 12.

TIMBER HARVESTING PLAN

STATE OF CALIFORNIA
 DEPARTMENT OF FORESTRY
 AND FIRE PROTECTION
 RM-63 (02-03)

THP Name: **Rim Road**

(In the CDF FPS, this is "THP Description")

If this is a Modified THP, check box: ☐

FOR ADMIN. USE ONLY

THP No. **2-09-084-SHA**Dates Rec'd **OCT 07 2009**Date Filed **OCT 17 2009**Date Approved **DEC 1 12 2009**Date Expires **DEC 10 2012**Extensions 1) ☐ 2) ☐

This Timber Harvesting Plan (THP) form, when properly completed, is designed to comply with the Forest Practice Act (FPA) and Board of Forestry and Fire Protection rules. See separate instructions for information on completing this form. NOTE: The form must be printed legibly in ink or typewritten. The THP is divided into six sections. If more space is necessary to answer a question, continue the answer at the end of the appropriate section of your THP. If writing an electronic version, insert additional space for your answer. Please distinguish answers from questions by *font change*, **bold** or underline.

SECTION I - GENERAL INFORMATION

This THP conforms to my/our plan and upon approval, I/we agree to conduct harvesting in accordance therewith. Consent is hereby given to the Director of Forestry and Fire Protection, and his or her agents and employees, to enter the premises to inspect timber operations for compliance with the Forest Practice Act and Forest Practice Rules.

1. TIMBER OWNER(S) OF RECORD: Name: **California Department of Forestry and Fire Protection**

Address **875 Cypress Avenue**City **Redding** State **CA** Zip **96001** Phone **(530) 225-2505**Signature Bruce A Beck 10-6-09 Date

NOTE: The timber owner is responsible for payment of a yield tax. Timber Yield Tax information may be obtained at the Timber Tax Section, MIC: 60, State Board of Equalization, P.O. Box 942879, Sacramento, California 94279-0060; phone 1-800-400-7115; BOE Web Page at [http:// www.boe.ca.gov](http://www.boe.ca.gov).

2. TIMBERLAND OWNER(S) OF RECORD: Name: **California Department of Forestry and Fire Protection**

Address **875 Cypress Avenue**City **Redding** State **CA** Zip **96001** Phone **(530) 225-2505**Signature Bruce A Beck 10-6-09 Date

3. TIMBERLAND OWNER(S) OF RECORD: **Brooks Walker et al. C/O W. M. Beaty & Associates (Water drafting only)**

Address: **P.O. Box 990898**City **Redding** State **CA** Zip **96099-0898** Phone **(530) 243-2783**Signature: See attached letter Section V Date: **RECEIVED****OCT 07 2009****REDDING
FOREST PRACTICE**

RECEIVED

ARNOLD SCHWARZENEGGER, Governor



DEPARTMENT OF FORESTRY AND FIRE PROTECTION
NORTHERN REGION HEADQUARTERS-REDDING
6105 Airport Road
Redding, CA 96002
(530) 224-2445
Website: www.fire.ca.gov

DEC 30 2009
Shasta-Trinity
Resource Management



December 11, 2009

Timber Harvesting Plan
No. 2-09-084-SHA
RIM ROAD

CA DEPT OF FORESTRY & FIRE PROTECTION
875 CYPRESS AVE
REDDING, CA 96001

Dear Gentleperson(s):

Enclosed is a true copy of your Timber Harvesting Plan identified by date and document number shown above. The Director of Forestry finds that the plan conforms with the rules and regulations of the Board of Forestry pursuant to the provisions of the Z'Berg-Nejedly Forest Practice Act of 1973. Conformance is indicated by the facsimile signature of his duly constituted representative being shown on the attached copy of the plan.

You may begin the timber operations proposed in the plan according to the conditions specified therein, and subject to the Forest Practice Act, Forest Practice Rules of the Forest District in which the operations will take place, related Board of Forestry Regulations and other applicable laws, regulations and ordinances.

The Forest Practice Act requires the filing of the two reports listed below for each timber harvesting operation undertaken:

1. Timber operations after completion of work described in a Timber Harvesting Plan, excluding work for stocking, a report shall be filed by the timber owner or his agent with the Director that all work, except stocking, has been completed.
2. Report of Stocking - within five (5) years after completion of timber operations covered by a Timber Harvesting Plan, a report of stocking shall be filed by the timber owner or his agent with the Director.


The Timber Harvesting Plan will expire on **December 10, 2012**. Any request for an extension must be received ten (10) days prior to the expiration date shown above.

THP 2-09-084-SHA
Page Two

The effective period of this Timber Harvesting Plan is up to three years from the date the Director's representative signed the plan as being in conformance with the Forest Practice Act and Rules unless extended pursuant to **Public Resources Code 4590**.

In future correspondence, please refer to the number in the box in the upper right corner of the plan.

Sincerely,



WILLIAM E. SCHULTZ
Deputy Chief
Forest Practice
RPF #1974

Attachment

cc:
SHU/Darley
RPF-Rowe
TLO/TO CAL FIRE
Board of Equalization
Shasta County PW
F&G 1
WQ 5

Section: 1

North McMullen Mountain THP

FOR ADMIN. USE ONLY
Amendments-date & S or M

TIMBER HARVESTING PLAN
STATE OF CALIFORNIA
DEPARTMENT OF FORESTRY

FOR ADMIN. USE ONLY

THP No.
2-10-049-SHA (4)

AND FIRE PROTECTION
RM-63 (02-03)

Dates Rec'd **10/1/2010**

1. SHU 7. Darley
2. FGI 8. _____
3. WQ5 9. _____
4. SHA-PW 10. _____
5. CGS 11. _____
6. RT 12. _____

THP Name: **North McMullen Mt.**

(In the CDF FPS, this is "THP Description")

If this is a Modified THP, check box: ☐ []

Date Filed **OCT 08 2010**

Date Approved **MAY 24 2011**

Date Expires **MAY 23 2014**

Extensions 1) ☐ [] 2) ☐ []

This Timber Harvesting Plan (THP) form, when properly completed, is designed to comply with the Forest Practice Act (FPA) and Board of Forestry and Fire Protection rules. See separate instructions for information on completing this form. NOTE: The form must be printed legibly in ink or typewritten. The THP is divided into six sections. If more space is necessary to answer a question, continue the answer at the end of the appropriate section of your THP. If writing an electronic version, insert additional space for your answer. Please distinguish answers from questions by *font change*, **bold** or underline.

SECTION I - GENERAL INFORMATION

This THP conforms to my/our plan and upon approval, I/we agree to conduct harvesting in accordance therewith. Consent is hereby given to the Director of Forestry and Fire Protection, and his or her agents and employees, to enter the premises to inspect timber operations for compliance with the Forest Practice Act and Forest Practice Rules.

1. TIMBER OWNER(S) OF RECORD: Name: **California Department of Forestry and Fire Protection**

Address **875 Cypress Avenue**

City **Redding** State **CA** Zip **96001** Phone **(530) 225-2505**

Signature Bruce W. Beck

Date **9/30/10**

NOTE: The timber owner is responsible for payment of a yield tax. Timber Yield Tax information may be obtained at the Timber Tax Section, MIC: 60, State Board of Equalization, P.O. Box 942879, Sacramento, California 94279-0060; phone 1-800-400-7115; BOE Web Page at <http://www.boe.ca.gov>.

2. TIMBERLAND OWNER(S) OF RECORD: Name: **California Department of Forestry and Fire Protection**

Address **875 Cypress Avenue**

City **Redding** State **CA** Zip **96001** Phone **(530) 225-2505**

Signature Bruce W. Beck

Date **9/30/10**

TIMBERLAND OWNER(S) OF RECORD: **Carl J. & Jo Ann Davis (Water drafting only)**

Address: **P.O. Box 142**

City Whitmore State CA Zip 96069 Phone none

Signature: See attached letter Section V Date: _____

RECEIVED

OCT 01 2010

REDDING
FOREST



DEPARTMENT OF FORESTRY AND FIRE PROTECTION
NORTHERN REGION HEADQUARTERS-REDDING
6105 Airport Road
Redding, CA 96002
(530) 224-2445
Website: www.fire.ca.gov

RECEIVED
MAY 25 2011
Shasta-Trinity
Resource Management



May 24, 2011

Timber Harvesting Plan
No. 2-10-049-SHA
NORTH MCMULLEN MT

CA DEPT OF FORESTRY & FIRE PROTECTION
875 CYPRESS AVE
REDDING, CA 96001

Dear Gentleperson(s):

Enclosed is a true copy of your Timber Harvesting Plan identified by date and document number shown above. The Director of Forestry finds that the plan conforms with the rules and regulations of the Board of Forestry pursuant to the provisions of the Z'Berg-Nejedly Forest Practice Act of 1973. Conformance is indicated by the facsimile signature of his duly constituted representative being shown on the attached copy of the plan.

You may begin the timber operations proposed in the plan according to the conditions specified therein, and subject to the Forest Practice Act, Forest Practice Rules of the Forest District in which the operations will take place, related Board of Forestry Regulations and other applicable laws, regulations and ordinances.

The Forest Practice Act requires the filing of the two reports listed below for each timber harvesting operation undertaken:

1. Timber operations after completion of work described in a Timber Harvesting Plan, excluding work for stocking, a report shall be filed by the timber owner or his agent with the Director that all work, except stocking, has been completed.
2. Report of Stocking - within five (5) years after completion of timber operations covered by a Timber Harvesting Plan, a report of stocking shall be filed by the timber owner or his agent with the Director.

The Timber Harvesting Plan will expire on **May 23, 2014**. Any request for an extension must be received ten (10) days prior to the expiration date shown above.

CONSERVATION IS WISE-KEEP CALIFORNIA GREEN AND GOLDEN

PLEASE REMEMBER TO CONSERVE ENERGY. FOR TIPS AND INFORMATION, VISIT "FLEX YOUR POWER" AT WWW.CA.GOV.

The effective period of this Timber Harvesting Plan is up to three years from the date the Director's representative signed the plan as being in conformance with the Forest Practice Act and Rules unless extended pursuant to **Public Resources Code 4590**.

In future correspondence, please refer to the number in the box in the upper right corner of the plan.

Sincerely,

A handwritten signature in black ink, reading "Michael J. Bacca". The signature is fluid and cursive, with the first name "Michael" and last name "Bacca" clearly legible.

MICHAEL J. BACCA RPF #2236
Forester III, Cascade,
Sierra & Southern Regions
Forest Practice Manager

Attachment

cc:
UNIT-SHU
RPF-Benjamin Rowe
TLO/TO-CA Dept of Forestry & Fire Protection/Carl J. & Jo Ann Davis
INSPECTOR-Daley
Board of Equalization
Public Works-SHA
FG-1
WQ-5
FILE

Date: May 2 2011

Mitigation Monitoring Plan

The compliance with mitigation measures required or incorporated in this Timber Harvesting Plan will be monitored during the inspections conducted by CDF as authorized or required by the Forest Practice Act. The inspections include but are not limited to inspections during operations pursuant to Section 4604, inspections of completed work pursuant to Section 4586, and stocking inspections pursuant to Section 4588.

Approved


For Ken Pimlott, Acting Director
California Department of
Forestry & Fire Protection

**CHRISTMAS TREE; DEAD, DYING OR DISEASED;
FUELWOOD OR SPLIT PRODUCTS EXEMPTION**

FOR ADMIN. USE ONLY

STATE OF CALIFORNIA
DEPARTMENT OF FORESTRY AND FIRE PROTECTION
NOTICE OF TIMBER OPERATIONS THAT ARE EXEMPT FROM
TIMBER HARVESTING PLAN REQUIREMENTS; RM-73 (1038ab) (11/11)

Ex. # _____

Date of Receipt _____

Date Expires _____

VALID FOR ONE YEAR FROM DATE OF RECEIPT BY CAL FIRE

The Director of the Department of Forestry and Fire Protection (CAL FIRE) is hereby notified of timber operations under the requirements of 14 CCR § 1038(a) or (b). The following type(s) of timber operation is to be conducted:

- XX Harvesting Christmas trees.
- XX Harvesting dead, dying or diseased trees of any size in amounts less than 10 percent of the average volume per acre, where timber operations will meet the conditions listed in 14 CCR § 1038(b).
- XX Harvesting fuelwood or split products in amounts less than 10 percent of the average volume per acre, where timber operations will meet the conditions listed in 14 CCR § 1038(b). **Note:** If you are harvesting fuelwood or split products, please be aware that cut wood can be infested with harmful forest pests. Long distance transport of infested firewood can result in the unintentional spread of these pests. Please see www.firewood.ca.gov for more information.

The timber owner shall complete this form both pages, then sign on page two.

1. TIMBER OWNER(S) OF RECORD: Name CAL FIRE, LaTour Demonstration State Forest

Address 875 Cypress Ave

City Redding State CA Zip 96001 Phone 530-225-2505

TIMBER TAX NOTICE: Timber owners owe timber yield tax when they harvest trees unless the harvest is exempt (Revenue and Taxation Code sec. 38116). Some small or low value harvests may be exempt from the timber yield tax: timber removed from an operation whose value does not exceed \$3,000 within a quarter, according to BOE Harvest Value Schedules, Rule 1024. If you believe your harvest may qualify for this exemption, please complete items A, B, C, and D below. **For timber yield tax information or for further assistance with these questions call the State Board of Equalization, 1-800-400-7115** or write: Timber Tax Section, MIC: 60, State Board of Equalization, P.O. Box 942879, Sacramento, California 94279-0060; or contact the BOE Web Page on the Internet at <http://www.boe.ca.gov>.

A. Circle the option that most closely estimates the total volume for this harvest, in thousands of board feet (mbf - Net Scribner short log):

Under 8 mbf 8-15 mbf 16-25 mbf Over 25 mbf

B. Estimate what percentage of timber will be removed during this harvest:

Redwood _____%; Ponderosa/Sugar pine _____%; Douglas-fir _____%; Fir _____%;

Port-Orford Cedar _____%; Cedar (IC, WRC) _____%; Other conifer %; _____; Other hardwood _____%.

C. Fuelwood over 150 cords? Yes _____ No _____ D. Christmas trees over 3,000 lineal feet? Yes _____ No _____

2. TIMBERLAND OWNER(S) OF RECORD: Name CAL FIRE, LaTour Demonstration State Forest

Address 875 Cypress Ave

City Redding State CA Zip 96001 Phone 530-225-2505

3. LICENSED TIMBER OPERATOR(S): Name CAL FIRE, LaTour Demonstration State Forest Lic. # _____

Address 875 Cypress Ave

City Redding State CA Zip 96001 Phone 530-225-2505

NOTICE OF EXEMPTION FOR CHRISTMAS TREES; DEAD, DYING OR DISEASED; FUELWOOD. Page Two

4. Designate the legal land description of the location of the timber operation. Attach a 7.5 minute quadrangle or equivalent map showing the location of the timber operation. It would be helpful to show the access road and attach a copy of an assessor's parcel map for areas of less than 40 acres.

Section	Township	Range	Base & Meridian	County	Logging Area Acreage (Estimated)	Assessors Parcel # (Optional)
1-3,10-15,22-24	32N	2E	MDB&M			
6,7,17,18	32N	3E	MDB&M	Shasta	9,033	

The following are limitations or requirements for timber operations conducted under a Notice of Exemption for Christmas Trees, Dead, Dying or Diseased, or Fuelwood (Notice, Notice of Exemption):

1. This notice must be submitted to and received by CAL FIRE at one of the offices listed below prior to the commencement of timber operations.
2. 14 CCR § 1038(b) places certain limits on the harvesting of Christmas trees, dead, dying and diseased trees, and fuelwood or split products. These limits need to be examined to assure compliance.
3. Timber operations conducted under this notice shall comply with all operational provisions of the Forest Practice Act and District Forest Practice Rules applicable to "Timber Harvest Plan," "THP," and "plan." The requirements to submit a completion and stocking report normally do not apply. The requirements for environmental review under the California Environmental Quality Act (See 14 CCR § 15300.1) also do not apply.
4. There are special requirements for timber operations conducted in Coastal Commission Special Treatment Areas, the Tahoe Regional Planning Agency area, and in counties with special rules adopted by the Board of Forestry and Fire Protection. These rules should be reviewed prior to submitting this notice to CAL FIRE.
5. This Notice of Exemption is valid for one year from the date of receipt by CAL FIRE.
6. A timber operator with a valid state license must be designated upon submission of this notice.

The following suggestions may help ensure your compliance with the Forest Practice Rules:

1. Timber owners, timberland owners and timber operators should obtain and review copies of the Forest Practice Rules pertaining to the Notice of Exemption. Copies may be obtained from BARCLAYS LAW PUBLISHERS, P.O. BOX 3066, SO. SAN FRANCISCO, CA. 94080. or from CAL FIRE, Forest Practice Section, P.O. BOX 944246, Sacramento, CA 94244-2460; or from CAL FIRE's Web Page on the Internet at <http://www.fire.ca.gov>.
2. Contact the nearest CAL FIRE office listed below for questions regarding the use of this notice.

FILE THIS NOTICE WITH THE CAL FIRE OFFICE BELOW FOR THE COUNTY IN WHICH THE OPERATION WILL OCCUR:

Alameda, Colusa, Contra Costa, Del Norte Humboldt, Lake, Marin, Mendocino, Napa,
San Mateo, Santa Clara, Santa Cruz, Solano, Sonoma, western Trinity and Yolo Counties.

=> Forest Practice Program Manager
=> CAL FIRE
135 Ridgway Avenue
Santa Rosa, CA 95401

Butte, Glenn, Lassen, Modoc, Nevada, Placer, Plumas, Shasta,
Sierra, Siskiyou, Sutter, Tehama, eastern Trinity and Yuba Counties.

=> Forest Practice Program Manager
=> CAL FIRE
6105 Airport Road
Redding, CA 96002

Alpine, Amador, Calaveras, El Dorado, Fresno, Imperial, Inyo, Kern, Los Angeles,
Madera, Mariposa, Merced, Mono, Monterey, Orange, Riverside, San Benito, San Bernardino,
San Diego, San Luis Obispo, Santa Barbara, Stanislaus, Tuolumne, Tulare, and Ventura Counties.

=> Forest Practice Program Manager
=> CAL FIRE
=> 1234 East Shaw Avenue
Fresno, CA 93710

SIGNATURE OF THE TIMBER OWNER OR AGENT THEREOF: _____

Date: 1/17/2012

4. Printed Name: Benjamin C. Rowe

Title: LDSF Assistant Manger

Address 875 Cypress Ave.

City Redding

State CA

Zip 96001

Phone 530-225-2506



State of California
The Resources Agency
Board of Forestry and Fire Protection

NOTICE OF DETERMINATION

To: Office of Planning and Research
State Clearinghouse
1400 Tenth Street, Room 121
Sacramento, CA 95814

From: California Board of Forestry and Fire Protection
P.O. Box 944246
Sacramento, CA 94244-2460

Contact Person : George Gentry, Executive Officer
Phone Number: 916-653-8007
Email Address: george.gentry@fire.ca.gov

SUBJECT: Filing of Notice of Determination in compliance with Section 21108 and 21152 of the Public Resources Code.

State Clearinghouse #: SCH#2008062009

Project Title: Draft Mitigated Negative Declaration for La Tour Demonstration State Forest Management Plan Update

County of Project: Shasta County

Project Location: La Tour Demonstration State Forest, Shasta County, approximately 11 miles east of the town of Whitmore. Legal description: Township 33N, R3E, Section 31; Township 32N, Range 2E, Sections 1, 2, 3, 10, 11, 12, 13, 14, 15, 22, 23, 24; Township 32N, Range 3E, Sections 6, 7, 17, 18, MDBM.

Project Description: Revision of Management Plan for La Tour Demonstration State Forest, a state owned property managed by the California Department of Forestry & Fire Protection. The property is managed for a variety of benefits, including research and demonstration of forest management techniques, public recreation, watershed improvement, fisheries and wildlife.

This is to advise that the California Board of Forestry and Fire Protection has approved the above-described


[☒ Lead Agency ☐ Responsible Agency]

project on August 6, 2008 and has made the following determinations regarding the above-described project:


1. The project [☐ will ☒ will not] have a significant effect on the environment.
2. ☐ An Environmental Impact Report was prepared for this project pursuant to the provisions of CEQA.
☒ A Negative Declaration was prepared for this project pursuant to the provisions of CEQA.
3. Mitigation Measures [☒ were ☐ were not] made a condition of the approval of the project.
4. A statement of Overriding Considerations [☐ was ☒ was not] adopted for this project.
5. Findings [☐ were ☒ were not] made pursuant to the provisions of CEQA.

This is to certify that the record of project approval is available to the General Public at:

Board of Forestry and Fire Protection
1416 9th Street, Room 1506-14
P.O. Box 944246
Sacramento, CA 94244-2460


George D. Gentry, Executive Officer
Board of Forestry and Fire Protection

Date



RECEIVED

AUG 12 2008

STATE CLEARING HOUSE

Date received for filing and posting at OPR:

Mitigation Monitoring and Reporting Plan (MMRP)
for the
LaTour Demonstration State Forest 2008 Management Plan Update
Initial Study/Mitigated Negative Declaration
State Clearinghouse # 2008062009
Shasta County, California

In accordance with CEQA Guidelines Section 15074(d), when adopting a mitigated negative declaration, the lead agency will adopt a Mitigation Monitoring and Reporting Plan (MMRP) that ensures compliance with mitigation measures required for project approval. The Board of Forestry and Fire Protection (Board) is the lead agency for the above-listed project and has developed this MMRP as a part of the final Initial Study/Mitigated Negative Declaration (IS/MND) supporting the project.

This MMRP accomplishes the following:

- 1) Lists the mitigation measures developed in the IS/MND which were designed to reduce environmental impacts to a less-than-significant level.
- 2) Identifies the party responsible for implementing the mitigation measure.
- 3) Defines when the mitigation measure must be implemented.
- 4) Identifies which party or public agency is responsible for ensuring compliance with the measure.

One of the findings of the IS/MND for the 2008 LaTour DSF Management Plan Update was that mitigation is required to reduce potentially significant impacts related to Hazards and Hazardous Materials. Potential significant impacts could occur by accidental spilling of the material.

1) Mitigation Measures to Avoid Accidental Spilling

Mitigation Measure 1: To insure that all hazardous materials are properly used, stored and transported, Material Safety Data Sheets (MSDS), material labels, and any additional handling and emergency instruction of the materials are kept on file at LaTour Demonstration State Forest (LDSF) Headquarters.

Mitigation Measure 2: Any state employee handling these materials are made aware of the potential hazards, given proper training and instruction, and also made aware of the location of the MSDS, and any other documentation for the material.

Mitigation Measure 3: All contractors used in the application or use of these hazardous materials shall have the appropriate licenses and be able to read and understand the MSDS, labels, appropriate recommendations and application instructions.

Mitigation Measure 4: The storage of potentially hazardous materials on LDSF is in accordance to the MSDS and any buildings that are used for storage will display appropriate placards.

Implementation of these mitigation measures will reduce the environmental impacts of the proposed project to a less-than-significant level.

2) Responsible Party for Implementing Mitigation Measures

CAL FIRE.

3) Schedule

Continuously during periods when potentially hazardous materials are being used.

4) Verification of Compliance

Monitoring Party: CAL FIRE.

Initials: BB

Date: 8-20-08

The Board of Forestry and Fire Protection hereby adopts this MMRP:

George Gentry 8-19-08
George Gentry Date

RECEIVED

AUG 31 2009

FOR ADMIN. USE ONLY
Amendments-date & S or MTIMBER HARVESTING PLAN
STATE OF CALIFORNIA
DEPARTMENT OF FORESTRY
AND FIRE PROTECTION
RM-63 (02-03)

FOR ADMIN. USE ONLY

THP No **2-09-059-SHA** (A) 5Dates Rec'd **AUG 31 2009**Date Filed **SEP 10 2009**Date Approved **NOV 12 2009**Date Expires **NOV 11 2012**

Extensions 1) [] 2) []

1. IGU 7. NSO
 2. FGI 8. Buck Butte
 3. WQ5 9. CGS
 4. LNF 10. _____
 5. SHW-PW 11. _____
 6. RT 12. _____

THP Name: Buck Butte

(In the CDF FPS, this is "THP Description")

If this is a Modified THP, check box: []

This Timber Harvesting Plan (THP) form, when properly completed, is designed to comply with the Forest Practice Act (FPA) and Board of Forestry and Fire Protection rules. See separate instructions for information on completing this form. NOTE: The form must be printed legibly in ink or typewritten. The THP is divided into six sections. If more space is necessary to answer a question, continue the answer at the end of the appropriate section of your THP. If writing an electronic version, insert additional space for your answer. Please distinguish answers from questions by *font change* bold or underline.

SECTION I - GENERAL INFORMATION

This THP conforms to my/our plan and upon approval, I/we agree to conduct harvesting in accordance therewith. Consent is hereby given to the Director of Forestry and Fire Protection, and his or her agents and employees, to enter the premises to inspect timber operations for compliance with the Forest Practice Act and Forest Practice Rules.

1. TIMBER OWNER(S) OF RECORD: Name: **California Department of Forestry and Fire Protection**

Address **875 Cypress Avenue**City **Redding** State **CA** Zip **96001** Phone **(530) 225-2505**Signature Bruce W. BeattyDate **8-26-09**

NOTE: The timber owner is responsible for payment of a yield tax. Timber Yield Tax information may be obtained at the Timber Tax Section, MIC: 60, State Board of Equalization, P.O. Box 942879, Sacramento, California 94279-0060; phone 1-800-400-7115; BOE Web Page at <http://www.boe.ca.gov>.

2. TIMBERLAND OWNER(S) OF RECORD: Name: **California Department of Forestry and Fire Protection**

Address **875 Cypress Avenue**City **Redding** State **CA** Zip **96001** Phone **(530) 225-2505**Signature Bruce W. BeattyDate **8-26-09**

TIMBERLAND OWNER(S) OF RECORD: **Brooks Walker et al. C/O W. M. Beatty & Associates (Water drafting only)**

Address: **P.O. Box 990898**City **Redding** State **CA** Zip **96099-0898** Phone **(530) 243-2783**Signature: **See attached letter Section V**

Date: _____

TIMBERLAND OWNER(S) OF RECORD: Carl J. & Jo Ann Davis (Water drafting only)

Address: P.O. Box 142

City Whitmore State CA Zip 96069 Phone none

Signature: See attached letter Section V Date: _____

3. LICENSED TIMBER OPERATOR(S): Name **California Department of Forestry and Fire Protection** Lic. No. C-1275
(If unknown, so state. You must notify CDF of LTO prior to start of operations)

Address **875 Cypress Avenue**

City **Redding** State **CA** Zip **96001** Phone **(530) 225-2505**

Signature *Michael Beck* Date 8-26-09

4. PLAN SUBMITTER(S): Name: **California Department of Forestry and Fire Protection**

Address **875 Cypress Avenue**

City **Redding** State **CA** Zip **96001** Phone **(530) 225-2505**

(Submitter must be from 1, 2, or 3 above. He/she must sign below. Ref. Title 14 CCR 1032.7 (a))

Signature *Michael Beck* Date 8-26-09

5. a. List person to contact on-site who is responsible for the conduct of the operation. If unknown, so state and name must be provided for inclusion in the THP prior to start of timber operations.

Name **The Plan Submitter or designated RPF will notify CAL FIRE of responsible person prior to start of operations.**

Address

City State Zip Phone

- b. ☒ Yes ☐ No Will the timber operator be employed for the construction and maintenance of roads and landings during conduct of timber operations? If no, who is responsible?

- c. Who is responsible for erosion control maintenance after timber operations have ceased and until certification of the Work Completion Report? If not the LTO, then a written agreement must be provided per 14 CCR 1050 (c).

The Licensed Timber Operator. Pursuant to 14 CCR 936.9(p), "The erosion control maintenance period on permanent and seasonal roads and associated landings that are not abandoned in accordance with 14 CCR 923.8 shall be three years."

6. a. Expected date of commencement of timber operations:

☒ date of THP conformance, or ☐ (date)

- b. Expected date of completion of timber operations:

☒ 3 years from date of THP conformance, or ☐ (date)

7. The timber operation will occur within the:

- ☐ COAST FOREST DISTRICT
☐ Southern Subdistrict of the Coast F. D.

- ☐ The Tahoe Regional Planning Authority Jurisdiction
☐ A County with Special Regulations, identify:

- ☐ SOUTHERN FOREST DISTRICT
☐ High use subdistrict of the Southern F. D.

- ☐ Coastal Zone, no Special Treatment Area
☐ Special Treatment Area(s), type and identify
☐ Other

☒ NORTHERN FOREST DISTRICT

8. Location of the timber operation by legal description: covered by USGS 7.5 minute Quad. *Viola & Jacks Backbone CA 1995*
Base and Meridian: ☒ Mount Diablo ☐ Humboldt ☐ San Bernardino

Section	Township	Range	Acreage	County	Assessor's Parcel Number (Optional)
13	32N	2E	16	Shasta	
24	32N	2E	79	Shasta	
17	32N	3E	109	Shasta	
18	32N	3E	233	Shasta	

TOTAL ACREAGE 437 (Logging Area Only)

Planning Watershed: CALWATER Version, Identification Number, and Name

Version 2.2 Cal Water Planning Watersheds	
Name	Number
Upper Battle Creek	5507.120104
Beal	5507.310103

USGS 7.5" Quadrangle Names: *Viola & Jack's Backbone.1995*

9. ☐ Yes ☒ No Has a Timberland Conversion been submitted? If yes, list expected approval date or permit number and expiration date if already approved.

10. ☐ Yes ☒ No Is there an approved Sustained Yield Plan for this property? Number Date app.

☐ Yes ☒ No Has a Sustained Yield Plan been submitted but not approved? Number Date sub.

11. ☐ Yes ☒ No Is there a THP or NTMP on file with CDF for any portion of the plan area for which a Report of Satisfactory Stocking has not been issued by CDF?
If yes, identify the THP or NTMP number(s):

☐ Yes ☒ No Is there a contiguous even aged unit with regeneration less than five years old or less than five feet tall? If yes, explain. Ref. Title 14 CCR 913.1 (933.1, 953.1) (a)(4).

12. ☒ Yes ☐ No Is a Notice of Intent necessary for this THP?

☒ Yes ☐ No If yes, was the Notice of Intent posted as required by 14 CCR 1032.7 (g)?

13. RPF preparing the THP: Name **Gabriel V. Schultz** RPF Number **2749**

Address **875 Cypress Avenue**

City **Redding** State **CA** Zip **96001** Phone **(530) 225-2506**

a. ☐ Yes ☒ No I have notified the plan submitter(s), in writing, of their responsibilities pursuant to 14 CCR 1035 of the Forest Practice Rules.

☐ Yes ☒ No I have notified the timber owner and the timberland owner of their responsibilities for compliance with the Forest Practice Act and rules, specifically the stocking requirements of the rules and the maintenance of erosion control structures of the rules.

The timberland is owned by the California Department of Forestry and Fire Protection and managed by the LaTour Demonstration State Forest (LDSF). Mr. Bruce Beck is the manager of LDSF and is the Plan Submitter.

- b. ☒ Yes ☐ No I will provide the timber operator with a copy of the portions of the approved THP as listed in 14 CCR 1035 (f). If "no", who will provide the LTO a copy of the approved THP?

I or my supervised designee will meet with the LTO prior to commencement of operations to advise of sensitive conditions and provisions of the plan pursuant to 14 CCR 1035.2.

- c. I have the following authority and responsibilities for preparation and administration of the THP and timber operation. (Include both work completed and work remaining to be done):

I am responsible for the preparation of the THP including layout, flagging of WLPZ's, designation of timber to be harvested or retained and any additional work deemed necessary for plan approval. Additionally it is my responsibility to administer the operations described in the THP and explain to the LTO his responsibilities to ensure conformance with the requirements of the plan and the Forest Practice Act and Rules.

I will be present, or ensure that that my designee is present, on the logging area at a sufficient frequency to know the progress of operations and to advise the LTO and timberland owner, but not less than once during the life of the plan.

I will immediately furnish written notification to the LTO, the plan submitter, and the Department of a decision to withdraw professional services from the plan.

- d. Additional required work requiring an RPF, which I do not have the authority or responsibility to perform:

None


- e. After considering the rules of the Board of Forestry and Fire Protection and the mitigation measures incorporated in this THP, I have determined that the timber operation:

☐ will have a significant adverse impact on the environment. (Statement of reasons for overriding considerations contained in Section III).

☒ will not have a significant adverse impact on the environment.

Registered Professional Forester: I certify that I, or my supervised designee, personally inspected the THP area, and this plan complies with the Forest Practice Act, the Forest Practice Rules and the Professional Foresters Law. If this is a Modified THP, I also, certify that: 1) the conditions or facts stated in 14 CCR 1051 (a) (1) - (16) exist on the THP area at the time of submission, preparation, mitigation, and analysis of the THP and no identified potential significant effects remain undisclosed; and 2) I, or my supervised designee, will meet with the LTO at the THP site, before timber operations commence, to review and discuss the contents and implementation of the Modified THP.

Signature



Date

8/25/09

SECTION II - PLAN OF TIMBER OPERATIONS

NOTE: If a provision of this THP is proposed that is different than the standard rule, the explanation and justification should normally be included in Section III unless it is clearer and better understood as part of Section II.

14. a. Check the Silvicultural methods or treatments allowed by the rules that are to be applied under this THP. Specify the option chosen to demonstrate Maximum Sustained Production (MSP) according to 14 CCR 913 (933, 953) .11. If more than one method or treatment will be used show boundaries on map and list approximate acreage for each.

<input type="checkbox"/> Clearcutting	ac.	<input type="checkbox"/> Shelterwood Prep. Step	ac.	<input type="checkbox"/> Seed Tree Seed Step	ac.
		<input type="checkbox"/> Shelterwood Seed Step	ac.	<input type="checkbox"/> Seed Tree Removal Step	ac.
		<input type="checkbox"/> Shelterwood Removal Step	ac.		
<input checked="" type="checkbox"/> Selection	320 ac.	<input type="checkbox"/> Group Selection	ac.	<input type="checkbox"/> Transition	ac.
<input type="checkbox"/> Commercial Thinning	ac.	<input checked="" type="checkbox"/> Road Right of Way	1 ac.	<input checked="" type="checkbox"/> Sanitation Salvage	101 ac,
<input type="checkbox"/> Special Treatment Area	ac.	<input type="checkbox"/> Rehab. of Understocked Area	ac.	<input type="checkbox"/> Fuelbreak	ac.
<input type="checkbox"/> Alternative	ac.	<input type="checkbox"/> Conversion	ac.	<input checked="" type="checkbox"/> Non-Timberland Area	15 ac.

Total acreage 437 ac.: Explain if total is different from that in 8. MSP option chosen: (a) [X] (b) [] (c) []

- b. If Selection, Group Selection, Commercial Thinning, Sanitation Salvage or Alternative methods are selected the post harvest stocking levels (differentiated by site if applicable) must be stated. Note mapping requirements of 1034 (x) (12).

This THP is Under the Option "A" filed under THP 2-02-187 SHA.

Selection: Immediately upon completion of operations the area shall meet the stocking standards of CCR 933.2(a)(2)(A)(2), 75 square feet per acre of basal area shall be retained for Site III lands. The residual stand shall contain sufficient 18 inch DBH trees to meet at least the 15 sq/ft basal area, size, and phenotypic quality of tree requirement specified under the seed tree method as specified in CCR 933.1(c)(1)(A)(1.). Post harvest stocking will be met with group A species.

Sanitation Salvage: Immediately upon completion of operations the area shall meet the stocking standards of CCR 932.7(b), 300 point count for Site III lands.

Biomass harvesting may be utilized throughout the plan area. The biomass harvest will select trees not merchantable as sawlogs (trees less than 10 inches DBH) to reduce stocking levels and accelerate individual tree growth in the residual stand. Trees harvested for biomass will not be marked.

- c. ☐ Yes ☒ No Will evenage regeneration step units be larger than those specified in the rules (20 acres tractor, 30 acres cable)? If yes, provide substantial evidence that the THP contains measures to accomplish any of subsections (A) - (E) of 14 CCR 913 (933, 953) .1 (a) (2) in Section III of the THP. List below any instructions to the LTO necessary to meet (A) - (E) not found elsewhere in the THP. These units must be designated on map and listed by size.

- d. Trees to be harvested or retained must be marked by or marked under the supervision of the RPF. Specify how the trees will be marked and whether harvested or retained.

All harvest trees 10 inches and greater DBH shall be marked in Orange paint with a horizontal stripe near breast height and a mark at the stump. A sample area will be marked prior to the preharvest inspection.

- [X] Yes [] No Is a waiver of marking by the RPF requirement requested? If yes, how will LTO determine which trees will be harvested or retained? If yes and more than one silvicultural method, or Group Selection is to be used, how will LTO determine boundaries of different methods or groups?

CAL FIRE requests a waiver of marking associated with proposed biomass harvesting throughout the plan area. The biomass harvest will select trees not merchantable as sawlogs (trees less than 10 inches DBH) to reduce stocking levels and accelerate individual tree growth in the residual stand. Directions for LTO are as follows: 1) No saw logs are to be harvested. 2) Leave healthy clumps of 8 inch DBH and smaller trees that cannot be thinned without damaging the residual saplings. 3) In heavily stocked areas, harvest trees in

suppressed crown positions that are less than 10 inches DBH. 4) Harvest trees that show significant signs of mistletoe, insect attack, disease, or mechanical damage.

e. Forest products to be harvested:

Sawlogs, cull logs, chips, pulp logs, and fuel-wood, poles.

- f. ☐ Yes ☒ No Are group B species proposed for management?
☐ Yes ☒ No Are group B or non-indigenous A species to be used to meet stocking standards?
☐ Yes ☒ No Will group B species need to be reduced to maintain relative site occupancy of A species?

If any answer is yes, list the species, describe treatment, and provide the LTO with necessary felling and slash treatment guidance. Explain who is responsible and what additional follow-up measures of manual treatment or herbicide treatment are to be expected to maintain relative site occupancy of A species. Explain when a licensed Pest Control Advisor shall be involved in this process.

g. Other instructions to LTO concerning felling operations

Check all road location flagging, watercourse flagging, WLPZ boundary flagging, EEZ and ELZ flagging, and skid trail flagging prior to the commencement of any felling operations. Have the responsible RPF or supervised designee replace any flagging that is incomplete or unclear.

Trees designated for removal within the EEZ or ELZ shall be directionally felled towards the perimeter and away from the protection zone and endlined, so as to keep heavy equipment out of the protection zone. In the ELZ of Class III watercourses, trees may be felled bridging the watercourse and endlined from outside the ELZ. The purpose of this measure is to allow for trees that if not directionally felled across the ELZ would fall into the ELZ or damage the residual stand.

- h. ☐ Yes ☒ No Will artificial regeneration be required to meet stocking standards?
i. ☐ Yes ☒ No Will site preparation be used to meet stocking standards? If yes, provide the information required for a site preparation addendum, as per 14 CCR 915.4 (935.4, 955.4).
j. If the rehabilitation method is chosen provide a regeneration plan as required by 14 CCR 913 (933, 953) .4 (b).

PESTS

15. a. ☐ Yes ☒ No Is this THP within an area that the Board of Forestry and Fire Protection has declared a Zone of Infestation or Infection, pursuant to PRC 4712 - 4718? If yes, identify feasible measures being taken to mitigate adverse infestation or infection impacts from the timber operation. See 14 CCR 917 (937, 957) .9 (a).
b. ☐ Yes ☒ No If outside a declared zone, are there any insect, disease or pest problems of significance in the THP area? If yes, describe the proposed measures to improve the health, vigor, and productivity of the stand(s).

HARVESTING PRACTICES

16. Indicate type of yarding system and equipment to be used:

- | GROUND BASED* | | CABLE | SPECIAL |
|---|--|--|--|
| a. <input checked="" type="checkbox"/> Tractor, including end/long lining | | d. <input type="checkbox"/> Cable, ground leadg. | g. <input type="checkbox"/> Animal |
| b. <input checked="" type="checkbox"/> Rubber tired skidder, Forwarder | | e. <input type="checkbox"/> Cable, high lead | h. <input type="checkbox"/> Helicopter |
| c. <input checked="" type="checkbox"/> Feller buncher | | f. <input type="checkbox"/> Cable, Skyline | i. <input type="checkbox"/> Other |
- * All tractor operations restrictions apply to ground based equipment.

17. Erosion Hazard Rating: Indicate Erosion Hazard Ratings present on THP. (Must match EHR worksheets)

☐ Low

☒ Moderate

☒ High

☐ Extreme

If more than one rating is checked, areas must be delineated on map down to 20 acres in size (10 acres for high and Extreme EHRs in the Coast District).

18. Soil Stabilization: In addition to the standard waterbreak requirements describe soil stabilization measures or additional erosion control measures to be implemented and the location of their application. See requirements of 14 CCR 916.7 (936.7, 956.7), and 923.2 (943.2, 963.2) (m), and 923.5 (943.5, 963.5) (f).

1. Stabilization measures shall be selected that will prevent significant soil loss or sediment transport into Class I, Class II and Class III waters and may include, but need not be limited to, mulching, rip-rapping, grass seeding, or chemical stabilizers. Preference to which stabilization measure to be used, if the need occurs, shall be based upon on site conditions and the availability of treatment materials. If appropriate for the site, mulching will be the method of choice.
2. Mulch shall consist of straw or other material that is less than 3 inches in diameter (i.e. logging slash or brush). Straw mulch shall cover > 90% of the exposed area at an applied depth of > 2 inches. If logging slash or brush is used for mulch it shall be compacted by equipment and cover 90% of the exposed area.
3. Where the undisturbed natural ground cover cannot effectively protect beneficial uses of water from timber operations, the ground shall be treated by measures including, but not limited to, seeding, mulching, or replanting, in order to retain and improve its natural ability to filter sediment, minimize soil erosion, and stabilize banks of watercourses and lakes. Treatments shall meet the standards described in item 1 and 2 above.
4. Waterbreaks shall be constructed as soon as practical upon conclusion of use of skid trails, roads, and landings, which do not have permanent and adequate drainage facilities, or drainage structures.

The maximum distance between waterbreaks on all roads and skid trails within the THP area shall not exceed the following standards except where natural drainage will occur, i.e., low spots, draws, and depressions. In these areas, any berm on the downhill side of the road or skid trail shall be removed to allow drainage and a drainage facility shall not be constructed.

Road or Trail Gradient (%)	10 or Less	11-25	26-50	> 50
Moderate EHR	200 ft.	150 ft.	100 ft.	75 ft.
High EHR	150 ft.	100 ft.	75 ft.	50 ft.

Waterbreaks shall be cut diagonally a minimum of 6 inches into the firm roadbed or skid trail surface and shall have a continuous firm embankment of at least 6 inches in height immediately adjacent to the lower edge of the waterbreak cut.

Waterbreaks shall be located to allow water to be discharged into some form of vegetative cover, duff, slash, rocks, or less erodible material wherever practical, and shall be constructed to provide for unrestricted discharge at the lower end of the waterbreak so that water will be discharged and spread in such a manner that erosion and sediment transport shall be minimized. Where waterbreaks cannot effectively disperse surface runoff, including where waterbreaks on roads and skid trails cause surface runoff to be concentrated on down-slopes, roads, or skid trails, other erosion control methods, as described in 1 above, shall be installed as needed to comply with 14 CCR 934.

5. Soil stabilization of logging roads - Permanent drainage facilities (rolling dips or drivable waterbars) shall be constructed on appurtenant seasonal roads used for this operation. These drainage facilities shall be constructed prior to the completion of hauling on all road segments where practical. Where pre-haul drainage facilities are not feasible, the standard waterbreak construction and spacing specifications will be used.
6. All outside berms along roads created from grading or truck traffic during operations shall be pulled back onto the road surface prior to completion of use and final road grading. Where feasible, and to the extent that can reasonably be done with minor road dressing and grading, existing side-hill roads shall be outsloped.
7. The traveled surface of logging roads shall be treated to prevent waterborne transport of sediment and concentration of runoff that results from timber operations. Consequently, during timber operations, road

running surfaces in the logging area shall be treated as necessary to prevent excessive loss of road surface materials by watering.

8. The erosion control maintenance period on permanent and seasonal roads and associated landings that are not abandoned in accordance with 14 CCR 943.8 shall be three years.
9. Pursuant to 14 CCR 936.9(n), exposed areas, >100 square feet, approaches to watercourse crossings between the drainage facilities closest the watercourse, and road cuts and fills within the WLPZ, and within any EEZ or ELZ designated for watercourse or lake protection, shall be treated to stabilize soils, minimize soil erosion, and prevent the discharge of sediment into waters in amounts deleterious to the beneficial uses of water. Treatments shall meet the standards described in item 1 and 2 above.
10. Timing requirements for all erosion prevention activities.

1. For areas disturbed from May 1 through October 15, treatment shall be completed prior to the start of any rain that causes overland flow across or along the disturbed surface.
2. For areas disturbed from October 16 through April 30, treatment shall be completed prior to any day for which a chance of rain of 30 percent or greater is forecast by the National Weather Service or within 10 days, whichever is earlier.
3. All tractor roads shall have drainage facilities installed as soon as practical following yarding and any day with a National Weather Service forecast of chance of rain 30 percent or more, a flash flood warning, or a flash food watch as specified in CCR 14 936.9(m).

19. ☐ Yes ☒ No Are tractor or skidder constructed layouts to be used? If yes, specify the location and extent of use:

20. ☐ Yes ☒ No Will ground based equipment be used within the area(s) designated for cable yarding? If yes, specify the location and for what purpose the equipment will be used. See 14 CCR 934.3 (e).

21. Within the THP area will ground based equipment be used on:

- a. ☐ Yes ☒ No Unstable soils or slide areas? Only allowed if unavoidable.
- b. ☐ Yes ☒ No Slopes over 65%?
- c. ☒ Yes ☐ No Slopes over 50% with high or extreme EHR?
- d. ☐ Yes ☒ No Slopes between 50% and 65% with moderate EHR where heavy equipment use will not be restricted to the limits described in 14 CCR 914 (934, 954) .2 (f) (2) (i) or (ii)?
- e. ☐ Yes ☒ No Slopes over 50% which lead without flattening to sufficiently dissipate water flow and trap sediment before it reaches a watercourse or lake?

If a. is yes, provide site specific measures to minimize effect of operations on slope stability below. Provide explanation and justification in section III as required per 14 CCR 914 (934, 954) .2 (d). CDF requests the RPF consider flagging tractor road locations if "a." is yes.

If b., c., d. or e. is yes:

- 1) the location of tractor roads must be flagged on the ground prior to the PHI or start of operations if a PHI is not required, and
- 2) you must clearly explain the proposed exception and justify why the standard rule is not feasible or would not comply with 14 CCR 914 (934, 954).

The location of heavy equipment operation on unstable areas or any use beyond the limitations of the standard rules must be shown on the map. List specific instructions to the LTO below.

c. Slopes over 50% with high or extreme EHR:

Operations shall be restricted to existing tractor roads that do not require reconstruction or designated skid trails (flagged and mapped) on slopes over 50% with a High EHR. See THP map for location of these skid trails. See Section III for explanation and justification. See Section III for additional discussion.

22. ☐ Yes ☒ No Are any alternative practices to the standard harvesting or erosion control rules proposed for this plan? If yes, provide all the information as required by 14 CCR 914 (934, 954) .9 in Section III. List specific instructions to the LTO below.

WINTER OPERATIONS

23. a. ☒ Yes ☐ No Will timber operations occur during the winter period? If yes, complete "b, c, or d." State in space provided if exempt because yarding method will be cable, helicopter, or balloon.
- b. ☐ Yes ☒ No Will mechanical site preparation be conducted during the winter period? If yes, complete "d".
- c. ☐ I choose the in-lieu option as allowed in 14 CCR 914 (934, 954) .7 (c). Specify below the procedures listed in subsections (1) and (2), and list the site specific measures for operations in the WLPZ and unstable areas as required by subsection (3), if there will be no winter operations in these areas, so state.
- d. ☒ I choose to prepare a winter operating plan per 14 CCR 914 (934, 954) .7 (b).

The following Winter Operation Plan is for timber operations taking place between October 15 to May 1, as required by 14 CCR 936.9(k). Winter Period is defined in 14 CCR 895.1 as the period between November 15 to April 1. No operations shall occur for the remainder of the winter period after the first shut down due to the restrictions under item 10 below. The harvesting activities that may occur during the winter operational period include but not limited to felling timber, yarding with ground-based equipment, decking logs and hauling logs. The use of landing L2, Road construction and abandonment shall not occur during the Winter Period (Nov 15-April1).

WINTER OPERATING PLAN

1. The erosion hazard rating in the THP is moderate and high.
2. No mechanical site preparation is proposed during the Winter Period.
3. The yarding system is ground based.
4. The operational period may be at any time between October 15 to May 1 when dry, rainless, or hard frozen conditions exist and when soils are not saturated. Use of heavy equipment or trucks on roads and landings shall be limited to a stable operating surface. Refer to "Definitions" below for the definitions of hard frozen conditions, stable operating surface and saturated soil conditions.
5. Erosion control facilities timing. This Winter Operating Plan shall be effective from October 15 to May 1. The installation of erosion controls utilizing drainage facilities is required from October 15 to May 1 on all seasonal roads, constructed skid trails and tractor roads prior to sunset if the National Weather Service forecast is a "chance" (30% or more) of rain within the next 24 hours, a flash flood warning or flash flood watch within the next 24 hours and prior to any weekend shut down periods.
6. Precipitation - Consideration in form of rain or snow. Precipitation in the THP area is primarily in the form of snow between October 31 and April 1. Spring rains usually fall onto a substantial snow pack and snow persists until middle to late May with drifts present until mid June. No hauling or ground based operations shall occur when saturated soil conditions are present. Drainage facilities shall be kept in effective condition throughout operations conducted during the winter period.
7. Ground conditions (soil moisture condition, frozen). Use of logging roads, tractor roads or landings shall not take place at any location where saturated soil conditions exist, where a stable logging road or landing operating surface does not exist, or when visibly turbid water from the road, landing, or skid trail or inside ditch may reach a watercourse or lake.
8. Silvicultural system-ground cover. Healthy regeneration, slash, needle cast and existing ground cover (such as *Arctostaphylos petula*.) will ensure adequate ground cover to dissipate rainfall impact and runoff.
9. Operations within the WLPZ. Designated harvest trees within the WLPZ of Class II watercourses are to be felled toward the perimeter of the zone and endlined out. All watercourse crossing facilities not constructed to permanent crossing standards shall be removed before November 15.
10. Equipment use limitations. No ground-based operations shall occur during locally saturated soil conditions and shall be limited to stable operating surface. Refer to "Definitions" below for the definitions of hard frozen conditions, stable operating surface and saturated soil conditions.
11. Known Unstable Areas. No known unstable areas are within the plan area.

Definitions (14 CCR 895.1):

Low Antecedent Soil Wetness is defined as conditions not meeting the threshold of saturated soil conditions.

Hard Frozen Conditions means those frozen soil conditions where loaded or unloaded vehicles can travel

sinking into the road surfaces to a depth of more than six inches over a distance of more than 25 feet.

Saturated Soil Conditions means that site conditions are sufficiently wet that timber operations displace soils in yarding or mechanical site preparation areas or displace road and landing surface materials in amounts sufficient to cause a turbidity increase in drainage facilities that discharge into Class I, II, III, or IV waters, or in downstream Class I, II, III, or IV waters that is visible or would violate applicable water quality requirements.

In yarding and site preparation areas, this condition may be evidenced by: a) reduced traction by equipment as indicated by spinning or churning of wheels or tracks in excess of normal performance, b) inadequate traction without blading wet soil, c) soil displacement in amounts that cause visible increase in turbidity of the downstream waters in a receiving Class I, II, III, or IV waters, or in amounts sufficient to cause a turbidity increase in drainage facilities that discharge into Class I, II, III, or IV waters, or d) creation of ruts greater than would be normal following a light rainfall.

On logging roads and landing surfaces, this condition may be evidenced by a) reduced traction by equipment as indicated by spinning or churning of wheels or tracks in excess of normal performance, b) inadequate traction without blading wet soil, c) soil displacement in amounts that cause visible increase in turbidity of the downstream waters in receiving Class I, II, III, or IV waters, or in amounts sufficient to cause a turbidity increase in drainage facilities that discharge into Class I, II, III, or IV waters, d) pumping of road surface materials by traffic, or e) creation of ruts greater than would be created by traffic following normal road watering, which transports surface material to a drainage facility that discharges directly into a watercourse.

Soils or road and landing surfaces that are hard frozen are excluded from this definition.

Stable operating surface means that throughout the period of use, the operating surface of a logging road or landing does not either (1) generate waterborne sediment in amounts sufficient to cause a turbidity increase in downstream Class I, II, III, or IV waters, or in amounts sufficient to cause a turbidity increase in drainage facilities that discharge into Class I, II, III, or IV waters or, that is visible or would violate applicable water quality requirements; or (2) channel water for more than 50 feet that is discharged into Class I, II, III, or IV waters.

Winter period means the period between November 15 and April 1, except as noted under special County Rules at Title 14 CCR 925.1, 926.18, 927.1, and 965.5... (a) except as otherwise provided in the rules: (1) All waterbreaks shall be installed no later than the beginning of the winter period of the current year of timber operations. (2) Installation of drainage facilities and structures is required from October 15 to November 15 and April 1 to May 1 on all constructed skid trails and tractor roads prior to sunset if the National Weather Service forecast is a "chance" (30% or more) of rain within the next 24 hours.

ROADS AND LANDINGS

24. Will any roads be constructed? ☒ Yes ☐ No, or reconstructed? ☐ Yes ☒ No. If yes, check items "a." through "g."
Will any landings be constructed? ☒ Yes ☐ No, or reconstructed? ☐ Yes ☒ No. If yes, check items "h." through "k."

- | | |
|--|---|
| a. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | Will new or reconstructed roads be wider than single lane with turnouts? |
| b. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | Are logging roads proposed in areas of unstable soils or known slide-prone areas? |
| c. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | Will new roads exceed a grade of 15% or have pitches of up to 20% for distances greater than 500 feet? Map must identify any new or reconstructed road segments that exceed an average 15% grade for over 200 feet. |
| d. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | Are roads to be constructed or reconstructed, other than crossings, within the WLPZ of a watercourse? If yes, completion of THP Item 27 a. will satisfy required documentation. |
| e. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | Will roads be located across more than 100 feet of lineal distance on slopes over 65%, or on slopes over 50% which are within 100 feet of the boundary of a WLPZ? |
| f. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | Will any roads or watercourse crossings be abandoned? |
| g. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | Are exceptions proposed for flagging or otherwise identifying the location or roads to be constructed? |
| h. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | Will any landings exceed one half acre in size? If any landing exceeds one quarter acre in size or requires substantial excavation the location must be shown on the map. |
| i. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | Are any landings proposed in areas of unstable soils or known slide prone areas? |
| j. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | Will any landings be located on slopes over 65% or on slopes over 50% which are within 100 feet of the boundary of a WLPZ? |
| k. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | Will any landings be abandoned? |

25. If any section in "Item 24" above is answered yes, specify site-specific measures to reduce adverse impacts and list any additional or special information needed by the LTO concerning the construction, maintenance, and/or abandonment of roads or landings, as required by 14 CCR Article 12. Include required explanation and justification in THP Section III.

Road and Landing construction:

Map Point A: Approximately 800 feet of temporary road construction that will terminate with the construction of a new landing. There are no watercourse crossings, the side slope is less than 30%, the road grade averages less than 15 %, EHR is moderate, and there are no unstable areas. No segment of this road extends over 500 feet at 15% or greater in slope.

The temporary road shall be constructed as a seasonal, single lane roads with a sufficient number of turnouts for safe vehicle passage. Any tree over 12 inches d.b.h. with more than 25% of the root surface exposed by road construction, shall be felled concurrently with the timber operations. Waste organic material, such as uprooted stumps, cull logs, accumulations of limbs and branches, and unmerchantable trees, shall not be buried in road fills. The road shall be out-sloped where feasible.

Wood debris or cull logs and chunks may be placed and stabilized at the toe of fills to restrain excavated soil from moving down slope. Drainage structures or facilities shall be installed so as to minimize erosion, ensure proper functioning, and to maintain the natural drainage pattern. Drainage structures and facilities shall be of sufficient size, number and location to carry runoff water off of roadbeds, landings and fill slopes. Drainage structures and drainage facilities shall not discharge on erodible fill or other erodible material unless suitable energy dissipaters are used.

Temporary road grade has been flagged. No watercourse crossings are associated with this road. No watercourses are located near this road that may receive any runoff.

If road construction occurs after October 15, drainage structures shall be installed concurrently with the activity.

The limited construction will not significantly expand the area covered by the transportation system within the watersheds. New construction will affect less than 0.001% of the total area within the watersheds.

Upon Completion of operations, the temporary road and associated landing shall be abandoned in accordance with 14 CCR 943.8;

1. Road shall be **BLOCKED** so that standard production four wheel-drive highway vehicles cannot pass the point of closure at the time of abandonment.
2. The road surface shall be graded or shaped to provide dispersal of water flow.

WATERCOURSE AND LAKE PROTECTION ZONE (WLPZ) AND DOMESTIC WATER SUPPLY PROTECTION MEASURES

26. a. ☒ Yes ☐ No Are there any watercourse or lakes which contain Class I through IV waters on or adjacent to the plan area? If yes, list the class, WLPZ or ELZ width, and protective measures determined from Table I and/or 14 CCR 916 (936, 956) .4 (c) of the WLPZ rules for each watercourse. Specify if Class III or IV watercourses have WLPZ , ELZ or both.

Class I Watercourse

The Class I watercourse has been flagged with blue and white striped flagging. Consistent with 14 CCR 936.5 the class I watercourse has at least the minimum widths as shown in the table below.

Pursuant to 14 CCR 936.5(e) "B" ("A") WLPZ shall be clearly identified on the ground by an RPF or supervised designee, with paint, flagging, or other suitable means *prior to the preharvest inspection*. No timber is proposed for harvest within the Class I WLPZ.

Class II watercourses

The Class II watercourses have been flagged with blue and white striped flagging. Consistent with 14 CCR 936.5 all of the class II watercourses have at least the minimum widths as shown in the table below.

Pursuant to 14 CCR 936.5(e) "E", to ensure retention of shade canopy filter strip properties and the maintenance of wildlife values described in 14 CCR 936.4(b) a base mark shall be placed below the cut line of the harvest trees within the zone in advance of timber operations by an RPF or supervised designee. Additionally, pursuant to 14 CCR 936.5(e) "I" To protect water temperature, filter strip properties, upslope stability, and fish & wildlife values, at least 50% of the total canopy covering the ground shall be left in a well distributed multi-storied stand configuration

composed of a diversity of species similar to that found before the start of operations. The residual overstory canopy shall be composed of at least 25% of the existing overstory conifers. As is with class I watercourses, all class II watercourses shall comply with 14 CCR 936.3(g) recruitment of large woody debris for instream habitat shall be provided by retaining at least two living conifers per acre at least 16 inches dbh and 50ft. tall within 50 ft. Trees shall be marked prior to the PHI.

Class III watercourses

Pursuant to 14 CCR 936.4(c)(1), Class III watercourses shall have a 25-foot ELZ on slopes less than 30% and a 50-foot ELZ on slopes greater than 30%.

Class III watercourse ELZs shall be flagged with blue and white striped flagging prior to start of operations. The ELZs shall be flagged by the RPF or supervised designee. Within the ELZ of Class III watercourses, equipment shall be allowed to operate on existing roads, prepared crossings and designated tractor road crossings. At least 50% of the understory vegetation present before timber operations shall be left living and well distributed within the ELZ to maintain soil stability. Note: "ELZ" means, "Equipment Limitation Zone" and shall be defined as follows: a) all heavy equipment is to be excluded from operating within the ELZ except on existing skid trails, skid trail crossings and existing haul roads, b) approved existing skid trails and existing skid trail crossings have been identified on the ground with yellow flagging. c) Approved skid trail crossings shall only be used when dry.

Slope Class %	Width in Feet		
	Class I	Class II	Class III
<30	150	50	25
30-50	150	75	50
>50	150	100	50

Non Classified Draw

No draws, swales, or channels shall be used as skid trails. Skid trail crossings of these non-classified draws, swales, and channels shall be kept to a minimum. Existing crossings shall be used where feasible and shall be as close to a 90-degree angle as possible.

Springs and seeps

These areas include seeps and springs and shall be protected with a minimum 25 foot EEZ.

- b. ☒ Yes ☐ No Are there any watercourse crossings that require mapping per 14 CCR 1034 (x) (7)?
- c. ☐ Yes ☒ No Will tractor road watercourse crossings involve the use of a culvert? If yes state minimum diameter and length for each culvert (may be shown on map).
- d. ☐ Yes ☒ No Is this THP Review Process to be used to meet Department of Fish and Game CEQA review requirements? If yes, attach the 1603 Addendum below or at the end of this Section II; provide the background information and analysis in Section III; list instructions for LTO below for the installation, protection measures, and mitigation measures; as per THP Form Instructions or CDF Mass Mailing, 07/02/1999, "Fish and Game Code 1603 Agreements and THP Documentation".

General Watercourse Crossing Procedures

All existing culvert crossings within the plan area and appurtenant road systems have been evaluated and were found to be functioning properly outside of WC 1.

The disturbance or removal of vegetation will not exceed the minimum necessary to complete the operations as described. The channel and bank configuration of the disturbed areas will be restored to as near its natural condition as practicable.

All cleared vegetation and debris will be removed from the watercourse corridor and placed or secured where they cannot re-enter a watercourse. Large woody debris may be replaced or left in the watercourse channel.

Within the WLPZ of the Class II watercourses and within the Class III ELZs, areas of disturbed, bare mineral soil greater than 100 square feet that is exposed in conjunction with crossing construction, maintenance, repair or removal will be treated for erosion control immediately upon completion of work.

All temporary watercourse crossing shall be removed prior to October 15 of the year of operations.

Discharge of sediment will be avoided to the maximum extent practicable. In no case will the discharge of sediment result in amounts that are deleterious to fish.

If the watercourse channel has been altered during the operations, its low flow channel will be returned as nearly as possible to its natural state, including its shape and gradient.

If operations require moving equipment across a flowing watercourse, such operations will be conducted without causing a prolonged visible increase in turbidity. For repeated crossings, a bridge, culvert, or rock-lined crossing will be installed as described. Equipment may be operated in the watercourse channel of flowing watercourses only as may be necessary to construct crossings, or channel changes during the use of fords. During construction of crossings, if substantial turbidity may be transported downstream, the flow will be diverted around the work area by temporary pipe, diversion channel or pumping.

If a temporary structure is required to minimize the downstream movement of turbid or silt-laden waters, that structure will only be built from materials such as sandbags, gabions, clean gravel or other materials which will cause little or no turbidity or siltation. All remnants of any such dam or barrier will be removed upon completion of work.

When any dam or other artificial barrier is being constructed, maintained, or placed in operation, sufficient water will at all times be allowed to pass downstream to maintain aquatic life below the diversion structure.

Structures and associated materials that are not designed to withstand high seasonal flows will be removed to areas above bank full stage before such flows occur.

Asphalt or materials containing asphalt, discarded vehicle tires, and/or other petroleum products are prohibited from use or being placed where they may come into contact with flowing waters.

Debris, soil, silt, sand, bark, slash, rubbish, cement or concrete or washings thereof, oil or petroleum products or other organic or earthen material will not be allowed to enter into or placed where it may be washed by rainfall or runoff into a watercourse.

No equipment maintenance or refueling will be conducted within 100 feet any watercourse channel or lake margin.

When any dam, road, or artificial obstruction is being constructed, maintained, or placed in operation, sufficient water will at all times be allowed to pass downstream to maintain aquatic life below the work area.

Watercourse Crossing (WC) 1 shall be a rock rolling dip on a class III watercourse. The crossing is currently a 24 inch culvert. The crossing shows evidence of water flowing over the culvert and is subject to flash flows of rain on snow events. The crossing and the first 25 feet of the approaches shall be rocked with 4 inch competent rock creating a rocked ford. The rocked used within the rolling dip shall be 4 inch fractured rock and may be topped with smaller base rock for the driving surface. Rocks 12 inches and larger shall be used to reinforce the fill and prevent erosion. Smaller rocks may be used to fill in the interstices between the larger rocks. The crossing shall be installed no later than October 31. If water is present during timber operations a temporary pipe shall be installed. The pipe shall be of sufficient size to accommodate the flow of water with a minimum diameter of 4 inches.

Beaver Creek Drafting Location is currently functioning . The inlet shall be beveled.

27. Are site specific practices proposed in-lieu of the following standard WLPZ practices?

- a. ☒ Yes ☐ No Prohibition of the construction or reconstruction of roads, construction or use of tractor roads or landings in Class I, II, III, or IV watercourses, WLPZs, marshes, wet meadows, and other wet areas except as follows:
- (1) At prepared tractor road crossings.
 - (2) Crossings of Class III watercourses which are dry at time of timber operations.
 - (3) At existing road crossings.
 - (4) At new tractor and road crossings approved by Department of Fish and Game.
- b. ☐ Yes ☒ No Retention of non-commercial vegetation bordering and covering meadows and wet areas?
- c. ☐ Yes ☒ No Directional felling of trees within the WLPZ away from the watercourse or lake?
- d. ☐ Yes ☒ No Decrease of width(s) of the WLPZ(s)?
- e. ☐ Yes ☒ No Protection of watercourses which conduct class IV waters?
- f. ☐ Yes ☒ No Exclusion of heavy equipment from the WLPZ except as follows:
- (1) At prepared tractor road crossings.
 - (2) Crossings of Class III watercourses which are dry at time of timber operations.
 - (3) At existing road crossings.
 - (4) At new tractor and road crossings approved by Department of Fish and Game.
- g. ☐ Yes ☒ No Establishment of ELZ for Class III watercourses unless sideslopes are <30% and EHR is low?

- h. ☐ Yes ☒ No Retention of at least 50% of the overstory canopy in the WLPZ?
- i. ☐ Yes ☒ No Retention of at least 50% of the understory in the WLPZ?
- j. ☐ Yes ☒ No Are any additional in-lieu or any alternative practices proposed for watercourse or lake protection?

NOTE: A yes answer to any of items "a." through "j." constitutes an in-lieu practice. If any item is answered yes, refer to 14 CCR 916 (936, 956).1 and address the following for each item checked yes:

1. The RPF shall state the standard rule;
2. Explain and describe each proposed practice;
3. Explain how the proposed practice differs from the standard practice;
4. The specific location where it shall be applied, see map requirements of 14 CCR 1034 (x) (15) and (16);
5. Provide in THP Section III an explanation and justification as to how the protection provided is equal to the standard rule and provides for the protection of the beneficial uses of water, as per 14 CCR 916 (936, 956) .1 (a). Reference the in-lieu and location to the specific watercourse to which it will be applied.

Landing and Associated Skid Trails within WLPZs

There are three landings (L1, L2 & L3) and associated skid trails proposed for use that are currently within or partially within a WLPZ (Refer to In Roads and Watercourses Map). In these areas, skidders or tractors will be allowed to skid logs into the WLPZ to the landing and return on existing skid trails only. No new construction of skid trails or roads are proposed in WLPZs. Normal landing operations including limbing, bucking, sorting, and decking may occur on the landings.

The standard rule, 14 CCR 936.3(c) states that the timber operator shall not use landings or skid trails in the WLPZ unless explained and justified in the THP by the RPF, and approved by the Director. The proposed in lieu practice differs from the standard rule in that it allows limited use of designated landings and skid trails within the WLPZ.

- Only existing, pre-flagged skid trails shall be used within the WLPZ. Approved skid trails shall be flagged with yellow flagging by the RPF.
- The outside edge of the landing shall be defined by the RPF or designee with white flagging prior to operations. No operations, including decking of logs and parking equipment, shall occur beyond the flagged limits. If necessary to prevent sediment delivery to a watercourse or other wet area, brow logs will be placed between the active portion of the landing or skid trail and the watercourse.
- Existing vegetation between the outside edge of the landings (brow logs) and the watercourses shall remain undisturbed.
- No material shall be side cast off the landing or skid trail surface towards the watercourse.
- Landings and skid trails shall be stabilized as specified in Item 18 above.

Roads within WLPZ

Though not an in-lieu practice a road segment exist that is adjacent to and falls within the WLPZ of a Class II watercourses and the ELZ of Class III watercourses. This road segment is immediately south of South Cow Creek Camp Ground. This road will be used for normal vehicular traffic, and log hauling. Equipment will also be allowed to travel on these roads and perform the necessary road maintenance.

In preparing the THP this road segment was reviewed and assessed for any negative impacts to the beneficial uses of water. There are currently no apparent negative impacts and none are anticipated as a result of the proposed operations. This road segment is well established and stable, and the watercourses appear stable. In addition, there are no feasible alternative locations to construct a new road.

28. a. ☒ Yes ☐ No Are there any landowners within 1000 feet downstream of the THP boundary whose ownership adjoins or includes a class I, II, or IV watercourse(s) which receives surface drainage from the proposed timber operations? If yes, the requirements of 14 CCR 1032.10 apply. Proof of notice by letter and newspaper should be included in THP Section V. If No, "28 b." need not be answered.
- b. ☒ Yes ☐ No Is an exemption requested of the notification requirements of 14 CCR 1032.10? If yes, an explanation and justification for the exemption must appear in THP Section III. Specify if requesting an exemption from the letter, the newspaper notice or both.
- c. ☐ Yes ☒ No Was any information received on domestic water supplies that required additional mitigation beyond that required by standard Watercourse and Lake Protection rules? If yes, list site specific measures to be implemented by the LTO.

29. ☐ Yes ☒ No Is any part of the THP area within a Sensitive Watershed as designated by the Board of Forestry and Fire Protection? If yes, identify the watershed and list any special rules, operating procedures or mitigation that will be used to protect the resources identified at risk?

HAZARD REDUCTION

30. a. ☒ Yes ☐ No Are there roads or improvements which require slash treatment adjacent to them? If yes, specify the type of improvement, treatment distance, and treatment method.
- b. ☐ Yes ☒ No Are any alternatives to the rules for slash treatment along roads and within 200 feet of structures requested? If yes, RPF must explain and justify how alternative provides equal fire protection. Include a description of the alternative and where it will be utilized below.

Within 100 feet of the edge of the traveled surface of public roads, slash created and trees knocked down by timber operations shall be treated by lopping for fire hazard reduction, piling and burning, chipping, burying or removal from the zone.

31. ☒ Yes ☐ No Will piling and burning be used for hazard reduction? See 14 CCR 917.1-.11, 937.1-.10, or 957.1-.10, for specific requirements. Note: LTO is responsible for slash disposal. This responsibility cannot be transferred.

LTO is responsible for slash disposal. Any landing slash that is not spread back onto skid trails shall be piled near the center of the landing. Piles shall not exceed 50 x 50 x 20 feet with a fire line completely around the pile that has a width at least 1.5 times the height of the pile to a maximum of 30 feet. Efforts shall be made to ensure that these piles are as compact and free of soil as practical. Material shall be piled at or near its final location to minimize the amount of movement necessary and subsequent soil deposition in the piles. Slash piles created prior to September 1 of each year shall be burned that fall when safe burning conditions occur. Slash piles created after September 1 of each year may be burned the following fall, prior to December 31, when safe burning conditions occur. See Section III, Item 31.

The local representative of the Director shall be notified in advance of the time and place of any burning of logging slash.

BIOLOGICAL AND CULTURAL RESOURCES

32. a. ☒ Yes ☐ No Are any plant or animal species, including their habitat, which are listed as rare, threatened or endangered under federal or state law, or a sensitive species by the Board, associated with the THP area? If yes, identify the species and the provisions to be taken for the protection of the species.
- b. ☐ Yes ☒ No Are there any non-listed species which will be significantly impacted by the operation? If yes, identify the species and the provisions to be taken for the protection of the species.

NOTE: See THP Form Instructions or the CDF Mass Mailing, 07/02/1999, section on "CDF Guidelines for Species Surveys and Mitigations" to complete these questions.

All trees and snags with visible nesting sites of any threatened, endangered, or board sensitive species will be left standing as prescribed under 14 CCR 939.1 and 939.2(d). If during timber operations within the critical period, the timber operator discovers a snag or tree with a nesting threatened, endangered, or board sensitive species the operator shall protect the nest tree, screen trees, perch trees and replacement trees and shall cease operations within .25 miles, and notify the RPF, the Department of Fish and Game (DFG) and Cal Fire. The RPF shall consult with DFG and develop site specific mitigations and protection measures.

LISTED:

Northern Goshawk: there is a Northern Goshawk activity center located approximately .5 miles north of the THP, NE ¼, Section 13, T32N, R2E. The activity center was originally located in 2001 and has been active every year since. The activity center has fledged offspring in 2001, 2002, 2005-2006. There has been 4 different nest trees all within 300 yards of each other. If Northern Goshawks are observed nesting within the THP area the LTO shall cease all operations within .25 miles of the nest and contact the RPF, CAL FIRE inspector, and DFG.

NON-LISTED:

Pine Marten: The Pine Marten has been detected in the southeastern portions of the forest (Section 24), within the assessment area, during the forest carnivore surveys being conducted by LDSF staff in 2005 and 2006. The THP will maintain habitat for the Pine Marten. LDSF staff in cooperation with the DFG is conducting a monitoring program to evaluate the presence and continued use of known mid-sized forest carnivores.

Pacific Fisher:

On April 27, 2009 the Pacific Fisher became a candidate for listing under the California Endangered Species Act. Emergency regulations were developed by the Fish and Game Commission for this species in order to allow incidental take of fisher for specified activities including timber operations (Section 749.5, Title 14, CCR). This emergency regulation was approved by the Office of Administrative Law on April 27, 2009 and will be in effect until October 27, 2009.

LDSF contains habitats for both the Pacific Fishers and the Pine Marten. Both species were detected on LDSF in a 1990 furbearer presence survey. More recently the Pine Marten has been detected in the southeastern portions of the forest during the forest carnivore surveys being conducted by LDSF staff. No subsequent detections of the Pacific Fisher have occurred. The project will maintain habitat for both the Pine Marten and the Pacific Fisher. If Pacific Fishers are observed within the THP area the LTO shall cease all operations within .25 miles of the observation site and contact the LDSF staff, CAL FIRE inspector, and DFG.

The pertinent DFG Timberland Planning office shall be notified of the detection including time, date, and map location.

The critical period for fishers is March 1 through July 31, where reproduction and caring for young occurs and when the highest potential for disturbance exists.

Observations, detections, and take shall be reported to the Department of Fish and Game, Wildlife Branch, Attn: Fisher Observations, 1812 Ninth St., Sacramento, CA 95811, or by email submission to fisherdata@dfg.ca.gov. Information reported to the Department pursuant to this subdivision shall include as available: a contact name; the date and location (GPS coordinate preferred) of the observation, detection, or take; and details regarding the animal(s) observed (Title 14 CCR, Section 749.5(c)).

See Section III for additional discussion of biological review.

33. ☒ Yes ☐ No Are there any snags which must be felled for fire protection or safety reasons? If yes, describe which snags are going to be felled and why.

Snags greater than 20 feet tall and 16 inches DBH which are within 100 feet of permanent or seasonal roads or landings will be felled if they lean towards the road or landing and present a safety hazard, or if they are a potential hindrance to future access for initial attack of wildfire as per 14 CCR 939.1(a)(2). Additionally, any snag thought to contain sound volume may be harvested as allowed under 14 CCR 939.1(d).

34. ☐ Yes ☒ No Are any Late Succession Forest Stands proposed for harvest? If yes, describe the measures to be implemented by the LTO that avoid long-term significant adverse effects on fish, wildlife and listed species known to be primarily associated with late succession forests.

35. ☐ Yes ☒ No Are any other provisions for wildlife protection required by the rules? If yes, describe.

All trees and snags with visible nesting sites of any non-listed raptor will be left standing as prescribed under 14 CCR 939.1 and 939.2(d). If during timber operations, the timber operator discovers a snag or tree with a nesting of any non-listed raptor the operator shall protect the nest tree, screen trees, perch trees and replacement trees, and cease operations within 500' of the nest, notify the RPF, DFG, Cal Fire. DFG shall have ten (10) days to respond and develop a consultation based on site specific conditions. If a consultation is not developed within the ten (10) days, all non-listed raptors shall have the nest tree, screen trees, perch trees, and replacement trees protected.

Other trees within the THP area that have special value to wildlife will similarly be retained. These trees have been marked with a "W" at dbh. Additionally all snags that do not met the criteria in Item 33 above shall be retained for the benefit of wildlife

36. a. ☒ Yes ☐ No Has an archaeological survey been made of the THP area?
- b. ☒ Yes ☐ No Has a current archaeological records check been conducted for the THP area?
- c. ☐ Yes ☒ No Are there any archaeological or historical sites located in the THP area? Specific site locations and protection measures are contained in the Confidential Archaeological Addendum in Section VI of the THP, which is not available for general public review.
37. ☐ Yes ☒ No Has any inventory or growth and yield information designated "trade secret" been submitted in a separate confidential envelope in Section VI of this THP?
38. Describe any special instructions or constraints that are not listed elsewhere in Section II.

Water drafting plan

Drafting locations are Beaver Creek crossing on South Cow Creek Road (Class I watercourse), South Cow Creek crossing on Upper Bridge Road (Class I watercourse), Roaring Spring crossing on Bateman Road (Class II watercourse), and Atkins Creek crossing on the Bateman Road (Class I watercourse).

It is estimated that water usage will be approximately 40,000 gallons per day distributed among the drafting locations during active timber operations.

Water drafting shall not occur at any of these locations when:

- (A) bypass flows are less than 2 cubic feet per second, or
- (B) pool volume at the water drafting site would be reduced by 10%, or
- (C) diversion rate exceeds 350 gallons per minute, or
- (D) diversion rate exceeds 10% of the above surface flow.

The following are requirements when drafting:

- a. Openings in perforated plate or woven wire mesh screens shall not exceed 3/32 inches (2.38 millimeters).
- b. The approach velocity (water moving through the screen) shall not exceed 0.33 feet/second.
- c. Flow in the source stream shall be at least 2 cubic feet per second (cfs).
- d. Reduction in pool volume shall not exceed 10 percent.
- e. The screen surface shall have at least 2.33 square feet of openings and the diversion rate shall not exceed 350 gallons per minute (gpm) or 10 percent of the surface flow.
- f. If an alternative screen surface area or diversion rate is desired, the following formula can be used: $\text{diversion rate (gpm)} \times 0.00676 = \text{square feet of screen surface area}$. The diversion rate can be calculated by dividing the tank capacity by the fastest filling time (i.e., 3000 gallons / 15 minutes = 200 gpm).
- g. The drafting operator shall actively observe the drafting operation. Pumping shall cease and the screen cleaned if it becomes more than 10 percent obstructed with debris.

All drafting locations shall include measures (such as drip pans or absorbent fiber pads) to prevent petroleum-based products originating from vehicles from reaching surface water, groundwater, and soil. These items shall be disposed of properly.

Check all WLPZ, EEZ and ELZ flagging, and skid trail flagging prior to the commencement of any falling operations. Have the responsible RPF or supervised designee replace any flagging that is incomplete or unclear.

Review any restrictions in yarding equipment access which may cause a need for directional falling toward the lead where the logs will be yarded. Trees designated for removal within the WLPZ of a watercourse shall be directionally felled away from the watercourse and longlined, so as to keep heavy equipment out of the protection zone. In the ELZ of Class III watercourses, trees may be felled bridging the watercourse and endlined from outside the ELZ. The purpose of this measure is to allow for trees that if not directionally felled across the ELZ would fall into the ELZ or damage the residual stand.

Use only designated skid trails and tractor road crossing within WLPZs. Designated skid trails and tractor road crossings are delineated with yellow flagging.

All trees marked with a "W", a "No" or a "L" shall be retained.

Review the Winter Operations Plan and the Site Preparation Addendum. L2 shall not be used during the winter period.

The LTO shall carefully review the Forest Practice Rules regarding Conduct of Operations on Roads and Landings, 14 CCR 943.6.

The LTO shall carefully review the Forest Practice Rules regarding Wildlife Protection Practices contained in 14 CCR 939.2 and 939.3.

All trees and snags with visible nesting sites of eagles, hawks, owls, waterfowl, or any rare or endangered species shall be left standing.

Timber may be removed within 100 feet, as measured on the surface of the ground, from the edge of the traveled surface of appurtenant roads owned or controlled by the timberland owner, timber operator or timber owner, and being used during the harvesting of the particular area for safety reasons (hazard, dead, dying and disease and trees that interfere with the maintenance of the road). The traveled surface of such appurtenant roads is also part of the logging area as defined in CCR 895.1 "Logging Area".

The THP boundary has been designated by pink "THP Boundary" flagging.


The Plan submitter shall notify the Department of the commencement of timber operations at the following address:

TEHAMA-GLENN UNIT
Unit Forester
CAL FIRE
604 Antelope Boulevard
Red Bluff, CA 96080
530-528-5106

DIRECTOR OF FORESTRY AND FIRE PROTECTION

This Timber Harvesting Plan conforms to the rules and regulations of the Board of Forestry and Fire Protection and the Forest Practice Act:

By:


(Signature)

William E. Schultz, RPF #1974
(Printed Name)

November 12, 2009
(Date)

Deputy Chief Forest Practice
(Title)

This page is blank


Buck Butte THP Project Area Map

- THP Boundary
- Class I Watercourse
- Class II Watercourse
- Class III Watercourse
- Spring
- Wet Area
- Primary Road
- Secondary Road
(all roads are seasonal)


T 32 N, R 2 E, Sec 13 & 24
T 32 N, R 3 E, Sec 17 & 18

PART OF PLAN

SCALE 1:13332



Magnetic Declination



16° E



Buck Butte THP Silviculture Map

- THP Boundary
- Class I Watercourse
- Class II Watercourse
- Class III Watercourse
- Spring
- Wet Area
- Primary Road
- Secondary Road
(all roads are seasonal)
- Selection
- Sanitation Salvage
- Brush Field

T 32 N, R 2 E, Sec 13 & 24
T 32 N, R 3 E, Sec 17 & 18

PART OF PLAN


SCALE 1:13332



Buck Butte THP EHR Map


- THP Boundary
- Class I Watercourse
- Class II Watercourse
- Class III Watercourse
- Spring
- Wet Area
- Primary Road
- Secondary Road
(all roads are seasonal)
- Moderate EHR
- High EHR

Magnetic Declination




PART OF PLAN

SCALE 1:13332



Buck Butte THP Roads, Landings & Skid Trail Map (1 of 2)


- THP Boundary
- - - Class I Watercourse
- · - · - Class II Watercourse
- · - · - Class III Watercourse
- ⊙ Spring
- W Wet Area
- ==== Primary Road
- ||||| Secondary Road
(all roads are seasonal)
- XXXXX Existing skid trails
- OOOOO New skid trails
- =A= Temporary Road
- Ⓛ Landings



Revised Page 23, 10/20/09

Buck Butte THP Roads, Landings & Skid Trail Map (2 of 2)

- THP Boundary
- Class I Watercourse
- Class II Watercourse
- Class III Watercourse
- Spring
- Primary Road
- Secondary Road
(all roads are seasonal)
- Existing skid trails
- Temporary Road
- Landings



T 32 N, R 3 E, Sec 17 & 18


Buck Butte THP Watercourse Crossing Map


- THP Boundary
- Class I Watercourse
- Class II Watercourse
- Class III Watercourse
- Spring
- Wet Area
- Primary Road
- Secondary Road
(all roads are seasonal)
- Watercourse crossing
- Skid Trail Crossing
(dry at time of use)
- WLPZ Landing

T 32 N, R 2 E, Sec 13 & 24
T 32 N, R 3 E, Sec 17 & 18




PART OF PLAN



SCALE 1:13332





Buck Butte THP
Appurtenant Roads &
Drafting Location Map
(1 of 2)

 Drafting Location
 Appurtenant Road
 THP Boundary




Buck Butte THP **Appurtenant Roads &** **Drafting Location Map** **(2 of 2)**



Drafting Location

Magnetic Declination



16° E

SCALE 1:26666

1 MILES

0

2000 YARDS

0

1 KILOMETER

0

SECTION III

Support Documentation

Feasibility of Alternatives

No significant adverse effects from the proposed operations under this THP are expected to occur. However, an analysis of THP alternatives follows.

Purpose

The legislative authority for the State Forest System is contained in Public Resources Code (PRC) §4631-4658. CAL FIRE is responsible for the management of LDSF. As part of this oversight, the LDSF staff operates under a management plan, which provides general objectives and goals. The plan is required pursuant to Public Resources Code (PRC) §4645 and Article 8 of the California Board of Forestry and Fire Protection (Board) policy.

LDSF has a management plan, approved by the board, which provides direction and guidance for the managed uses of forest resources with an emphasis on forest demonstration, research, recreation, maintenance of wildlife habitat, and water quality protection. Timber harvesting is one of the mechanisms used to implement forest management goals and foster maintenance and enhancement of other non-timber resources. Guided by the statutes, the Board of Forestry and Fire Protection establishes policy, which governs LDSF and other state forests. Board policy states that the primary purpose of the state forest program is to conduct innovative demonstrations, experiments, and education in forest management.

Objectives

- Demonstrate sound forest management.
- Reduce fuel loading thus reducing the risks of wildfires
- Avoid the waste of timber resources
- Enhance growth and vigor of timber resources
- Improvement of the forest road system
- Improve wildlife habitat, and watershed values promoted by the resulting healthy stands

The project as proposed meets is in conformance with the CEQA compliant 2008 LDSF Management Plan, LDSF's Option A for Long Term Sustained Yield (LTSY), the Board's policy and meets the following objectives:

Achieve a balance between growth and harvest over time consistent with the harvesting methods within the rules of the Board.

Maintain functional wildlife habitat in sufficient condition for continued use by the existing wildlife community within the planning watershed.

Maintain growing stock, genetic diversity, and soil productivity.

Demonstrate various erosion control measures, including watercourse crossing design, pre and post harvest.

Capture tree mortality and improve overall health of timber stands.

Alternatives Considered

No Project

Site would remain as is.

No economic benefits would be realized.

Stand vigor would decrease due to the overstocked stand conditions.

Mortality not harvested would be wasted.

Increased risk to wildfires resulting from the overstocked stand conditions and increasing fuel loads.

Forest management and timber harvest demonstrations will not be carried out.

Project Timing

The proposed project will be completed within the next 5 years.

Delaying the project to another decade was considered.

A delay of the proposed timber harvest would result in the waste of timber resources through stand mortality and allow for the continual risk of wildfire.

A delay in harvest and income timing would substantially reduce the present net worth of the proposed project.

The landowners manage their land on a 10 to 20 year cutting cycle. Delaying the project will increase the acres to be treated in future years to maintain the stand treatment schedule.

Alternative Site

This alternative is not necessary, as any significant negative effect from the proposed operations has been mitigated in the THP.

Alternative Silviculture

Alternative silvicultural methods are limited by the restrictions in LDSF's Option A for Long Term Sustained Yield. The LTSY was determined by modeling timber growth for LDSF using specific silvicultural prescriptions. The LTSY was calculated primarily using uneven-aged silviculture. Even though even-aged silviculture is available to use, the minimal acres modeled are better suited for different locations on the forest, within stands of high disease and mortality, or marginal stocking. Single tree selection was modeled in the southeast portion of LDSF where the soil is more erosive. For modeling purposes, no regeneration was assumed in these stands so as to be conservative in projecting growth. Consequently, an alternative silvicultural method is not a viable option.

Upon review of the alternatives considered, the proposed project is the landowner's best alternative to meet the above stated objectives.

General Project Description

Location: The THP is located in Shasta County on LDSF in Sections 13 and 24, T 32N, R 2 E, and Sections 17, and 18, T 32 N, R 3 E. The elevation of the THP ranges from 5,400 feet to 6,120 feet. The THP is approximately 13 air miles east of the community of Whitmore, California, 22 miles south of Burney and 17 miles northeast of Lassen Volcanic National Park.

Vegetation and Stand Conditions

There are two major commercial timber types found on LDSF, mixed conifer and true fir. The mixed conifer type is found at lower elevations on drier south and west facing slopes. The tree components of this type are ponderosa pine (*Pinus ponderosa*), sugar pine (*Pinus lambertiana*), white fir (*Abies concolor*), incense cedar (*Calocedrus decurrens*), Douglas-fir (*Pseudotsuga menziesii*), and at the upper elevations Jeffrey pine (*Pinus jeffreyi*) and red fir (*Abies magnifica*). The major component of the mixed conifer type is white fir.

The true fir type is found on higher elevations and on the north slopes. This type is characterized by almost pure even aged stands of white and red fir. Other species found in association with the true firs are sugar pine, Jeffrey pine, lodgepole pine (*Pinus contorta*), western white pine (*Pinus monticola*) and in an isolated area, mountain hemlock (*Tsuga mertensiana*).

The western and lower elevation areas within the harvest area are largely composed of the Sierra mixed conifer stands are uneven-aged with all size classes represented. Regeneration exists in the understory especially in areas where past harvest activities have created openings in the canopy.

The entire harvest area is well stocked. In the selection area the average basal area is estimated at 190 square feet per acre and ranges from 120 to 300 square feet per acre. The target average basal area post harvest in the group selection area is 140 square feet, but this THP does not limit LDSF from retaining the Forest Practice Rule standards of 75 square feet.

The sanitation salvage area is also well stocked with a multi story dispersion and two-story stand portions. The overstory is composed of residual trees from a harvest that resembled a shelterwood seed step. The overstory trees are declining in health and vigor. The understory is well stocked with advanced 20-30 year old regeneration. The basal area in the sanitation salvage area is estimated at an average of 120 square feet per acre and ranges from 85-200 square feet.

The disease problems observed in the harvest area largely consist of dwarf mistletoe and cytospora or fir canker. Pockets of dead trees exist in the harvest area from fir canker infection. Minor infection of White Pine Blister Rust is affecting intolerant sugar pine and the western white pine. Endemic insect populations of Mountain Pine Beetle and Ips in the pine species and Scolytis in the fir have also been observed.

Soils and Topography

Topography in the area ranges from relatively level in the southern portion of the plan area in Section 24 to 60% slopes along the edge of Buck Butte. The Soil Survey of Shasta County Area, California identifies several soil types, Lyonsville-Jiggs complex, Windy and McCarthy (very) stony sandy loams and rock land.

Lyonsville-Jiggs Complex

(LgE) – About 45% of this complex is Lyonsville stony sandy loam and 45% is Jiggs gravelly sandy loam on 10-50% slopes. The remaining 10% is inclusions of Windy soils. The Lyonsville soil has moderate permeability. Available water capacity is 2 to 5 inches. Weathered dacite is at a depth of 20-40 inches. Stones and cobblestones cover 3 to 15 percent of the surface. The Jiggs soil has moderate rapid permeability. Available water capacity is 2 to 4 inches. Dacite is at a depth of 20-40 inches and exposed dacite bedrock outcrops cover 5-10% of the surface. Runoff is medium to rapid and the hazard of erosion is moderate to high.

(LhE) – Similar to LgE. Lyonsville has an increased in water capacity of 4-7 inches and the Jiggs soil has an increased capacity of 3 to 6.5 inches. Runoff is medium to rapid and erosion is moderate to high. Both soils are deep to 40 to 60 inches.

Windy and McCarthy Stoney SandyLoams (WeD) – This soil is made up of equal parts Windy and McCarthy. Windy soil has rapid permeability with a water capacity of 5 to 7 inches. The McCarthy soil is moderately rapid permeability with a 4 to 6 inch water capacity. Runoff is medium to rapid in this soil type and the erosion is moderate to high. Bedrock is at a depth of 40- 60 inches. Stones cover 1-3% of the surface.

Windy and McCarthy Very Stoney SandyLoams (WeD) – This soil is made up of equal parts Windy and McCarthy. Windy soil has rapid permeability with a water capacity of 5 to 7 inches. The McCarthy soil is moderately rapid permeability with a 4 to 6 inches water capacity. Runoff is rapid in this soil type and the erosion is moderate to high. Bedrock is at a depth of 40- 60 inches. Stones cover 3-10% of the surface.

Rock land (RxF) – Shallow soil, rock outcrops. Vegetation, where present, is similar to adjacent soils, except that rockland has less grass and more drought resistant species, such as Manzanita.

Watershed and Stream Conditions

LDSF is the headwaters source of two major streams, Old Cow Creek and South Cow Creek. A Tributary to the North Fork Battle Creek and South fork Bear Creek drain small portions of the south side of LDSF.

The THP area primarily occurs within the Beal planning watershed, but has a small portion that drifts over to the Upper Battle Creek planning watershed. Within the Beal planning watershed South Cow Creek starts in the South Cow Creek Basin and flows westerly. South Cow Creek is a class I watercourse for most of its length. Springs and tributaries contribute to its flow constituting it as a major stream before it leaves LDSF. Tributaries to South Cow Creek are Bullhock, Beaver, and Atkins Creeks. Bull hock Creek is a Class I watercourse at its confluence with South Cow Creek to the Middle Bridge Road crossing, approximately 4500 feet upstream. Three intermittent streams that contribute to South Cow Creek are Beal Creek, Dry Gulch and Lee March Gulch. Beal planning watershed is considered threatened and impaired because it has potential for steelhead.

South Cow Creek and Old Cow Creek contains generally complex habitat with deep pools, riffles, and boulders forming step pools. The creek appears to have good channel conditions in the lower portion of the planning watersheds and impacts from timber operations were not significant to those portions of South Cow Creek and Old Cow Creek. Further evaluation of the watercourses occurred in the summer of 2000 from the *LaTour Demonstration State Forest Watershed Monitoring Project*, Stream Channel and Fish Habitat Assessment prepared by the Sacramento Watersheds Action Group (SWAG) under contract with the Department of Forestry and Fire Protection. In this report South Cow Creek, Bullhock Creek and Old Cow Creek were assessed within LDSF boundaries.

The SWAG report evaluated the Class I reaches of all three creeks including 16,579 feet of South Cow Creek within the State Forest Boundaries. The report concluded nearly all (91%) of the watercourse is stable with some instability noted at the upper reaches in a meadow. Banks were stabilized primarily by large cobbles, boulders, and riparian vegetation. By length, habitat was 44% riffles, 44% flat water, 5% pools and 7% dry. Mean pool depth was 1.8 feet for the entire segment. The Class I portion of Bullhock Creek is also stable and has a steep gradient. There is evidence that the watercourse has supported large flood events. Some bank scouring, erosion and depositional features are present in the upper reaches of the Class II segment. These features are largely due to the 1997 rain-on-snow event that resulted in significant runoff in the watershed. By length the habitat of the class I segment of Bullhock Creek is 36% riffles, 58% flat water, and 6% pools. The channel is steep with banks being stabilized with large boulders and diverse woody riparian vegetation.

Only 72 acres in Section 24 of this THP is within the Upper Battle Creek Planning watershed. Within that 72 acres, four Class III watercourse channels merge to a Class II watercourse that drains to Upper Battle Creek. Upper Battle Creek is not considered threatened or impaired. The stream conditions within this plan area are on a relatively flat topography and the channels appear to have meandered in the past. The eastern road that passes south through this area has been raised above the surrounding terrain. It appears that this may have been intentional to help isolate the movement of the Class III watercourses and direct it into several channels in order to maintain a road running surface. The relatively poor channeling of these watercourses appears to originate on the adjacent landowner.

Plan addendum # 14

Selection: pursuant to 14CCR 933.2(a)(2)(A), selection will occur on 321 acres of the plan area. Three silvicultural considerations were observed within the existing stand (1) high stand density in the true fir stands (2) lack of regeneration, and (3) disease and mistletoe infection. In the selection area the average basal area is estimated at 190 square feet per acre and ranges from 120 to 300 square feet per acre. The target average basal area post harvest in the group selection area is 140 square feet, but this THP does not limit LDSF from retaining the Forest Practice Rule standards of 75 square feet. The site classification in the area to be harvested is Dunning Site III.

Sanitation Salvage: pursuant to 14CCR 933.3(b), the sanitation salvage will be used on 101 acres of the plan area. Sanitation salvage will be applied as a result of silvicultural practices that were applied to the areas in 1990. The stands were harvested to open the understory and retain seed trees to regenerate the stand. The stands can be described as multistory stands, but sections are currently a two tiered stand with large dominate trees over advanced 20 to 30 year old regeneration. The basal area in the sanitation salvage area is estimated at an average of 120 square feet per acre and ranges from 85-200 square feet. The overstory is declining in health and vigor. Disease problems such as dwarf mistletoe and white pine blister rust in the overstory are infecting the understory. The intent of this prescription is to remove only those trees which are dead, dying, or deteriorating, because of damage from fire, wind, insects, disease, flood, or other injurious agent in order to capture future mortality, improve forest health, and release the advanced regeneration.

Sanitation salvage areas shall contain (as a minimum) an average point count of 300 "countable trees" per acre immediately following timber operations.

Plan addendum #17 - Erosion Hazard Rating (EHR)

The Soil Survey of Shasta County California and field observations were used to determine the erosion hazard ratings (EHR) for this THP area. The EHR areas were delineated according to soil type and ground observations with regard to slope, ground cover, and physical characteristics. The EHRs for the THP area are moderate and high. The EHR types are delineated on the EHR Map.

Plan addendum #21

c. Slopes over 50% with high or extreme EHR:

Operations shall be restricted to existing tractor roads that do not require reconstruction and designated skid trails (flagged and mapped) on slopes over 50% with a High EHR. See THP map for location of these skid trails. See Section III for explanation and justification. See Section III for additional discussion.

The standard Rule 14 CCR 934.2 (f)(1) states that heavy equipment shall be prohibited where any of the following conditions are present:

- (ii) Slopes steeper than 50% where the erosion hazard rating is high or extreme.

The proposed alternative practice, as described in Section II, item 21, of using existing and RPF designated skid trails will provide equivalent environmental protection as the standard rules. A skid trail network is already existing and is well established. The existing skid trail network shall not require reconstruction. These slopes do flatten to sufficiently dissipate water flow and trap sediment before it reaches a watercourse. The existing skid trail pattern is on a rocky soil that is considered to be a high EHR, but there are no strong signs of erosion (rilling, gulling, etc.). The existing skid trails are not currently, and should not in the future, negatively impact the beneficial uses of water downstream. Cable yarding is not an option since no tail hold can be established to facilitate this yarding method. Due to the silviculture and timber species, helicopter yarding is also not feasible. The two proposed skid trails are required to provide access to an area that does not support adequate tail hold locations for cable operations. Consequently, the requirement under 14 CCR 934.2(f)(2)(i) & (ii) are proposed for enforcement purposes;

On slopes between 50 percent and 65 percent where the erosion hazard rating is moderate, and all slope percentages are for average slope steepness based on sample areas that are 20 acres, or less if proposed by the RPF or required by the Director, heavy equipment shall be limited to:

- (i) Existing tractor roads that do not require reconstruction, or
- (ii) New tractor roads that have been flagged by an RPF or supervised designee prior to use.

Waterbreaks shall be spaced at 50 feet.

Plan addendum #25

Map Point A: Approximately 800 feet of temporary road construction that will terminate with the construction of a new landing. There are no watercourse crossings, the side slope is less than 30%, the road grade averages less than 15 %, EHR is moderate, and there are no unstable areas.

The temporary road shall be constructed as a seasonal, single lane roads with a sufficient number of turnouts for safe vehicle passage. Any tree over 12 inches d.b.h. with more than 25% of the root surface exposed by road construction, shall be felled concurrently with the timber operations. Waste organic material, such as uprooted stumps, cull logs, accumulations of limbs and branches, and unmerchantable trees, shall not be buried in road fills.

Wood debris or cull logs and chunks may be placed and stabilized at the toe of fills to restrain excavated soil from moving down slope. Drainage structures or facilities shall be installed so as to minimize erosion, ensure proper functioning, and to maintain the natural drainage pattern. Drainage structures and facilities shall be of sufficient size, number and location to carry runoff water off of roadbeds, landings and fill slopes. Drainage structures and drainage facilities shall not discharge on erodible fill or other erodible material unless suitable energy dissipaters are used.

The limited construction will not significantly expand the area covered by the transportation system within the watersheds. New construction will affect less than 0.001% of the total area within the watersheds. The temporary road construction is approximately 680 feet.

Upon Completion of operations, the temporary road and associated landing shall be abandoned in accordance with 14 CCR 943.8;

1. Road shall be BLOCKED so that standard production four wheel-drive highway vehicles cannot pass the point of closure at the time of abandonment.
2. The road surface shall be graded or shaped to provide dispersal of water flow.

Plan addendum #27

Standard rule 14 CCR 936.3 (c) states that the timber operator shall not construct or reconstruct roads, construct or use tractor roads or landings in Class I, II, III, IV watercourses, in the WLPZ, marshes, wet meadows, and other wet areas unless when explained and justified in the THP by the RPF, and approved by the Director, except as follows:

- (1) At prepared tractor road crossings as described in 934.8 (b).
- (2) Crossings of Class III watercourses which are dry at the time of operations
- (3) At existing road crossings
- (4) At new tractor and road crossings approved as part of the Fish and Game Code process.

The proposed in-lieu practices, as described in Section II, Item 27, of using existing skid trails, landings and roads within the WLPZ will provide equivalent, and possibly better, protection to the beneficial uses of water than would the standard rules. The proposed practice eliminates the need to relocate landings, skid trails, and road segments outside and adjacent to the WLPZ. Relocation and new construction is not feasible and would create an overall greater soil disturbance within the watershed. The existing skid trails, landings and roads are stable, and are not currently, and should not in the future; negatively impact the beneficial uses of water downstream. Measures to mitigate possible adverse effects from operations proposed under this plan are specified in Section II, Item 27.

L1 – is an existing landing on South Cow Creek Road that approximately 20 feet encroach in a Class I WLPZ. This landing has also been use as a rock pit in the past. In addition, there is an existing berm along the outside edge of the landing. Measures to mitigate possible adverse effects from operations proposed are specified in Section II, Item 27.

L2 – is an existing landing that is bisected by a Class II WLPZ. In addition, only one skid trail accesses this landing. This skid trail is within a Class II WLPZ and Class II ELZ. This existing skid trail access is the only viable entry point for harvesting the section of timber immediately south of the landing. There are no viable alternative skid trail locations. The silvicultural prescription is sanitation salvage for this area. Measures to mitigate possible adverse effects from operations proposed are specified in Section II, Item 27.

L3 – is an existing landing that is partially within a Class II WLPZ. An existing skid trail does access this landing that is within the Class II WLPZ. However, this skid trail is not proposed to be used. An alternate skid trail has been flagged on the ground in yellow skid trail flagging that prevent reentry into the Class II WLPZ. Measures to mitigate possible adverse effects from operations proposed are specified in Section II, Item 27.

Plan addendum #28 (b) – Notification requirements

An exemption to the Notification requirements for information on domestic water supplies is requested for the newspaper notice. USFS and Sierra Pacific Industries are the only landowners within 1000 feet downstream that receive surface drainage for areas proposed for harvest. USFS and SPI received letters requesting any information regarding domestic water uses within 1000 feet from the proposed project boundary. No responses had been received at time of submittal.

Plan addendum #31 - Piling and burning for hazard reduction

The standard rules 14 CCR 937.2(a) and 937.5(b) state slash to be treated by piling and burning shall be treated no later than April 1 of the year following creation, or within 30 days following climatic access, or as justified in the plan. The piles and concentrations shall be burned at a safe time during the first wet fall or winter weather or other safe period following piling and according to laws and regulations.

An alternative to the standard rule is proposed to allow treatment of landing slash accumulations that result from the use of chipping and/or de-limbing equipment created after September 1 of each year. This material may be burned the following fall when safe burning conditions occur. This alternative practice shall be applied over the entire THP area.

This practice differs from the standard practice in that piles will remain in place over the spring and summer and will be treated in the fall, rather than in the winter or early spring following their creation.

This alternative will provide equal or greater hazard reduction. Slash will be concentrated in the landings so that it is no longer a fuel component of the forested stands. There will be protective space around the piles as specified in Section II, Item 31. Also, there have been several incidents of burnt piles rekindling and even escaping following spring burning in this general region. Allowing fall burning of these piles will assure better consumption of the material and a cooling off period through the winter months.

All other provisions of 14 CCR 937.5 will be complied with. Piles will be constructed so that they are sufficiently free of soil for effective burning. These piles will be burned at a safe time during wet fall or winter weather according to other applicable laws and regulations. Piles that fail to burn sufficiently to remove the fire hazard shall be further treated to eliminate the hazard. All necessary precautions shall be taken to confine such burning to the piles.

Although some scorching of surrounding trees may occur, the extent of this damage will not result in conditions that do not meet the silvicultural and stocking requirements of this THP. No excessive buildup of bark beetle populations is expected to occur as a result of this proposed alternative.

Plan addendum #32 – Biological Resources - Listed Species

The biological assessment area (baa) includes the THP area and the Upper Battle Creek & Beal watersheds. These boundaries represent an area where species using a large home range could possibly be affected. The RPF did a CEQA scoping for plant and wildlife species occurring within the baa. Scoping for species potentially affected by proposed operations always includes the listed species which receive either site specific or area wide habitat retention requirements. In addition non listed species were considered for habitat needs within the baa. The Natural Diversity Data Base (NDDDB) was used as a scoping tool to check if any rare, threatened, endangered, or special concern species and/or their habitat are located on or surrounding the THP area. A nine quadrangle query was conducted, which included Viola 7.5 minute quad, its surrounding eight quads. The following is a list of rare, threatened, endangered species, and/or their habitat that occurs within the THP area. There are no recorded occurrences of threatened or endangered species on LDSF.

Northern Goshawk, *Accipiter gentilis*. The harvest area contains both nesting and foraging habitat for the Northern Goshawk. The silvicultural prescriptions proposed will have a very low impact on the Northern Goshawk's habitat requirements. The type of harvest being conducted may even improve forage habitat conditions for the goshawk where dense stands are opened.

This will be the *listed* species that is most likely to occur in the general habitat types found in or near the plan boundaries. There is one known goshawk territory approximately .75 miles of the THP boundary. In the event that goshawks are discovered or suspected of inhabiting the THP area, efforts will be made to verify their presence.

Because habitat for northern goshawks does exist with the THP area, and care has been and will continue to be taken during operations (including marking, field preparation, supervision, etc.) to identify any potential goshawk nest sites or other indications of goshawk presence with the area. In the event that a previously unknown goshawk nest is discovered within 0.25 miles of an area scheduled for operations under this THP, operations will cease immediately within 0.25 miles of the nest until a consultation with DFG can be conducted. At a minimum, all goshawk nest sites will be protected according to 14 CCR 939.3. No currently suitable habitat for northern goshawks will be rendered unsuitable as a result of the harvest proposed under this THP.

Sierra Red Fox, *Vulpes vulpes nector*: The assessment area and the THP do contain the vegetation types considered habitat for the Sierra Red Fox. Observations of the red fox have occurred within the scoping area and primarily around Lassen Volcanic National Park. The closest observation to the THP is near Highway 44 and Sarch Meadow. LDSF staff has been conducting forest carnivore surveys the last three years and the Sierra Red Fox has not been detected. The project will maintain habitat for the Sierra Red Fox.

California Wolverine, *Gulo gulo*: The California wolverine has been detected within the scoping area. The assessment area and the THP do contain the vegetation types that are considered habitat for the wolverine. LDSF staff has been conducting forest carnivore surveys the last three years and the wolverine has not been detected. The project will maintain habitat for the California Wolverine.

Pacific Fisher, *Martes pennanti*: On April 27, 2009 the Pacific Fisher became a candidate for listing under the California Endangered Species Act. Emergency regulations were developed by the Fish and Game Commission for this species in order to allow incidental take of fisher for specified activities including timber operations (Section 749.5, Title 14, CCR). This emergency regulation was approved by the Office of Administrative Law on April 27, 2009 and will be in effect until October 27, 2009.

It appears that the fisher is a generalist as habitat information ranges from mature timber stands, second growth stands and pure hardwood stands. The general habitat includes intermediate to large tree stages of coniferous forests & deciduous-riparian areas with a high percent canopy closure. The micro habitat includes cavities, snags, logs & rocky areas for cover & denning. They appear to require large areas of mature, dense, forest.

LDSF contains habitats for the Pacific Fisher. This species has been detected on LDSF in a 1990 furbearer presence survey. More recently the Pine Marten has been detected in the southeastern portions of the forest during the forest carnivore surveys being conducted by LDSF staff. No subsequent detections of the Pacific Fisher have occurred. The project will maintain habitat for the Pacific Fisher. If Pacific Fishers are observed within the THP area the LTO shall cease all operations within .25 miles of the observation site and contact the LDSF staff, CAL FIRE inspector, and DFG.

The critical period for fishers is March 1 through July 31, where reproduction and caring for young occurs and when the highest potential for disturbance exists. During timber operations, if a fisher den or a female with young is observed, operations shall cease within 0.25 miles and DFG will be immediately contacted.

Due to the silvicultural methods applied in this THP, no potential impacts are expected. Habitat needs will continue to be present within the plan area. In addition, LDSF staff in cooperation with the DFG is developing a monitoring program to evaluate the present and continued use of mid-sized forest carnivores.

Pine Marten, *Martes Aericaa sierrae*: The assessment area and the THP do contain habitat the Pine Marten. Pine Marten were detected on LDSF in a 1990 furbearer presence survey. The Pine Marten has been detected in the southeastern portions of the forest (Section 24), within the assessment area, during the forest carnivore surveys being conducted by LDSF staff in 2005 and 2006. The THP will maintain habitat for both the Pine Marten and the Pacific Fisher. LDSF staff in cooperation with the DFG is conducting a monitoring program to evaluate the presence and continued use of known mid-sized forest carnivores.

Northern Spleenwort, *Asplenium septentrionale*: Northern spleenwort is found growing out of crevices in granite like rock outcrops and is usually found above 5000 feet in elevation. There are several rock outcrops located on LDSF and within the assessment area that have potential habitat for northern spleenwort. Typically these rock outcroppings are not disturbed by timber harvest activities. The road construction described within the plan doesn't traverse any large rock outcrop. Northern Spleenwort has not been observed within the THP or on LDSF.

Vanilla grass, *Hierochloa odorata*: The assessment area and the THP have the general habitat types associated with the known occurrences of vanilla grass. Vanilla grass is located within wet meadows and seeps above 5400 feet in elevation. The THP provides protection for all meadows and seeps.

Rayless mountain ragwort, *Packera indecora*: Rayless mountain ragwort is located in meadows and seeps on mesic sites between 5200 and 6500 feet in elevation. The assessment area and the THP has the general habitat types associated with the known occurrences of Rayless mountain ragwort. The THP has potential habitat along the class II watercourses, meadows, springs and seeps. The THP provides protection for all meadows, seeps, and watercourses.

Northwestern moonwort: The assessment area and the THP have the general habitat types associated with the few known occurrences of northwestern moonwort. Northwestern moonwort is located along creek banks, meadows, upper and lower montane coniferous forest above 5310 feet in elevation. The THP provides protection for all watercourse, meadows and seeps.

Mingan moonwort, *Botrychium minganense*: The assessment area and the THP have the general habitat types associated with the known occurrences of mingan moonwort. Mingan moonwort is located along creek banks of lower montane coniferous forest above 4500 feet in elevation. The THP provides protection for all watercourse and seeps.

Upswept moonwort, *Botrychium ascendens*: The assessment area and the THP have the general habitat types associated with the few known occurrences of upswept moonwort. Upswept moonwort is located along creek banks, meadows, upper and lower montane coniferous forest above 4500 feet in elevation. The THP provides protection for all watercourse and seeps.

Western goblin, *Botrychium montanum*: The assessment area and the THP have the general habitat types associated with the few known occurrences of western goblin. Western goblin is located along creek banks in old growth lower montane coniferous forest above 4500 feet in elevation. The THP provides protection for all watercourse and seeps.

Tall alpine-aster, *Oreostemma elatum*: The assessment area and the THP have the general habitat types associated with the vaguely

documented occurrence of tall alpine-aster in this area. Tall alpine-aster is located on mesic sites along meadows and seeps of upper montane coniferous forest above 3015 feet in elevation. The THP provides protection for all watercourse, meadows and seeps.

Scalloped moonwort, Botrychium crenulatum: The assessment area and the THP have the general habitat types associated with the known occurrences of scalloped moonwort. Scalloped moonwort is located along moist meadows and near creeks of lower montane coniferous forests and freshwater marshes above 4500 feet in elevation. The THP provides protection for all watercourse and seeps.

Santa Lucia dwarf rush, Juncas luciensis: The assessment area and the THP have the general habitat types associated with the vaguely documented occurrence of Santa Lucia dwarf rush in this area. Santa Lucia dwarf rush is located on chaparral, Great Basin scrub, lower montane coniferous forests, meadows and seeps between 900 –6000 feet in elevation. The THP provides protection for all watercourse, meadows and seeps.

Broad-nerved hump moss, Meesia uliginosa: The assessment area and the THP have the general habitat types associated with the vaguely documented occurrence of broad-nerved hump moss in this area. Broad-nerved hump moss is located on meadows and seeps of upper montane coniferous forest above 3900 feet in elevation. The THP provides protection for all meadows and seeps

The following table shows additional species scoped by the CNDDDB on Jan 30 2008, Feb 27 2008 & July 14 2009 that retain no habitat in the THP area.

Scientific Name	Common Name	CA Status	CNPS List	Comments
<i>Fritillaria eastwoodiae</i>	Butte County fritillary	None	3.2	THP is above elevation
<i>Cryptantha crinita</i>	silky cryptantha	None	1B.2	THP is above elevation
<i>Phlox muscoides</i>	Moss phlox	None	2.3	Alpine bolder and rock field
<i>Potentilla newberryi</i>	Newberry's cinquefoil	None	2.3	Marshes and swamps
<i>Potamogeton praelongus</i>	White-stemmed pondweed	None	2.3	Marshes and swamps
<i>Draba aureola</i>	Golden alpine draba	None	1B.3	Serpentine or volcanic outcrops
<i>Smelowskia ovalis</i> var <i>congesta</i>	Lassen Peak smelowskia	None	1B.2	Alpine bolder and rock field
<i>Silene suksdorfii</i>	Cascade alpine campion	None	2.3	Alpine bolder and rock field
<i>Astragalus pulsiferea</i> var <i>suksdorfii</i>	Suksdorf's milk-vetch	None	1B.2	Lower Montane
<i>Collomia larsenii</i>	Talus collomia	None	2.2	Loose volcanic material
<i>Mielichhoferia tehamensis</i>	Lassen Peak coppermoss	None	1B.3	Volcanic rock
<i>Hulsea nana</i>	Little hulsea	None	2.3	Rocky or gravely volcanic substrates
<i>Trimorpha acris</i> var <i>debilis</i>	Snow fleabane daisy*	None	2.3	Volcanic rock outcrops
<i>Erigeron nivalis</i>	Snow fleabane daisy*	None	2.3	Alpine bolder and rock field
<i>Eriogonum pyrolifolium</i> var <i>pyrolifolium</i>	Pyrola-leaved buckwheat	None	2.3	Alpine bolder and rock field
<i>Botrychium virginianum</i>	Rattlesnake fern	None	2.2	THP is above elevation
<i>Rana boylei</i>	Foothill yellow-legged	Special	N/A	THP is above elevation, outside range
<i>Pandion haliaetus</i>	Osprey	Special	N/A	No good fish producing body of water
<i>Haliaeetus leucocephalus</i>	Bald eagle	Endanger	N/A	No good body of water near
<i>Falco peregrinus anatum</i>	American peregrine falcon	Endanger	N/A	No habitat for nesting
<i>Eriogonum pyrolifolium</i>	Pyrola-leaved buckwheat	None	2.3	Alpine bolder and rock field
<i>Draba aureola</i>	Golden alpine draba	None	1B.3	Alpine bolder and rock field
<i>Juncus digitatus</i>	Finger rush	None	1B.1	THP is above elevation
<i>Oncorhynchus tshawytscha</i>	Spring run Chinook salmon	Threat	N/A	No occurrences in watershed.

* Common name Snow Fleabane Daisy showed up twice in the CNPS database between Jan 30, 2008 and July 14, 2009.

There are numerous other wildlife species that exist on LDSF including the THP are that are not listed as threatened, rare, of endangered. Part of the South Cow Creek deer herd uses LDSF as summer range and fawning area. In the past, certain designated brush fields have been burned to improve forage habitat for the deer. There are other brush fields that may be burned in the future. The forest inventory on LDSF indicates there are 7130 acres of merchantable sized timber stands and 677 acres of plantation (1978 Whitmore burn). The remainder of the Forest is brush, rocky areas, meadows, and open areas with scattered trees.

Plan addendum #33 - Snag Felling / Hazard Reduction

Felling of snags for hazard reduction within 100 feet of all public roads, seasonal roads, and landings will not result in the loss of habitat elements associated with late seral stage timber stands. There are standing dead trees in later stages of decay throughout the THP. All snags with visible nesting sites of eagles, hawks, owls, waterfowl, or any rare or endangered species will be left standing as prescribed under 14 CCR 939.1 and 939.2(d). Special attention will be focused on retaining snags within WLPZs that may be recruited as large woody debris (LWD).

DEMONSTRATIONS AND EXPERIMENTS

According to statute and Board policy, the purpose of the state forest program is to investigate and demonstrate the economic feasibility of artificial reforestation and the productive and economic possibilities of forest management practices which are designed to promote continuous forest production, with due regard to conservation of soil, watershed, scenic, wildlife, and recreational values. PRC 4645 authorizes the Department of Forestry and Fire Protection to manage State Forests and states, "The department, in accordance with plans approved by the board, may engage in the management, protection, and reforestation of state forests." The primary current use of state forests is to demonstrate economical silvicultural practices and timber harvesting procedures that protect environmental values.

State forests have been established to furnish land for needed investigation, demonstrations, and education in such things as the economic feasibility of artificial reforestation, good forest practices, maintenance of forest land in a productive condition, study of effects of improved cutting methods, proper management and harvesting methods, and economical forest management.

The following potential demonstrations can be associated with this timber harvesting plan:

1. Continuous Forest Production and economical silvicultural practices.

Timber harvesting and forest production has occurred on LDSF since 1952. Approximately 160 million board feet of timber has been harvested from the Forest. Since the Forest's establishment, the estimated standing volume of timber has increased from 102 million board feet to 197 million board feet (based on TAI inventory conducted from 1994-2001). This harvest will continue to demonstrate forest production to achieve maximum sustained production of high quality forest products while giving consideration to other values relating to recreation, watershed, wildlife, range and forage, fisheries, and aesthetic enjoyment.

2. Native road surface stabilization within the WLPZ

The South Cow Creek Road is an existing road, partially within the WLPZ of the Class I and II of South Cow Creek including a Class III tributary. The road has a native surface and varies in slope. South Cow Creek Road currently utilizes rolling dips and outsloping for drainage. Sediment traps shall be installed at the drainage locations along that Class III tributary. The sediment traps should collect the majority of any sediment being transported off the road surface. The results will evaluate the efficacy of the current native road surface material for stabilization.

3. Pine Martin Monitoring

Presence has been detected in Section 24 of this THP. This plan will monitor the continued presence of the pine martin within the plan area in relation to a selection silviculture practice.

4. Red Fox Monitoring

Provide monitoring information on the possible presence of the red fox on LDSF. This information will be made available to the Department of Fish and Game for future studies beyond this THP. Information shall include vegetation type, soil type, elevation and climate conditions that observations were made in.

5. Remote photo monitoring for mid-size forest carnivores

LDSF staff in cooperation with the DFG is conducting a monitoring program to evaluate the presence and continued use of known mid-sized forest carnivores (& R.O.U.S.'s). Additionally within the study, a comparison of pre and post harvest use is being evaluated by silvicultural treatment.

This page is blank

SECTION IV
CUMMULATIVE IMPACTS

STATE OF CALIFORNIA
BOARD OF FORESTRY
CUMULATIVE IMPACTS ASSESSMENT

- (1) Do the assessment area(s) of resources that may be affected by the proposed project contain any past, present, or reasonably foreseeable probable future projects? ☒ Yes ☐ No
If the answer is yes, identify the project(s) and the effected resource subject(s).
- (2) Are there any continuing, significant adverse impacts from past land use activities that may add to the impacts of the proposed project? ☐ Yes ☒ No
If the answer is yes, identify the activities, describing their location, impacts, and the affected resource subject(s).
- (3) Will the proposed project, as presented, in combination with the past, present, or reasonably foreseeable probable future projects identified in items (1) and (2) above, have a reasonable potential to cause or add to significant cumulative impacts in any of the following resource subjects?

Impact Assessment	Yes After Mitigation (a)	No After Mitigation (b)	No Reasonably Potential Significant Effects (c)
1. Watershed			X
2. Soil Productivity			X
3. Biological			X
4. Recreation			X
5. Visual			X
6. Traffic			X
7. Other			X
<p>a. Yes, means that potential significant adverse cumulative impact are left after application of the forest practice rules and mitigations or alternatives proposed by the plan submitter.</p> <p>b. No after mitigation means that any potential for the proposed timber operation to cause or add to significant adverse cumulative impacts by itself or in combination with other projects has been reduced to insignificance or avoided by mitigation measures or alternatives proposed in the THP and application of the forest practice rules.</p> <p>c. No reasonably potential significant cumulative effects means that the operations proposed under the THP do not have a reasonable potential to join with the impacts of any other project to cause, add to, or constitute significant adverse cumulative impacts.</p>			

- (4) If column (a) is checked in (3) above, describe why the expected impacts cannot be feasibly mitigated or avoided and what mitigation measures or alternatives were considered to reach this determination. If column (b) is checked in (3) above describe what mitigation measures have been selected which will substantially reduce or avoid reasonably potential cumulative impacts except for those mitigation measures or alternatives mandated by the application of the rules of the Board of Forestry.
- (5) Provide a brief description of the assessment area used for each resource subject.
- (6) List and briefly describe the individuals, organizations, and records consulted in the assessment of cumulative impacts for each resource subject. Records of the information used in the assessment shall be provided to the Director upon request.

Past and Future Activities

The assessment area for past and future activities consists of the North Battle Creek (5507.120104) and Beal (5507.310103) Cal Water Planning Watersheds, version 2.2

For assessment purposes, the following is a table of past projects that have been approved within the North Battle Creek and Beal planning watersheds. The data was obtained from the CAL FIRE Cumulative Effects Database. Due to the limitations of the CDF database the acres listed below tend to be over estimates. If part of a THP is within the assessment area, then all of the acres of the THP are included in the database, unless noted otherwise.

Timber Harvest Plans in the Assessment Area (North Battle Creek & Beal Creek PW)													
THP Number	yarding method	status	Acres by Prescription										**Total
			NH	FB	AP	R/W	CC	R	SEL	SS	CT	GSEL	
2-02-033	tractor/skidder	completed					31						31
2-03-172	tractor/skidder	active							458				458
2-05-149	tractor/skidder	active	39	14					95	200		1914	2,262
2-06-138	tractor/skidder	active			167		239						406
2-99-253	tractor/skidder	completed					5	83				368	456
2-01-037	tractor/skidder	completed				1			300	50	1025		1,376
2-03-143	tractor/skidder	active					11	95	362				468
2-03-188	tractor/skidder	active		57			485	2			237		781
2-03-050	tractor/skidder	completed							1185				1,185
2-02-214	tractor/skidder	active	13	112			494	54	3		410		1,086
2-02-187	cable, tractor/skidder	completed						344				1288	1,632
2-99-252	tractor/skidder	completed			265								265
2-01-193	tractor/skidder	completed							2369		32		2,401
2-01-161	tractor/skidder	completed									50	611	661
2-04-211	tractor/skidder	active								292		749	1,041
2-05-147	tractor/skidder	active		4			40						44
2-08-071	tractor/skidder	active				2		7				341	350
*SCH# 2008062009	active		9,033 acre LDSF management plan										
**Total Acreage			52	173	432	3	1305	585	4772	542	1754	5271	14903
Percent of Assessment Area			0.2	0.8	2.0	0.0	6.1	2.7	22.3	2.5	8.1	24.6	69.5

UNK	Unknown (Silviculture not included in the CDF database check)
CC	Clear Cut
SWS	Shelterwood Seed
SWP	Shelterwood Prep
SWR	Shelterwood Removal
STS	Seed Tree Seed
STR	Seed Tree Removal
R of W	Right of Way
SEL	Selection
SS	Sanitation-Salvage
CT	Commercial Thinning
Trans	Transition Method
Rehab	Rehabilitation of Understocked Area
GSEL	Group Selection
NT	Non Timberland

* This is a CEQA compliant Mitigated Negative Declaration of LaTour Demonstration State Forest's Management Plan 2008.

** Acres and percentages shown within these tables may be increased over the actual acres harvested within the assessment area. Due to the limitations of CAL FIRE's database, if portion of a THP is within the assessment area, then all the acres of the THP are included in the data base.

Based on the CAL FIRE Database Check conducted on July 17, 2009 14,024 acres (69.5%) of the assessment area has been harvested or planned for harvest. Of the total area harvested, 1890 acres (8.8% of the assessment area) were treated with evenaged silviculture methods. The majority of the assessment area that was harvested was treated using unevenaged and intermediate silvicultural methods (13013 acres). No long-term site impacts has resulted from the harvesting with in the assessment area.

Present projects

For the purpose of assessing present projects the entire THP area is being treated with a selection, and sanitation salvage silviculture methods. Another THP is scheduled for LDSF, but the acreages are unknown at this time. Silviculture is expected to be Variable Retention and Selection. There are no other known California Environmental Quality Act projects currently proposed within the assessment area.

Future Projects

Future projects include the ongoing production and removal of high quality forest products through scheduled periodic harvesting on the commercial timberlands. LDSF will continue to manage the State's timberlands on periodic entries (18 year re-entry cycle) using predominantly unevenaged silviculture. Within the next 5 years LDSF has one additional THP planned within the Beal watershed. No increased impacts are expected to result from these ongoing forest management activities.

ASSESSMENT AREAS

Watershed Resources

The watershed assessment area consists of the Beal and Upper Battle Creek Cal Water 2.2 watersheds and is shown on the attached Watershed Assessment Map. The THP boundary lies within the headwaters of both watersheds. The watersheds are third order watersheds and Cow Creek is tributary to the Sacramento River. This assessment area was chosen because the key cumulative impact issues, related to timber harvest, typically express themselves at the scale of planning watersheds or a subset of the planning watershed area.

Beal watershed (planning watershed 5507.310103) is the headwaters of South Cow Creek and drains a basin of 11,598 acres, of which 5,928 acres are contained within the boundaries of LDSF. Elevation ranges from 6,740 at LaTour Butte to 2,920 feet at the junction with Atkins Creek. Major tributaries include Beaver, Bullhock and Beal Creeks. South Cow is a third order stream before the junction with Atkins Creek (and fourth order below Atkins). There are approximately 9 miles of Class I watercourses along the main channel of South Cow Creek. Ownership in the lower elevations of the watershed is predominately private commercial timberlands.

Upper Battle Creek watershed (planning watershed 5507.120104) includes the headwaters portion of North Fork Battle Creek. It includes North Battle Creek Reservoir, but is above McCumber Reservoir. Total watershed area is 9,830 acres, of which 199 acres are contained within the boundaries of LDSF. Elevation ranges from 7,064 (Huckleberry Mountain) to 4,100 feet at Bridges Creek. Major tributaries are unnamed. North Fork Battle Creek is a third order stream. There are approximately 7.5 miles of Class I watercourse along the main channel.

Soil Productivity

The assessment area will be the boundary of the THP. This will be adequate to cover impacts from timber operations.

Biological Resources

The biological assessment area (BAA) coincides with the watershed assessment area. The BAA has high biodiversity based on the elevation range, and multiple types of vegetation and habitat. Rational for selection of the BAA is that the watershed assessment area serves as a distinct boundary for collecting and observing wildlife data. This area provides a large enough area adjacent to the THP to assess cumulative impacts to wildlife.

Recreational Resources

The assessment area for recreational resources will be the harvest area plus 300 feet from the plan boundary. This area is appropriate due to the limited recreational use the area receives.

Visual Resources

The visual assessment area is the plan area that is readily visible to significant numbers of people within 3 miles of the THP. This was selected due to the distance of the harvest area from communities and well traveled roads.

Vehicular Traffic Impacts

The assessment area includes the two main haul routes from the THP area.

- a) Cutter Road to the Lassen National Forest Road A16, North to the Tamarack Rd (Shasta County Rd.)
- b) Bateman Road from the harvest boundary to the end of the county road portion on the Bateman Road. The county road ends at the Atkins Creek watercourse crossing.

The extent of the assessment area was determined based on these routes are the most logical routes off the harvest area and the assessment area terminates at the first county road.

B. Watershed Impact Assessment

LDSF is located at the top of a range and is the headwaters for one major drainage, South Cow Creek and part of the headwaters of North Battle Creek. Beal and North Battle Creek watersheds are the headwaters of these two major drainages. Precipitation averages 46 inches a year with most of it as snow (74%) between November and March. Summer rainfall in the form of thunderstorms is unpredictable.

The harvest area lies within the Beal and North Battle Creek watersheds. Tributaries to South Cow Creek, part of the Beal Watershed, are within the plan area although the WLPZ of South Cow Creek is outside the plan. Numerous skid trails and landings exist in the harvest area from past selection harvests. Slopes of the harvest area within the Beal Watershed are moderate with the average being approximately 25-30%.

Various portions of the plan area were initially harvested in the early 1960's. A second entry occurred in the 1990s, which covered a significant portion of the plan area. Past harvests used the selection silvicultural system.

South Cow Creek is a third order watercourse and a fourth order watercourse downstream of the junction of Atkins Creek. South Cow Creek is in good condition. South Cow Creek contains generally complex habitat with deep pools, riffles, and boulders forming step pools. The creek appears to have good channel conditions in the lower portion of the planning watershed and impacts from timber operations were not significant to those portions of South Cow Creek.

Further evaluation of the South Cow Creek, Old Cow Creek and Bullhock Creek occurred in the summer of 2000 from the *LaTour Demonstration State Forest Watershed Monitoring Project*, Stream Channel and Fish Habitat Assessment prepared by the Sacramento Watersheds Action Group (SWAG) under contract with the Department of Forestry and Fire Protection. In this report South Cow Creek, Bullhock Creek and Old Cow Creek were assessed within the LDSF boundaries. The SWAG report assessed 16,579 feet of South Cow Creek, 15,376 feet of Bullhock creek and 7,380 feet of Old Cow Creek within the LDSF Boundaries. The report concluded 91% of S. Cow Creek was stabile with some instability noted at the upper reaches in a meadow. The report noted that 99% of Old Cow Creek was stabile with the first 300 feet of Old Cow Creek being rated as stability at risk. Banks were stabilized primarily by large cobbles, boulders, and riparian vegetation. By length habitat within these two creek is approximately 40% riffle, 40% flatwater and 20% pools. Bullhock creek lies entirely within the LDSF Boundary. The 4500-foot class I segment of this watercourse was also rated as being stabile and begins at its confluence with South Cow Creek. The channel is steep with the banks being stabilized with large boulders and diverse woody riparian vegetation. By length habitat is 36% riffles, 58% flatwater, and 6% pools. Bullhock Creek has a steep gradient and has evidence of supporting large flood events. The habitat within all three Class I watercourses are boulder dominated.

South Cow Creek has been 303(d) listed based on the pollutant of Fecal Coliform. The possible sources of fecal coliform include agriculture, grazing related sources and others. Although LaTour may acquire an occasional lost cow on the property, it is not considered a highly desirable grazing area due to steep slopes, dense timber cover and minimal meadow grazing potential. In addition, weather conditions also attribute to the loss of grazing potential (moderate to heavy snow loads in the Winter and Spring). This THP does not propose cattle grazing, installation of septic tanks, nor will timber harvesting increase or decrease fecal coliform potential.

Trout occur in South Cow Creek and Old Cow Creek. The only other creek that has trout is Bullhock Creek in the lower 600 – 800 feet during the early part of the year. All planning watersheds within the assessment area are included within the Evolutionarily Significant Unit (ESU) for Chinook salmon and steelhead trout due to known downstream populations. Only the Beal and Atkins planning watersheds are classified as "Threatened and Impaired Watersheds" under the Forest Practice Rules. No anadromous salmonids occur on LDSF, nor are there historical records of observations.

Species of trout found on LDSF are rainbow trout (*Salmo gairdnerii*), brown trout (*Salmo trutta*), and an occasional eastern brook trout (*Salvelinus fontinalis*). South Cow Creek primarily has rainbow trout and Old Cow Creek has primarily brown trout.

PART OF PLAN

The desired future condition for watershed and fisheries resources on LaTour includes maintaining and improving current riparian conditions and in-stream habitat. Management in WLPZ areas on LaTour will in most cases exceed the requirements for riparian area protection laid out in the State forest practice rules. We anticipate that riparian areas will be a fertile area for future research on the Forest. Management in and near these areas will be focused on maintaining maximum future management flexibility and not foreclose on future options for research and management.

Although there are no current or historical records of anadromous salmonids on LaTour, all planning watersheds within LaTour are included within the Evolutionarily Significant Unit (ESU) for Chinook salmon and steelhead trout due to known downstream populations, and the Beal and Atkins planning watersheds are classified as "Threatened and Impaired Watersheds" under the forest practice rules. Timber Harvest Plans submitted within the Beale and Atkins planning watersheds will comply with the forest practice rule 14 CCR 936.9, "Protection and Restoration in Watersheds with Threatened or Impaired Values." All stream channels, streambanks, and riparian zones will be protected during forest management activities. Protection of watershed values will be an integral part of the overall management of the forest and will be directly correlated with silvicultural practices and logging standards pursuant to section 4651 of the Public Resource Code and the Forest Practice Act.

The following general guidelines for watershed and fisheries resources will be adhered to on LaTour:

- 1) Maintain conifer and hardwood trees in buffer zones along all watercourses and around all springs in order to lower water temperature, or prevent increases in water temperature.
- 2) Allow for the natural recruitment of large woody debris to the stream channel to improve or maintain instream habitat quality and stream ecosystem function.
- 3) Minimize the number of temporary watercourse crossings.
- 4) No significant increase in erosion or sedimentation over background levels is expected to result from timber harvesting at the levels described in this Option A document. Commonly used estimates of sedimentation rates attributable to timber operations do not take into account the reduction in sedimentation that will result from watershed remediation projects that will be implemented in conjunction with timber operations. Such projects are in addition to the mitigation measures required by the forest practice rules to reduce erosion. Examples of planned watershed remediation efforts on LaTour to be implemented over the next several years include rocking main roads as needed, replacing culverts at risk of failure with larger culverts and outslowing road segments with rolling dips. Where necessary, the existing road system will be upgraded

Each timber harvesting operation will be evaluated with respect for sediment source remediation. High-priority remediation sites will be considered when selecting areas for upcoming harvests. In some cases, remediation at locations other than timber harvest areas could constitute offsite mitigation for the watershed impacts of harvesting.

Sediment Effects

Sediment-induced cumulative watershed effects (CWE) occur when earth materials transported by surface or mass wasting erosion enter a stream or stream system at separate locations and are then combined at a downstream location to produce a change in water quality or channel condition. Sediment effects result from many factors such as weather, geology, soil erosion potential, road location, silviculture, vegetation retention, and heavy equipment operations adjacent to watercourses. Sedimentation has occurred to tributaries of the South Cow Creek during the winter storms of 1997, when rain-on-snow events caused significant runoff resulting in culvert crossing failures and road fill washing into the drainage system.

The management of LDSF has a goal of reducing sedimentation to watercourses. The LDSF has developed and implemented a Road Management Plan (RMP) in compliance with the California Environmental Quality Act (CEQA) that will reduce erosion and sediment from the permanent road system. Implementation of the RMP involves systematic survey of the road system and all watercourse crossings.

Since 1999 over 10 miles of roads in the Beal Watershed have been treated to improve drainage and reduce erosion. This treatment has included outslowing and installing rolling dips on 5.5 miles of road that were previously insloped with an inside ditch. Where road surface runoff is a concern the traveled surface is rocked. At the headwaters of South Cow Creek, 0.5 miles of South Cow Creek road was abandoned and five crossings permanently removed. Watercourse crossings are evaluated as to their potential to fail or contribute sediment from improper installation. Twelve crossings have been replaced since 1999. All of these actions have or will reduce potential sediment inputs into the Beal Watershed. Approximately 1 mile of LDSF roads have been rocked within the

Huckleberry watershed since the implementation of the RMP.

Under this THP steps have been taken to reduce sediment effects from timber operations and correct new road issues that have been identified as having the potential to contribute sediment to watercourses. The prescribed silvicultural systems will maintain vegetation over the harvest area. There will be no groups designated to be harvested within the WLPZ of watercourses. Where operations will occur in the WLPZ or ELZ of a watercourse, mitigations are incorporated into the plan to reduce erosion and the impact to insignificance.

Water Temperature/Thermal Loading Effects

Water temperature related CWEs are changes in water chemistry or biological properties caused by the combination of solar warmed water from two or more locations (in contrast to an individual effect that results from impacts along a single stream segment) where natural cover has been removed. Due to the elevation of the plan area the two major factors that would affect water temperature are water source and canopy cover. The contribution of water from the plan area within both watersheds, during the summer months, is spring-fed watercourses from streams with gradients that result in high flow velocities. Stream reaches with low flow velocities and full solar exposure that would result in an increase in water temperature are uncommon on the LDSF within these watersheds. Past harvests have maintained canopy cover over watercourses. The SWAG report found that the Class I watercourses within the Beal watershed had an average of 69% canopy cover, measured with a solar pathfinder, within the LDSF boundaries. Ninety four (94) percent of this cover consisted of coniferous vegetation.

This THP will maintain streamside vegetation that will continue to shade watercourses from solar radiation and prevent water temperature increases.

Organic Debris/LWD Effects

Large woody debris can have both positive and negative effects on a watercourse. Large woody debris is an important stabilizing agent in steep gradient channels. The sudden introduction of large, unstable volumes of bigger debris (such as logs, chunks, and larger limbs produced during a logging operation) can obstruct and divert stream flow against erodible banks, block fish migration, and may cause debris torrents during periods of high flow. Removing streamside vegetation can reduce the natural, annual inputs of litter to the stream (after decomposition of logging-related litter). This can cause both a drop in food supply, and resultant productivity, and a change in types of food available for organisms.

Based upon the California Department of Fish and Game's *California Salmonid Stream Habitat Restoration Manual –Third Edition*, the SWAG study found that on average there were 22 pieces of large woody debris per 100 feet of watercourse segment in the Class I watercourses on the LDSF. Watercourse protection provided in the plan will continue to provide both LWD for streamside habitat and prevent the sudden introduction of debris from harvesting practices.

Chemical Contamination Effects

Sources of chemical contamination include run-off from roads treated with oil or other dust-retarding materials, direct application or run-off from pesticide treatments, contamination by equipment fuels and oils, and the introduction of nutrients released during slash burning.

The use of oil or dust retarding materials is not planned for this THP. Accidental contamination of equipment fuel or oil is unlikely. Fuel is stored in an area where it cannot contaminate a watercourse if a leak occurs. Additionally, equipment shall be serviced outside the protection zone of watercourses.

The use, type and the timing of the herbicide shall be determined and recommended by a PCA and the application shall adhere to the PCA's recommendation, the herbicide label instructions, and the Mitigated Negative Declaration, State Clearing House (SCH) # 2008062009 for LDSF Management Plan 2008 to DPR regulations, the PCA recommendation, the instructions on the herbicide label. The label is a comprehensive document about the herbicide, any associated hazards, active and inactive agents, and the proper use and handling of the herbicide. To speculate on potential impacts that could occur if the label, PCA recommendations, and DPR regulations are not followed is beyond the scope of this document.

No cumulative watershed effect, with regards to chemical contamination, is predicted for this THP.

Peak Flow Effects

Peak flow increases may result from management activities that reduce vegetative water use or produce openings where snow can accumulate (such as clear-cutting and site preparation) or that change the timing of flows by producing more efficient runoff routing (such as insloped roads).

The assessment area has experienced high peak flows from rain-on-snow events. These events, such as occurred in 1997, are unpredictable. The proposed silvicultural prescriptions will maintain vegetation over the plan area that will enhance infiltration of precipitation and maintain peak flows. Groups within the selection area will be less than 2.5 acres and will be planted to establish vegetation in the opening. There are no new roads planned for this timber harvesting plan that would reroute and concentrate runoff. As stated above for sediments effects, the drainage of existing roads is being improved through implementation of LaTour's Road

Management Plan. The potential for this plan to increase peak flows is insignificant.

This harvest will have no impact on water temperature, organic debris, chemical contamination, or peak flow cumulative watershed effects. Sediments effects from road use and harvesting activities may occur but will be insignificant. Only one new temporary road construction is planned. No large openings will be created. Nearly all tractor roads needed for this harvest exist. All watercourses and springs within and adjacent to the harvest area will be protected. Post harvest streamside vegetation will continue to provide filter strip properties and shading. Water drafting is proposed at four locations. Drafting locations will be rocked to prevent the introduction of sediment into the watercourse during drafting operations. Additionally the vehicles will be inspected to ensure chemical contaminants are not introduced into the watercourses. The silvicultural systems being applied should have no effect on peak flow. The vigorous residual stand will continue to maintain infiltration capacities and hold soil in place.

C. Soil Productivity Assessment

The Soil Survey of Shasta County Area, California identifies several soil types, Lyonsville-Jiggs complex, Windy and McCarthy (very stony sandy loams and rock land. The predominant soil series within the harvest boundary is the Lyonsville-Jiggs complex. The soils are well-drained with moderate to rapid permeability. Soils in the Lyonsville-Jiggs complex series make up about 95% of the soil types in the plan area.

Lyonsville-Jiggs Complex

(LgE) – About 45% of this complex is Lyonsville stony sandy loam and 45% is Jiggs gravelly sandy loam on 10-50% slopes. The remaining 10% is inclusions of Windy soils. The Lyonsville soil has moderate permeability. Available water capacity is 2 to 5 inches. Weathered dacite is at a depth of 20-40 inches. Stones and cobblestones cover 3 to 15 percent of the surface. The Jiggs soil has moderate rapid permeability. Available water capacity is 2 to 4 inches. Dacite is at a depth of 20-40 inches and exposed dacite bedrock outcrops cover 5-10% of the surface. Runoff is medium to rapid and the hazard of erosion is moderate to high.

(LhE) – Similar to LgE. Lyonsville has an increased in water capacity of 4-7 inches and the Jiggs soil has an increased capacity of 3 to 6.5 inches. Runoff is medium to rapid and erosion is moderate to high. Both soils are deep to 40 to 60 inches.

Windy and McCarthy Stony SandyLoams (WeD) – This soil is made up of equal parts Windy and McCarthy. Windy soil has rapid permeability with a water capacity of 5 to 7 inches. The McCarthy soil is moderately rapid permeability with a 4 to 6 inch water capacity. Runoff is medium to rapid in this soil type and the erosion is moderate to high. Bedrock is at a depth of 40- 60 inches. Stones cover 1-3% of the surface.

Windy and McCarthy Very Stony SandyLoams (WeD) – This soil is made up of equal parts Windy and McCarthy. Windy soil has rapid permeability with a water capacity of 5 to 7 inches. The McCarthy soil is moderately rapid permeability with a 4 to 6 inches water capacity. Runoff is rapid in this soil type and the erosion is moderate to high. Bedrock is at a depth of 40- 60 inches. Stones cover 3-10% of the surface.

Rock land (RxF) – Shallow soil, rock outcrops. Vegetation, where present, is similar to adjacent soils, except that rockland has less grass and more drought resistant species, such as Manzanita.

The primary factors influencing soil productivity to be assessed are:

1. Organic matter loss
2. Surface soil loss
3. Soil compaction
4. Growing space loss

Organic matter loss

The entire harvest area will be logged by tractor and disturbance of organic matter will occur. Throughout the harvest area there are many existing skid trails that will be utilized for this harvest. Few new skid trails will be constructed. When these skid trails are utilized organic matter will be displaced from them. To minimize disturbance, equipment will utilize designated or existing skid trails and trees will be felled to these skid trails. Replacement of organic matter will occur through logging residue, tree tops and limbs, that will be left behind after harvest and from natural needle fall. Existing skid trails not pertinent to the harvest will not be utilized.

Existing down woody material throughout the harvest area will remain. Retaining unmerchantable material in the harvest area will recruit woody material. In addition to providing wildlife habitat, leaving woody material will add organic matter to the forest floor. Increases of organic matter to the forest floor will also occur from the planned lop and scatter slash treatment throughout the entire plan area.

Surface soil loss

Surface soil loss will occur by displacement of soil from skid trail construction and log skidding. There are many existing skid trails from past harvests and the need to construct new ones is minimal. Only one new landing is planned. The loss of surface soil from construction will be slight. Surface soil loss from erosion will be nominal due to the silvicultural systems being applied, lack of road construction, and installation of waterbreaks on skid trails and landings after completion of use.

Soil Compaction

Soil compaction will occur from the tractor skidding operation. Compaction will be greatest on main skid trails. To reduce compaction over the harvest area and eliminate random wandering by equipment operators, main skid trails will be kept to the minimum needed to carry out the harvest. Skid trails will be designated prior to timber operations and equipment will be required to use designated trails, which will reduce the impact from compaction to the harvest area. Harvest activities will occur when soil moisture is low. When soils are saturated timber operations will be suspended. Timber operations will not occur during the winter period.

Growing Space Loss

Growing space loss from skid trail construction will occur, however, it will be minimal. All roads, landings, and skid trails are considered permanent. New skid trails are constructed so that they can be utilized in future harvests. The use of existing skid trails will be required. There may be a need for the construction of a few new skid trails for this harvest.

Timber may be removed within 100 feet, as measured on the surface of the ground, from the edge of the traveled surface of appurtenant roads used during the harvesting of the THP area for safety reasons (hazard, dead, dying and disease and trees that interfere with the maintenance of the road). The traveled surface of such appurtenant roads is also part of the logging area as defined in CCR 895.1 "Logging Area".

The limited road & landing construction will not significantly expand the area covered by the transportation system within the watersheds. New construction will affect less than 0.001% of the total area within the watersheds. The temporary road construction is approximately 680 feet. Any additional landings will be constructed within the existing transportation system.

D. Biological Assessment

Anadromy

There are no known anadromous salmonids within the biological assessment area. The Beal watershed is listed as a threatened and impaired for Chinook and Steelhead. No anadromous salmonids occur on LaTour nor are there historical records of observations in the Beal Creek Watershed. From information within the *Cow Creek Watershed Assessment* prepared by SHN Consulting Engineers & Geologists Inc. fall run Chinook have occurred in the lower reaches of South Cow Creek below Wagoner Canyon approximately 10 miles west of the Forest. Steelhead were reported at the crossing of South Cow Creek by Ponderosa Way, approximately 9.5 miles west of the plan boundary. Historical data indicates salmon above Wagoner Canyon were scarce due to a natural barrier in the Canyon and a dam constructed across South Cow Creek by PG&E in 1908. The barrier was removed by blasting and a fish ladder was constructed at the dam in the 1970's by the Department of Fish and Game. However, local residents state there was no significant increase in the number of fish above the dam. The Cow Creek report suggests one of the key limiting factors is adequate stream flow to provide passage of adult fish. Water is diverted from South Cow Creek for irrigation and power use during critical passage periods.

No physical barriers exist on South Cow Creek upstream of the Ponderosa Way crossing, as such Steelhead could potentially migrate upstream. It is unlikely they occur within in Bullhock creek due to low flows during the summer and fall.

From dives performed in 2000 for the fish habitat assessment of the SWAG report, only rainbow trout were observed in South Cow Creek, Old Cow Creek and Bullhock Creek on the LDSF.

Per 936.9(b) there will be no significant cumulative watershed effects on the populations and habitat of anadromous salmonids from implementation of this plan nor are any cumulative effects known. The Watershed assessment (section B) addresses sediment, thermal loading, large woody debris, and peak flow. Mitigation in the water drafting plan will prevent a take if Steelhead are present in Atkins Creek. Harvesting activities along watercourses have been conservative in the past to provide good shade cover. With the implementation of the protection afforded the watercourses in the plan coupled with the requirements of the Forest Practice act and Board of Forestry rules there should be no adverse cumulative impact to aquatic species or habitat.

Scoping

The Natural Diversity Data Base (NDDDB) was used as a scoping tool to check if any rare, threatened, endangered, or special concern species and/or their habitat are located on or surrounding the THP area. A nine quadrangle query was conducted, which included Viola 7.5 minute quad, its surrounding eight quads. Section III Item #32 contains a list of rare, threatened, endangered species, and/or their habitat that occurs within the THP area. There are no recorded occurrences of threatened or endangered species on LDSF.

Habitat types

Timber types and WHR habitat types for LDSF have been determined through aerial photo interpretation, vegetation inventory, and the use of a database program written by the Forest Staff which determines WHR types from forest inventory data. Plot data from the inventory represents a 2.5-acre area and the WHR type was determined for each plot. Within the plan area the tree size classes ranged from 3 to 5 and with a range of canopy closure from open to dense. The predominant WHR types were Sierra Mixed Conifer and White Fir 4D and 4M. WHR 5M, 5D exist in the plan area. However, these stands are scattered and do not have the continuity to qualify as late succession forest stands per rule definition. The desired forest structure on LDSF is described within *LDSF 2008 Management Plan*, "The overall goal is to maintain LDSF as a mid-seral forest type characteristic of the southern Cascades. Early and late seral stands will be represented but overall the Forest will maintain the characteristics of a mid-seral forest. This goal is not discretionary, but rather follows directly from the research and demonstration mandate for LDSF. Rather than a park or reserve, the legislated mandate for the Forest is that of a working forest property for demonstration and research purposes, serving a clientele of small to medium size land owners.

In order to remain relevant as a research forest, LDSF aims to create and maintain a wide range of forest types, ages, size classes, successional stages and structural characteristics. It is going to be very difficult to maintain pure stands of each of these characteristics on a Forest the size of LDSF. As a result, LDSF's approach will be to incorporate a continuum of types, age classes, successional stages and structures mixed within stands across the Forest as far as possible."

Snags and large down woody material are present on the THP and within the assessment area. Additional recruitment of snags and downed woody material will be accomplished through the retention of green cull trees and unmerchantable material in the forest stands.

Hardwoods

Hardwoods are not a large component of the stands on the LDSF, which is true for the THP area. The THP is located above 5400 feet in elevation, which is generally above the upper elevation limit at which oaks grow. Harvesting of oak will not occur within the THP area.

Road density

Road density, which can have a potential effect on wildlife, are moderate on LDSF and within the assessment area. The average density per section is 4 to 5 miles of seasonal and rocky seasonal roads on LDSF. Although accessible to the public, these roads receive little traffic most of the year. The only new road construction proposed is temporary and will be blocked to the standards specified in the Forest Practice Rules.

E. RECREATIONAL ASSESSMENT

The recreational activities that normally occur in the recreational assessment area is deer hunting, camping, fishing, snowmobile riding, and site seeing. Mountain bike riders occasionally use the forest but are rare and infrequent. Additionally, the forest is used by the public for fuelwood cutting. Harvesting will occur along the South Cow Creek Road. The road may be blocked to traffic for short periods of time during active timber operations. A sign will be posted on the Bateman road at the west entrance to the LDSF to warn the public of logging activities in the area and the Licensed Timber Operator will be advised to watch for recreationists and to allow thru traffic on South Cow Creek and the Bateman Road.

The primary use within the recreational assessment area is deer hunting. Impact to hunting may occur during any year the THP is operated since, for safety reasons, no hunting will be permitted in the vicinity of timber operations.

An agreement exists with the Lassen National Forest to allow the grooming of approximately 30 miles of Forest roads during the winter for snowmobile use. This recreational activity will not be adversely affected by timber operations.

F. VISUAL RESOURCE ASSESSMENT

This timber harvest cannot be seen by significant numbers of people since the harvest area is not visible from any well-traveled roads or communities. The closest paved public road is the paved section of Bateman Road, 6-1/2 miles to the west of the LDSF boundary. Adjacent ownerships are accustomed to timber production, however, one home is approximately 1/4 mile west of LDSF boundary. The harvest area cannot be viewed from the home, however, logging traffic will likely travel by the home enroute to/from Redding. There will be no adverse effect on the visual resource. The prescribed silviculture will not adversely change the visual aspect of the assessment area. The greatest visual impact will be from within the stand after harvest.

G. VEHICULAR TRAFFIC IMPACTS

Forest products from the harvest area will be hauled out over two potential routes. This will cause a slight increase in vehicular traffic.

a. Cutter Road and the Lassen National Forest Road A 16

This road network has a gravel surface with permanent culverts at watercourse crossings. Those portions of the road network which are not graveled have high coarse fragment contents in the native soil; these roads will not be used when soils are saturated. These roads will only be used during the non-winter months and a maintenance agreement and permit will be obtained prior to use for all private or federally owned roads. These roads will be graded as needed and watered during the operation (if used for log hauling).

b. Bateman Road.

This haul route will result in traveling down the Bateman Road. The Bateman Road is a private road and is graveled from Atkins Creek (end of the county road) to the harvest boundary. The one homeowner on the graveled portion of the road has posted 10 MPH signs near his home. The LTO will be advised to comply with the 10 MPH limit when passing by the home. The primary use of the road is from logging operations, recreation and access to the residence. Eleven miles of dirt and gravel roads will be used following this route. Bateman road will be graded as needed and watered during the operation (if used for log hauling).

Since the main use of these haul routes is logging traffic the impact to people who use them on a regular basis will be almost non-existent. The greatest impact from the increase in traffic will be on recreationists using these roads. Since weekend operations are not planned the impact will be minor.

H. OTHER

Climate Change and Forestry Practice

This THP complies with LDSF approved Management Plan, Mitigated Negative Declaration and Option A analysis. The following information is part of LDSF Mitigated Negative Declaration for LaTour Demonstration State Forest (SCH#2008062009) and the LDSF Management Plan:

In 2007 the State of California passed the Global Warming Solutions Act (AB 32), which set targets to reduce greenhouse gas emissions to 1990 levels by 2020 and 80 percent below 1990 levels by 2050. The California Air Resources Board was tasked with obtaining compliance with the cap through regulatory and market approaches. Planning is currently underway and definitive decisions by the Board have not yet been taken, however, it appears that forests will play a significant role in non-regulated strategies to meet targets. This is anticipated to occur both as offsets within a cap and trade system and through voluntary measures.

Recognized strategies to mitigate GHG emissions and enhance terrestrial sequestration include reforestation, forest management and fuels treatments to avoid catastrophic losses. LDSF will contribute to the targets of AB32 by increasing the resiliency of the Forest to catastrophic mortality by improving the general health of stands, pre-fire implementation of a shaded fuel break and maintenance of firefighting infrastructure such as roads, signage and water sources. The long-term carbon stocks of the Forest are anticipated to increase over time. For example, the Option A Plan indicates that the timber inventory on the Forest will increase from about 22.7 MBF per acre in 2005 to 34.4 MBF per acre in 2105.

Forest products produced from LDSF will sequester carbon during their life cycle. Biomass fuels produced on the Forest also provide an opportunity to replace fossil fuels with an alternative energy source that is close to carbon neutral.

This analysis evaluates whether climate change and greenhouse gas (GHG) issues related to management of LDSF have the potential to be a significant environmental effect, either on a project basis or cumulatively. Table 2 summarizes estimated net carbon dioxide sequestration levels under proposed management at LDSF over a 100-year planning interval¹. The analysis shows substantial positive carbon sequestration benefits. Proposed management at LDSF will sequester a net CO₂ equivalent of 3,773,000 tons of carbon at the end of 100 years.

Table 2. Estimated carbon sequestration at LDSF over the next 100 years.

1	2	3	4	5	6	7
Current standing inventory	CO ₂ stored in current standing timber ²	Standing inventory at end of 100-year planning interval	CO ₂ stored in standing timber at end of 100-year planning interval	Total harvest over 100-year planning interval	Total CO ₂ sequestered in forest products at end of 100-year planning interval	Total net CO ₂ sequestered at end of 100-year planning interval (4-2+6)
MBF*	M* tons	MBF	M tons	MBF	M tons	M tons
196,931	1,575	308,096	2,465	360,460	2,884	3,773

* MBF is thousand board feet and M is thousand.

Accounting for emissions from the Forest includes vehicles and buildings used by the Department that are associated with management. It also includes emissions from harvesting and manufacturing. We chose to do the downstream accounting. This will be the most conservative accounting approach because we are not including the negative substitution effect that occurs when alternative higher-GHG-impact building materials such as steel and concrete are used instead of wood products. Emissions from vehicles and buildings are estimated as follows:

Vehicles: 0.02 thousand (M) tons per year x 100-year planning horizon = 2 M tons

Building: 0.00003 M tons per year x 100-year planning horizon = 0.003 M tons

This is a total of 2.003 M tons for the 100-year planning horizon.

Harvesting emissions include in-woods emissions from equipment and vehicles and transportation to a mill. Mill emissions estimates from processing are included because long-term storage of wood products is included in the analysis. Mill emissions include sawing, drying, energy generation, and planing. Also, transport to final destination is included. The entire life cycle for green-dried lumber is included (Puettmann and Wilson 2005). This results in a total emission estimate of 0.13 metric tons CO₂ equivalent per thousand board feet (MBF).

Given the total harvest of 360,460 MBF over the 100-year planning horizon in table 1, this equates to 46,859 tons of CO₂ equivalent from harvesting emissions. Including vehicle and building emissions, the total GHG emissions estimate for LDSF is 46,861 tons of CO₂ equivalents.

These emissions including full life-cycle of wood, vehicle, and building emissions, represent 1.24 percent of the total carbon sequestered (column 7 in Table 2). The conclusion from the above analysis is that there is a substantial positive carbon sequestration benefit and a net negative emission of GHGs at LDSF under the guidance of the Project. Orders of magnitude more biomass is being conserved than is being harvested. In other words, the management plan proposes to harvest less biomass (and to emit less CO₂) than growth.

Climate change science is still in its infancy. There are likely wide error bars around the above estimates, given the general level of the analysis and the relatively new estimation equations in the literature. The result that positive sequestration benefits exceed emissions by orders of magnitude however, lends validity to the general conclusion that sequestration will be much greater than emissions. Our conclusion is also supported by estimates from the Air Resources Board, which indicate that forest land use in California results in a net decrease in atmospheric carbon, not an increase (http://www.arb.ca.gov/cc/inventory/data/tables/net_co2_flux_2007-11-19.pdf).

Since the net amount of carbon that would be sequestered under the Project is greatly higher than the amount of carbon that will be released by LDSF management activities, there are no potential significant adverse environmental impacts, single or cumulative. In fact, significant beneficial impacts of net carbon sequestration will occur.

² A conversion factor of 8.0 was used to convert thousand board feet to tons of CO₂ including soil root biomass, duff, litter, canopy and non-bole tree parts (Smith et al, 2002, GTR NE-298).

² A 100-year look-ahead period is necessary in forested ecosystems, where trees can take more than 50 years to reach maturity. The 100-year planning interval allows a minimum period necessary to evaluate long-term steady-state behavior of forested ecosystem while not exceeding the range of applicability of mathematical simulation models.

I. CONCLUSION

This harvest will not have any significant cumulative impacts to the resources.

I. REFERENCE MATERIAL

PERSONS:


Pete Johnson, Forester
W.M. Beatty and Associates
P.O. Box 898
Redding, CA 96099 Ph: (530) 243-2783


Kelly Dreesmann, Division Chief
CAL FIRE
875 Cypress Ave
Redding, CA 96001, (530) 225-2418

LITERATURE AND MODELS

California Wildlife Habitat Relationship System Version 7.0
Cow Creek Watershed Assessment, prepared by SHN Consulting Engineers & Geologist, Inc.
LaTour Demonstration State Forest Watershed Monitoring Project, Stream Channel and Fish Habitat Assessment, Final Report, prepared by Sacramento Watershed Action Group.
A Guide to Wildlife Habitats of California California Wildlife - Volumes II & III
Pine Marten - Pacific Fisher Study Phase II Report 1992
Dept. of Fish and Game Natural Diversity Data Base
Soil Survey of Shasta County., U. S. Dept. of Agriculture
CDF Timber Harvest Plan Records
Aerial Photographs - Latour Demonstration State Forest
LaTour Demonstration State Forest Option A
LaTour Demonstration State Forest Management Plan 2008
Mitigated Negative Dec. (SCH# 2008062009), *LaTour Demonstration State Forest Management Plan 2008*
American Marten, Fisher, Lynx, and Wolverine: Survey Methods for their detection, U. S. Dept. of Agriculture
PSW-GTR-157.

This page is blank





AB 47 Cumulative Map

--- THP Boundary

— LDSF Boundary

- - - Watershed Assessment Area



THP 02-187 SHA



THP 08-071 SHA




THP 01-161 SHA



THP 99-253 SHA

Scale: 1 mile



SECTION V

Reference Documents

- **Adjacent Property Landowners**
- **LTO/RPF/PS/ TLO Responsibilities**
- **EHR Worksheet**
- **Soil Classification Map & Descriptions**
- **Domestic Water Letters**
- **Water Drafting Letters**
- **Copy of NOI**

Adjacent Property Owners

**Sierra Pacific Industries
Sierra Pacific Holding Company
PO Box 496014
Redding, CA 96049**

**USDA Service Center
Lassen National Forest
2550 Riverside Drive
Susanville, CA 96130**

LICENSED TIMBER OPERATOR RESPONSIBILITY ACKNOWLEDGEMENT

(As per Section 1035.3 Title 14, CCR)

Harvesting Plan Number: _____

Licensed Timber Operator Information

Name: California Department of Forestry & Fire Protection

Street Address/PO Box: 875 Cypress Ave City: Redding Zip Code: 96001

Telephone Number: 530-225-2432 LTO Number: C-1275

As the LTO listed above I acknowledge responsibility for the following:

- 1) Inform the responsible RPF or plan submitter orally or in writing of any site conditions which in The LTO's opinion prevent implementation of the approved plan and amendments.
- 2) Be responsible for the work of his or her employees and familiarize all employees with the intent and details of the operational and protection measures of the plan and amendments that apply to their work.
- 3) Keep a copy of the applicable approved plan and amendments available for reference at the site of active timber operations.
- 4) Comply with all provisions of the Act, Board rules and regulations and the applicable approved plan, and amendments.
- 5) Attend an on-site meeting or discuss archaeological site protection with the RPF or supervised designee familiar with on-site conditions.
- 6) To inquire of the plan submitter, timberland owner or their authorized agent, RPF who wrote the plan, or the supervised designee, if any mitigation measures or specific operating instructions are contained in the Confidential Archaeological Addendum or any other confidential addendum to the plan.
- 7) Provide the RPF responsible for professional advice throughout the timber operations, the name, address and phone number of an on-site contact employee authorized by the LTO to receive RPF advice.
- 8) Keep the RPF responsible for professional advice throughout the timber operations advised of the status of timber operation activity.
- 9) Within 5 days before, and not later than the startup of timber operations, notify the RPF of the start of timber operations.
- 10) Within 5 days before, and not later than the shutdown of a timber operation, the LTO shall notify the RPF of the shutdown of timber operations.
- 11) Cease operations, except for emergencies and operations needed to protect water quality, upon receipt of written notice of an RPF's withdrawal of professional services from the plan. The LTO shall not resume operations until written notice is received from the plan submitter that another RPF has visited the site and accepts responsibility for providing advice regarding the plan as the RPF of record.

In addition to the above, I have specific responsibilities for the following: _____

I have read and understand my responsibilities as the Licensed Timber Operator summarized above and specifically described in 14 CCR 1035.3. I certify that I will fulfill my legal obligation as stated in the forest practice rules, and agree to fulfill my responsibilities as described above.

LTO Signature: *Michael Beck* Title: Adm & Inv't Forester

Responsible On-Site Contact (if different)

Name: Gabriel Schultz *[Signature]*

Printed Name: Gabriel Schultz Date: 8/25/09

Street Address/PO Box #: 875 Cypress Ave City: Redding
Zip: 96001

Telephone Number: 530-225-2506

**REGISTERED PROFESSIONAL FORESTER (RPF) RESPONSIBILITY
ACKNOWLEDGEMENT**

(As per Section 1035.1 Title 14, CCR)

RPF Certified to Provide Professional Advice:

Name: Gabriel Schultz

Street Address/PO Box: 875 Cypress Ave City: Redding Zip Code: 96001

Telephone Number: 530-225-2506 RPF Number: 2749

As of January 1, 2001, I have read and understand my responsibility as RPF, as described under 14 CCR 1035.1(a-g). I agree to fulfill my responsibilities as an RPF as they pertain to this plan.

☒ Yes ☐ No I have been retained as the RPF, available to provide professional advice to the licensed timber operator and timberland owner upon request throughout the active timber operations regarding: (1) the plan, (2) the forest practice rules, (3) and other associated regulations pertaining to timber operations.

RPF Signature: 

PLAN SUBMITTER RESPONSIBILITY ACKNOWLEDGEMENT

(As per Section 1035 Title 14, CCR)

Plan Submitter

Name: Cal Fire / California Department of Forestry and Fire Protection

Street Address/PO Box: 875 Cypress Ave City: Redding Zip Code: 96001

Telephone Number: 530-225-2505

As of January 1, 2001, I have read and understand my responsibilities as Plan Submitter as described under 14 CCR 1035. I certify that I have fulfilled my legal obligation as stated in the forest practice rules, and agree to fulfill my responsibility as the plan submitter as it pertains to this plan.

☒ Yes ☐ No I have retained the services of an RPF to provide professional advice to the LTO and timberland owner upon request throughout active timber operations regarding: (1) the plan, (2) the forest practice rules, (3) and other associated regulations pertaining to timber operations.

☐ Yes ☒ No I have authorized the timberland owner, _____ to perform the services of a professional forester, understanding that the services will be provided personally on lands owned by the timberland owner.

Plan Submitter Signature: 

TIMBERLAND OWNER RESPONSIBILITY ACKNOWLEDGEMENT

(As per Section 1035(d)(2)(B) Title 14, CCR)

Timberland Owner

Name: Cal Fire / California Department of Forestry and Fire Protection

Street Address/PO Box: 875 Cypress Ave City: Redding Zip Code: 96001

Telephone Number: 530-225-2505

I have read and understand my responsibilities as timberland owner as described under 14 CCR 1035(d)(2)(A - C). I certify that I have fulfilled my legal obligation as stated in the forest practice rules, and agree to fulfill my responsibilities as the timberland owner as it pertains to this plan.

I understand that I have been authorized by the plan submitter to perform the services of a professional forester pursuant to the Landowner exception in Public Resources Code Section 757, and such services will be personally performed only on those lands that I own.

Timberland Owner's Signature: 

ESTIMATED SURFACE SOIL EROSION HAZARD

RM-87 (4/84)

**STATE OF CALIFORNIA
BOARD OF FORESTRY**

SOIL FACTORS				FACTOR RATING BY AREA		
A. SOIL TEXTURE	Fine	Medium	Coarse	D	E	F
1. DETACHABILITY	Low	Moderate	High	23	23	23
Rating	1-9	10-18	19-30			
2. PERMEABILITY	Slow	Moderate	Rapid	1	1	1
Rating	5-4	3-2	1			

D - LgE > 30%
slopeE - LhE < 30%
slopeF - LhE > 30%
slope**B. DEPTH TO RESTRICTIVE LAYER OR BEDROCK**

	Shallow	Moderate	Deep			
	1"-19"	20"-39"	40"-60 (+)			
Rating	10-6	5-3	3-1	4	4	4

**C. PERCENT SURFACE COARSE FRAGMENTS GREATER THAN 2 MM IN SIZE INCLUDING
ROCKS OR STONES**

	Low	Moderate	High				FACTOR RATING BY AREA		
	(-)10-39%	40-70%	71-100%				D	E	F
Rating	10-6	5-3	2-1	5	5	5			
➡							33	33	33
SUBTOTAL									

II. SLOPE FACTOR

Slope	5-15%	16-30%	31-40%	41-50%	51-70%	71-80%(+)			
Rating	1-3	4-6	7-10	11-15	16-25	26-35	13	3	13

III. PROTECTIVE VEGETATIVE COVER REMAINING AFTER DISTURBANCE

	Low	Moderate	High			
	0-40%	41-80%	81-100%			
Rating	15-8%	7-4	3-1	4	4	4

IV. TWO-YEAR, ONE-HOUR RAINFALL INTENSITY (Hundredths Inch)

	Low	Moderate	High	Extreme			
	(-) 30-39	40-59	60-69	70-80 (+)			
Rating	1-3	4-7	8-11	12-15	12	12	12
TOTAL SUM OF FACTORS ➡					62	52	62

EROSION HAZARD RATING

<50	50-65	66-75	>75			
LOW (L)	MODERATE (M)	HIGH (H)	EXTREME (E)			
THE DETERMINATION IS ➡				H	M	H

ESTIMATED SURFACE SOIL EROSION HAZARD

RM-87 (4/84)

STATE OF CALIFORNIA BOARD OF FORESTRY

I. SOIL FACTORS

				FACTOR RATING BY AREA		
A. SOIL TEXTURE	Fine	Medium	Coarse	A	B	C
1. DETACHABILITY	Low	Moderate	High	23	23	23
Rating	1-9	10-18	19-30			
2. PERMEABILITY	Slow	Moderate	Rapid	1	1	1
Rating	5-4	3-2	1			

A – WeD > 30% slope

B – WfE < 30% slope

C – LgE < 30% slope

B. DEPTH TO RESTRICTIVE LAYER OR BEDROCK

Rating	Shallow	Moderate	Deep	3	3	4
	1"-19"	20"-39"	40"-60 (+)			
	10-6	5-3	3-1			

C. PERCENT SURFACE COARSE FRAGMENTS GREATER THAN 2 MM IN SIZE INCLUDING ROCKS OR STONES cx

Rating	Low	Moderate	High				FACTOR RATING BY AREA		
	(-)10-39%	40-70%	71-100%						
	10-6	5-3	2-1	5	5	5	A	B	C
<div><div></div><div>SUBTOTAL</div></div>							32	32	33


II. SLOPE FACTOR

Slope	5-15%	16-30%	31-40%	41-50%	51-70%	71-80%(+)	13	3	6
Rating	1-3	4-6	7-10	11-15	16-25	26-35			


III. PROTECTIVE VEGETATIVE COVER REMAINING AFTER DISTURBANCE

Rating	Low	Moderate	High	4	4	4
	0-40%	41-80%	81-100%			
	15-8%	7-4	3-1			

IV. TWO-YEAR, ONE-HOUR RAINFALL INTENSITY (Hundredths Inch)

Rating	Low	Moderate	High	Extreme	12	12	12
	(-) 30-39	40-59	60-69	70-80 (+)			
	1-3	4-7	8-11	12-15			
TOTAL SUM OF FACTORS 					61	51	55

EROSION HAZARD RATING

<50	50-65	66-75	>75	H	M	M
LOW (L)	MODERATE (M)	HIGH (H)	EXTREME (E)			
THE DETERMINATION IS 						

gravel is 15 to 30 percent throughout the profile. This soil is well drained, and permeability is moderately slow. Runoff is very slow, and the hazard of erosion is none to slight. Available water capacity is 7 to 9 inches. Roots can penetrate to a depth of more than 60 inches.

Included with this soil in mapping were small areas of Honn, Molinos, and Vina soils.

This Los Robles soil is used mainly for irrigated and dryland hay and as irrigated pasture. Small areas are used for crops. Capability unit IIs-4(17); range site, not assigned; woodland suitability group, not assigned; wildlife group 2.

Lyonsville Series

The Lyonsville series consists of well-drained soils that are underlain by light-colored volcanic rock. These soils are on uplands in the eastern part of the survey area from the Tehama County line to Big Bend. Slopes range from 10 to 70 percent. Elevation ranges from 2,500 to 6,500 feet. The annual precipitation is 40 to 50 inches, and the average annual air temperature is about 44° F. the 32° F. growing season is 100 to 150 days, and the 28° F. growing season is 125 to 175 days. The vegetation is mixed conifers and shrubs.

In a representative profile the surface layer is brown, strongly acid very stony sandy loam and pale-brown, strongly acid gravelly sandy clay loam about 18 inches thick. The subsoil is very pale brown, very strongly acid and strongly acid gravelly sandy clay loam. The substratum at a depth of 30 inches is light-gray, strongly acid very gravelly heavy sandy loam. Weathered dacite is at a depth of 33 inches.

The areas of Lyonsville soils are used as woodland and wildlife habitat and for water supply.

Representative profile of Lyonsville very stony sandy loam, 10 to 50 percent slopes, in an area of Lyonsville-Jiggs complex, 10 to 50 percent slopes, in Latour State Forest on Rim Road, 2½ miles northeast of Latour Butte Lookout in SE¼SW¼ sec. 17, T. 32 N., R. 3 E.:

O1—3 inches to 1 inch, litter from woody shrubs and conifer cover.

O2—1 inch to 0.8 inches.

A11—0 to 1 inch, brown (10YR 5/3) very stony sandy loam, dark brown (10YR 3/3) moist; strong, very fine, granular structure; soft, very friable, nonsticky and slightly plastic; many very fine roots and few fine and coarse roots; many very fine interstitial pores; strongly acid; abrupt, smooth boundary.

A12—1 to 12 inches, pale-brown (10YR 6/3) gravelly light sandy clay loam, dark grayish brown (10YR 4/2) moist; strong, very fine, granular structure; soft, very friable, nonsticky and slightly plastic; many very fine roots and few fine and coarse roots; many very fine interstitial pores; strongly acid; clear, smooth boundary.

A13—12 to 18 inches, pale-brown (10YR 6/3) gravelly sandy clay loam, dark brown (10YR 4/3) moist; strong, very fine, granular structure; soft, very friable, nonsticky and slightly plastic; common very fine roots and few fine and coarse roots; many very fine interstitial pores; strongly acid; clear, smooth boundary.

B21—18 to 25 inches, very pale brown (10YR 7/3) gravelly sandy clay loam, dark grayish brown (10YR 4/2) moist; brownish-yellow status; strong, very fine, granular structure; slightly hard, friable, nonsticky and slightly plastic; common very fine roots and few fine and coarse roots; many very fine interstitial pores;

very few thin clay films in pores; very strongly acid; abrupt, smooth boundary.

B22—25 to 30 inches, very pale brown (10YR 8/4) gravelly sandy clay loam, brown (10YR 5/3) moist; strong, very fine, granular structure; slightly hard, friable, nonsticky and slightly plastic; common very fine roots and few fine and medium roots; many very fine interstitial pores; very few thin clay films in pores; strongly acid; clear, smooth boundary.

C—30 to 33 inches, light-gray (10YR 7/2) very gravelly heavy sandy loam, brown (10YR 5/3) moist; massive; very hard, very firm nonsticky, slightly plastic; very few, fine, flattened roots; many very fine vesicular and interstitial pores; strongly acid; clear, smooth boundary.

R—33 inches, weathered dacite; some soil material in fracture planes; massive.

The A horizon ranges from 10 to 20 inches in thickness, from grayish brown or brown to light yellowish brown or pale brown in color, from gravelly sandy clay loam to very stony sandy loam in texture, and from slightly acid to strongly acid in reaction. The B2 horizon ranges from 10 to 20 inches in thickness, from light yellowish brown to very pale brown in color, from gravelly heavy sandy loam to sandy clay loam in texture, and from medium acid to very strongly acid in reaction. The C horizon ranges from 3 to 20 inches in thickness, and from gravelly sandy loam to very gravelly sandy loam in texture. Rhyolite, dacite, or andesite rock is at a depth of 20 to 60 inches. This soil is 20 to 40 inches deep in most places; however, as mapped in the Shasta Area, some areas are as deep as 60 inches over hard rock.

In Shasta County Area Lyonsville soils are mapped only in complexes or in undifferentiated units with Jiggs soils.

Lyonsville Jiggs complex, 10 to 50 percent slopes (lgE).—About 45 percent of this complex is Lyonsville very stony sandy loam, 10 to 50 percent slopes, and about 45 percent is Jiggs gravelly sandy loam, 10 to 50 percent slopes. The remaining 10 percent consists of inclusions of Windy soils. The Lyonsville and the Jiggs soil each has the profile described as representative for its respective series.

The Lyonsville soil has moderate permeability. Available water capacity is 2 to 5 inches. Weathered dacite is at a depth of 20 to 40 inches. Stones and cobblestones cover 3 to 15 percent of the surface.

The Jiggs soil has moderately rapid permeability. Available water capacity is 2 to 4 inches. Dacite is at a depth of 20 to 40 inches. Exposed dacite bedrock outcrops cover 5 to 10 percent of the surface.

Runoff is medium to rapid on the soils of this unit. The hazard of erosion is moderate to high.

The areas of these soils are used as woodland and wildlife habitat and for watershed. Capability unit VIIs-1 (22); range site, not assigned; woodland suitability group 5; wildlife group 9.

Lyonsville-Jiggs complex, deep, 10 to 50 percent slopes (lhE).—About 45 percent of this complex is Lyonsville very stony sandy loam, deep, 10 to 50 percent slopes, and about 45 percent is Jiggs gravelly sandy loam, deep, 10 to 50 percent slopes. The remaining 10 percent consists of inclusions of Windy soils and grayish-brown soils that formed on volcanic rocks. The Lyonsville and the Jiggs soil each has a profile similar to that described as representative for its respective series.

The Lyonsville soil has moderate permeability. Available water capacity is 4 to 7 inches. Stones cover 3 to 15 percent of the surface.

The Jiggs soil has moderately rapid permeability. Available water capacity is 3 to 6.5 inches. Exposed

dacite bedrock outcrops cover 5 to 10 percent of the surface.

Runoff is medium to rapid on the soils of this unit. The hazard of erosion is moderate to high. Both the Lyonsville and the Jiggs soils are 40 to 60 inches deep, which is deeper than the soils of their respective series recognized elsewhere in California.

The areas of these soils are used as woodland and wildlife habitat and for watershed. Capability unit VIc-1(22); range site, not assigned; woodland suitability group 3; wildlife group 8.

Lyonsville and Jiggs soils, 50 to 70 percent slopes (LkF).—This undifferentiated group consists of areas of Lyonsville very stony sandy loam, 50 to 70 percent slopes, and Jiggs rocky sandy loam, 50 to 70 percent slopes. The Lyonsville soil is on the lower parts of the slopes, and the Jiggs soil is on the upper or higher parts. The proportion of each soil varies from one area to another, but each soil generally makes up about 45 percent of the group. The remaining 10 percent consists mainly of inclusions of Windy soils. The Lyonsville and the Jiggs soil each has a profile similar to that described as representative for its respective series.

The Lyonsville soil has moderate permeability. Available water capacity is 2 to 5 inches. Stones cover 3 to 10 percent of the surface.

The Jiggs soil has moderately rapid permeability. Available water capacity is 2 to 4 inches. Exposed dacite bedrock outcrops cover 5 to 10 percent of the surface.

Runoff is very rapid on the soils of this group. The hazard of erosion is very high. Both soils are 20 to 40 inches deep to bedrock.

The areas of these soils are used as woodland and wildlife habitat and for watershed and recreation. Capability unit VIIc-1(22); range site, not assigned; woodland suitability group 6; wildlife group 8.

Marpa Series

The Marpa series consists of well-drained soils that are underlain by shale or slate. These soils are on uplands in the north-central part of the survey area near French Gulch, Bella Vista, and Ingot. Slopes range from 30 to 75 percent. Elevation ranges from 800 to 4,500 feet. The annual precipitation is 40 to 50 inches, and the average annual air temperature is about 56° F. The 32° F. growing season is 150 to 250 days, and the 28° F. growing season is 200 to 300 days. The vegetation is mixed conifers, oaks, and shrubs.

In a representative profile the surface layer is brown, slightly acid gravelly loam about 6 inches thick. The upper part of the subsoil is brown, slightly acid gravelly loam about 7 inches thick. The lower part of the subsoil is light-brown, strongly acid very gravelly clay loam. Fractured shale is at a depth of about 26 inches.

The areas of Marpa soils are used as woodland and wildlife habitat and for watershed.

Representative profile of Marpa gravelly loam, 50 to 75 percent slopes, about three-fourths mile north of the Mineral School near N¼ corner of sec. 31, T. 34 N., R. 1 W.:

0—1 inch to 0, litter and humus from black oak and Douglas fir.

A1—0 to 6 inches, brown (7.5YR 5/2) gravelly heavy loam, dark reddish brown (5YR 3/3) moist; moderate, medium, granular structure; soft, very friable, non-sticky and nonplastic; many fine roots, common medium roots, and few coarse roots; many very fine interstitial pores and few fine and medium tubular pores; few, thin, discontinuous clay films; slightly acid; gradual, wavy boundary.

B1—6 to 13 inches, brown (7.5YR 5/4) gravelly heavy loam, dark reddish brown (5YR 3/4) moist; weak, medium, granular structure; soft, friable, nonsticky and nonplastic; common fine and medium roots and few coarse roots; common very fine interstitial pores and few fine and medium tubular pores; common, thin, discontinuous clay films; slightly acid; gradual, wavy boundary.

B2t—13 to 26 inches, light-brown (7.5YR 6/4) very gravelly clay loam, brown (7.5YR 4/4) moist; massive; soft, friable, nonsticky and nonplastic; few fine and medium roots; common very fine interstitial pores and few fine and medium tubular pores; common, discontinuous, thick clay films; strongly acid; abrupt, smooth boundary.

R—26 inches, fractured shale.

The A horizon ranges from 3 to 14 inches in thickness, from brown to pinkish gray in color, and from slightly acid to medium acid in reaction. The B1 horizon is 7 to 12 inches thick. The B2t horizon ranges from 12 to 26 inches in thickness, from light brown to pink in color, and from gravelly loam to very gravelly clay loam in texture. Shattered shale bedrock is at a depth of 20 to 40 inches.

Marpa soils generally are near areas of Auburn, Goulding, Josephine, Maymen, Sheetiron, Sites, and Stonyford soils.

Marpa gravelly loam, 30 to 50 percent slopes (McE).—This soil has moderate permeability. Runoff is rapid, and the hazard of erosion is high. Available water capacity is 2.5 to 6 inches. Fractured shale is at a depth of 20 to 40 inches.

Included with this soil in mapping were areas of Josephine, Maymen, and Sheetiron soils.

This Marpa soil is used as woodland and wildlife habitat and for watershed. Capability unit VIc-1(22); range site, not assigned; woodland suitability group 3; wildlife group 8.

Marpa gravelly loam, 50 to 75 percent slopes (McG).—This soil has the profile described as representative for the series. Permeability is moderate. Runoff is very rapid, and the hazard of erosion is very high. Available water capacity is 2.5 to 6 inches. Fractured shale is at a depth of 20 to 40 inches.

Included with this soil in mapping were small areas of Josephine, Maymen, and Sheetiron soils.

This Marpa soil is used as woodland and wildlife habitat and for watershed. Capability unit VIIc-1(22); range site, not assigned; woodland suitability group 6; wildlife group 8.

Maymen Series

The Maymen series consists of somewhat excessively drained soils that are underlain by sedimentary or metasedimentary rock. These soils are on uplands in the western part of the survey area near French Gulch, Ono, and Platina. Slopes range from 30 to 80 percent. Elevation ranges from 1,000 to 4,500 feet. The annual precipitation is 30 to 40 inches, and the average annual air temperature is about 56° F. The 32° F. growing season is 150 to 200 days, and the 28° F. growing season is 200 to 300 days. The vegetation is shrubs and a sparse cover of annual grasses and forbs.

more than 5 feet. The substratum is mottled, but otherwise the profile is similar to that described as representative for the series. This soil is moderately well drained. Permeability is moderate. Water ponds on the surface, and erosion is not a hazard. Available water capacity is 9.5 to 11 inches. Roots can penetrate to a depth of more than 60 inches.

Included with this soil in mapping were small areas of Honn, Los Robles, and Molinos soils and areas of other Vina soils.

This Vina soil is used for irrigated hay and as irrigated pasture. Small areas are used for other irrigated crops and for orchards. Capability unit IIw-2 (17, 22); range site, not assigned; woodland suitability group, not assigned; wildlife group 2.

Vina gravelly loam, 3 to 8 percent slopes (VgB).—This soil has a profile similar to the one described as representative for the series, except that the content of gravel is 15 to 30 percent throughout the profile. This soil is well drained. Permeability is moderate. Runoff is slow, and the hazard of erosion is slight. Available water capacity is 6 to 8 inches. Roots can penetrate to a depth of more than 60 inches.

Included with this soil in mapping were areas of Honn, Los Robles, and Molinos soils.

This Vina soil is used for irrigated and dryland hay and as irrigated pasture. Small areas are used as dryland pasture. Capability unit IIe-1 (17, 18); range site, not assigned; woodland suitability group, not assigned; wildlife group 2.

Wet Alluvial Land

Wet alluvial land (Wc) is somewhat poorly drained or poorly drained, is dark colored, and is loamy or clayey. It is nearly level to gently sloping and is in drainageways and basins in the central part of the survey area, mainly on terraces southeast of Anderson. Elevation ranges from 400 to 500 feet. The annual precipitation is about 25 inches, and the average annual air temperature is about 62° F. The 32° F. growing season is 200 to 250 days, and the 28° F. growing season is 300 to 325 days. The vegetation is sedges, wiregrass, cattail, and willows.

Permeability is slow. Runoff is slow, and the hazard of erosion is slight. Available water capacity is 6 to 9 inches. Roots can penetrate to a depth of 36 to 48 inches.

Wet alluvial land generally is near areas of Perkins, Churn, Reiff, and Moda soils.

This land type is used as pasture. The quality of forage is poor and consists mainly of rushes and sedges. In places production can be improved by careful irrigation management of adjoining fields and by improving surface drainage. Capability unit IIIw-5 (17); range site, not assigned; woodland suitability group, not assigned; wildlife group 2.

Windy Series

The Windy series consists of well-drained soils that are underlain by basic volcanic rock. These soils are on uplands in the eastern part of the survey area from Viola to Latour State Forest and Hatchet Mountain. Slopes range from 0 to 75 percent. Elevation ranges from 4,000 to 7,000 feet. The annual precipitation is 40 to 50 inches, and the average annual air temperature is about 44° F.

The 32° F. growing season is 100 to 150 days, and the 28° F. growing season is 150 to 175 days. The vegetation is mixed conifers and brush.

In a representative profile the surface layer is very dark grayish-brown, strongly acid stony sandy loam and loamy sand about 8 inches thick. It is underlain by brown, very strongly acid sandy loam about 6 inches thick. The subsoil is light yellowish-brown, very strongly acid very gravelly sandy loam about 34 inches thick. Basic volcanic rock is at a depth of about 48 inches.

The areas of windy soils are used as woodland (fig. 8) and wildlife habitat and for watershed.

Representative profile of Windy stony sandy loam in an area of Windy and McCarthy stony sandy loams, 0 to 30 percent slopes, in Latour State Forest about 2 miles northwest of McMullen Mountain in E $\frac{1}{4}$ sec. 3, T. 32 N., R. 2 E.:

A11—0 to 4 inches, very dark grayish-brown (10YR 3/2) stony sandy loam, black (10YR 2/1) moist; strong, very fine, granular structure; soft, very friable, nonsticky and nonplastic; many fine roots; many very fine interstitial pores; much charcoal; strongly acid; clear, smooth boundary.

A12—4 to 8 inches, very dark grayish-brown (10YR 3/2) loamy sand, very dark brown (10YR 2/2) moist; moderate, very fine, granular structure; soft, very friable, nonsticky and nonplastic; many fine roots; many fine interstitial pores; strongly acid; clear, wavy boundary.

A3—8 to 14 inches, brown (10YR 5/3) sandy loam, very dark brown (10YR 2/3) moist; moderate, very fine, granular structure; soft, very friable, nonsticky and nonplastic; many very fine roots; many very fine interstitial pores; very strongly acid; gradual, smooth boundary.

B21—14 to 30 inches, light yellowish-brown (10YR 6/4) very gravelly sandy loam, dark brown (10YR 3/3) moist; massive; soft, very friable, nonsticky and nonplastic; few coarse roots; many very fine interstitial pores and common very fine tubular pores; very strongly acid; discontinuous, gradual, and broken boundary.

B22—30 to 48 inches, light yellowish-brown (10YR 6/4) very gravelly sandy loam, dark yellowish brown (10YR 4/4) moist; massive; soft, very friable, nonsticky and nonplastic; few coarse roots; many very fine interstitial pores and common very fine tubular pores; very strongly acid; discontinuous, broken boundary.

R—48 inches, basic volcanic rock.

The A horizon ranges from 10 to 20 inches in thickness, from very dark grayish brown to brown in color, from stony to very stony sandy loam or loam in texture, and from slightly acid to very strongly acid in reaction. The B horizon ranges from 20 to 40 inches in thickness, from light yellowish brown to very pale brown in color, from very gravelly sandy loam to loam in texture, and from medium acid to very strongly acid in reaction. Basic volcanic rock is at a depth of 40 to 60 inches. All areas of this soil are stony or very stony.

Windy soils generally are near areas of Jiggs, Lyonsville, and McCarthy soils. They are mapped in this survey area only in undifferentiated groups or complexes with McCarthy and Nanny soils.

Windy and McCarthy stony sandy loams, 0 to 30 percent slopes (WeD).—This unit is made up of Windy and McCarthy soils in about equal proportions. Windy stony sandy loam has north-facing and east-facing slopes, and McCarthy stony sandy loam has south-facing and west-facing slopes. Small areas of shallower soils were included in mapping.

The Windy soil has the profile described as representative for the Windy series. Permeability is rapid. Available water capacity is 5 to 7 inches.




Figure 8.—Profile of Windy stony sandy loam, 0 to 30 percent slopes, in a wooded area.

The McCarthy soil has a profile similar to the one described as representative for the McCarthy series. It has moderately rapid permeability. Available water capacity is 4 to 6 inches.

Runoff is medium to rapid on the soils of this unit. The hazard of erosion is moderate to high. Bedrock is at a depth of 40 to 60 inches. Stones cover 1 to 3 percent of the surface.

490-726-74-8

The areas of these soils are used as woodland and wildlife habitat and for watershed. Capability unit VIe-1(22); range site, not assigned; woodland suitability group 5; wildlife group 8.

Windy and McCarthy very stony sandy loams, 30 to 50 percent slopes (WfE).—This unit is made up of Windy and McCarthy soils in about equal proportions. Windy very stony sandy loam has north-facing and east-facing slopes, and McCarthy very stony sandy loam has south-facing and west-facing slopes. Included in mapping were small areas of shallower soils. The Windy and the McCarthy soil each has a profile similar to that described as representative for its respective series.

The Windy soil has rapid permeability, and its available water capacity is 5 to 7 inches.

The McCarthy soil has moderately rapid permeability, and its available water capacity is 4 to 6 inches.

Runoff is rapid on the soils of this unit. The hazard of erosion is high. Bedrock is at a depth of 40 to 60 inches. Stones cover 3 to 10 percent of the surface.

The areas of these soils are used as woodland and wildlife habitat and for watershed. Capability unit VI-1(22); range site, not assigned; woodland suitability group 5; wildlife group 8.

Windy and McCarthy very stony sandy loams, 50 to 75 percent slopes (WfG).—This unit is made up of Windy and McCarthy soils in about equal proportions. Windy very stony sandy loam has north-facing and east-facing slopes, and McCarthy very stony sandy loam has south-facing and west-facing slopes. Included in mapping were small areas of shallower soils. The Windy and the McCarthy soil each has a profile similar to the one described as representative for its respective series.

The Windy soil has rapid permeability, and its available water capacity is 5 to 7 inches.

The McCarthy soil has moderately rapid permeability, and its available water capacity is 4 to 6 inches.

Runoff is very rapid on the soils of this unit. The hazard of erosion is very high. Bedrock is at a depth of 40 to 60 inches. Stones cover 3 to 10 percent of the surface.

The areas of these soils are used as woodland and wildlife habitat and for watershed. Capability unit VII-1(22); range site, not assigned; woodland suitability group 6; wildlife group 6.

Windy and McCarthy very rocky sandy loams, 8 to 50 percent slopes (WgE).—This unit is made up of Windy and McCarthy soils in about equal proportions. Windy stony sandy loam has north-facing and east-facing slopes, and McCarthy stony sandy loam has south-facing and west-facing slopes. Included in mapping were areas of shallower soils. The Windy and the McCarthy soil each has a profile similar to that described as representative for its respective series.

The Windy soil has rapid permeability, and its available water capacity is 5 to 7 inches.

The McCarthy soil has moderately rapid permeability, and its available water capacity is 4 to 6 inches.

Runoff is medium to rapid on the soils of this unit. The hazard of erosion is moderate to high. Bedrock is at a depth of 40 to 60 inches. Stones cover 1 to 3 percent of the surface. Exposed bedrock outcrops cover 10 to 25 percent of the surface.

The areas of these soils are used as woodland and wild-

15 to 35 percent throughout the profile. This soil is well drained and has moderately rapid permeability. Runoff is very slow, and the hazard of erosion is none to slight. Available water capacity is 7 to 8.5 inches. Roots can penetrate to a depth of more than 60 inches.

Included with this soil in mapping were areas of soils that have a cobbly loam or a gravelly sandy loam surface layer and areas of other Reiff soils.

This Reiff soil is used for irrigated hay and as irrigated pasture. A few small areas are used for other irrigated crops and for orchards. Capability unit IIs-4(17); range site, not assigned; woodland suitability group, not assigned; wildlife group 2.

Reiff gravelly loam, slightly wet, 0 to 3 percent slopes (RoA).—This soil has a profile similar to the one described as representative for the series, except that it has mottles that are faint to distinct and yellowish brown to pale brown. Also, the content of gravel is 15 to 35 percent throughout the profile. Permeability is moderately rapid in this soil. Runoff is very slow or water ponds on the surface. Erosion is not a hazard. Available water capacity is 7 to 8.5 inches. Roots can penetrate to a depth of more than 60 inches.

Included with this soil in mapping were areas of Anderson soils and of other Reiff soils.

This Reiff soil is used for irrigated hay and as irrigated and dryland pasture. Small areas are used for other irrigated crops. Capability unit IIw-2(17, 22); range site, not assigned; woodland suitability group, not assigned; wildlife group 2.

Riverwash

Riverwash (Rw) is nearly level or gently sloping and is in stream channels and adjacent areas. It is subject to continuous or frequent flooding, so plants do not become established. Most of this land type is in the central part of the survey area from Cottonwood to Redding and Bella Vista. Elevation ranges from 350 to 600 feet. Willow, cottonwood, interior live oak, valley oak, and wild grape and blackberry plants are along the channel banks in most places.

This land type is excessively drained and has rapid permeability. Runoff is very slow, and the hazard of erosion is very high.

Riverwash has little or no potential for farming. It is a source of sand and gravel for roads and for construction work. It is also used for recreation. Capability unit VIIIw-1(17); range site, not assigned; woodland suitability group, not assigned; wildlife group 10.

Rock Land

Rock land (Rx) is nearly level to very steep and is on uplands in the mountainous parts of the survey area. Elevation ranges from 700 to 6,900 feet. Rock outcrops cover 25 to 90 percent of the surface. The appreciable amount of rock outcrop and the very shallow soil in the areas submerge the other characteristics of the soil. The rock consists of shale, sandstone, conglomerate, limestone, greenstone quartz diorite, andesite, basalt, rhyolite, schist, gneiss, serpentine, or peridotite.

The vegetation, where present, is similar to that on adjacent soils, except that Rock land has less grass and more

drought-resistant plant species, such as canyon live oak, manzanita, toyon, buckeye, and yerba santa.

Small areas of adjacent soils commonly were included with this unit in mapping. Rock land is used as watershed and for recreation. Capability unit VIII-1(15, 18, 22); range site, not assigned; woodland suitability group, not assigned; wildlife group 8.

Rubble Land

Rubble land (Ry) is nearly level to very steep and is on uplands in the eastern part of the survey area southeast of Round Mountain. Elevation ranges from 3,000 to 5,000 feet. Stones and boulders cover 90 percent or more of the surface. The vegetation is open stands of shrubs, white fir, Douglas-fir, and incense cedar.

This land type generally is near areas of Coliaset, Cone, and McCarthy soils. Included in mapping were small areas of these soils.

This land type generally is used for water supply. A few trees grow in places. Capability unit VIII-1(15, 18, 22); range site, not assigned; woodland suitability group, not assigned; wildlife group 8.

Sehorn Series

The Sehorn series consists of well-drained soils that are underlain by sedimentary rocks. These soils are on uplands in the eastern and western parts of the survey area along the tributaries of Cow Creek east of Millville and Bella Vista and in the Bald Hills south of Ono. Slopes range from 3 to 70 percent. Elevation ranges from 800 to 1,600 feet. The annual precipitation is 25 to 35 inches, and the average annual air temperature is about 62° F. The 32° F. growing season is 200 to 250 days, and the 28° F. growing season is 275 to 325 days. The vegetation is grasses or, in a few places, grass-oak.

In a representative profile the surface layer is light olive-brown, slightly acid silty clay about 20 inches thick. The substratum is mottled, grayish-brown, light olive-brown, and yellowish-brown, neutral silty clay loam. Weathered calcareous shale is at a depth of about 28 inches.

The areas of Sehorn soils are used as range, dryland pasture, and wildlife habitat and for watershed.

Representative profile of Sehorn very stony silty clay, 8 to 30 percent slopes, eroded, about 5 miles northeast of Millville, 300 feet south of N¼ corner of sec. 20, T. 32 N., R. 2 W.:

A11—0 to 1 inch, grayish-brown (2.5Y 5/2) very stony heavy clay loam, olive brown (2.5Y 4/4) moist; weak, thin, platy structure; very hard, firm, slightly sticky and plastic; many very fine roots; many very fine tubular pores; cracks about ½ inch to 1½ inches wide; medium acid; abrupt, smooth boundary.

A12—1 to 11 inches, light olive-brown (2.5Y 5/4) silty clay, olive brown (2.5Y 4/4) moist; strong, very coarse, prismatic structure; extremely hard, very firm, sticky and very plastic; common very fine roots; common very fine tubular pores; slightly acid; clear, smooth boundary.

A13—11 to 20 inches, light olive-brown (2.5Y 5/4) silty clay, olive brown (2.5Y 4/4) with vertical streaks of yellowish brown, ½ to ¾ inch wide, along cracks moist; strong, very coarse, prismatic structure; extremely hard, very firm, slightly sticky and very plastic; com-

**DEPARTMENT OF FORESTRY AND FIRE PROTECTION**

875 CYPRESS AVE
REDDING, CA 96001
Website: www.fire.ca.gov
(530) 225-2506



July 28, 2009

**USDA Service Center
Lassen National Forest
2550 Riverside Drive
Susanville, CA 96130**

To Whom it May Concern:


LaTour Demonstration State Forest is in the process of preparing a Timber Harvesting Plan (THP). The location of the THP is in Shasta County, in Sections 13 and 24, T 32N, R 2 E, and Sections 17, and 18, T 32 N, R 3 E; Mount Diablo Base Meridian. The THP is approximately 13 air miles east of the community of Whitmore, California, 22 miles south of Burney and Seventeen miles northeast of Lassen Volcanic National Park.

The California Code of Regulations, Title 14 Section 1032.10 requires that the THP Submitter provide notice by letter to all other landowners within 1000 feet downstream of the THP Boundary whose ownership adjoins or includes a Class I, II or IV watercourse which receives surface drainage from the proposed timber operations.

This notice is to request information about surface domestic water use from South Cow Creek, Beal Creek and Upper Battle Creek and within 1000 feet of the THP boundary. If you have any information about domestic water use in the area specified, please contact Bruce Beck, Ben Rowe or Gabriel Schultz within 10 days of receipt of this notice at the address or phone number listed below.


Thank you very much,

GABRIEL V. SCHULTZ
Forester I RPF#2749
Shasta-Trinity Unit, Redding
875 Cypress Ave.
Redding, CA 96001
530-225-2506



Location: 040° 37' 03.03" N 121° 40' 37.87" W NAD27
Caption: LDSF, Buck Butte THP
T 32 N, R 2 3 E, Sect 7, 13, 17, 18, 24.

Name: VIOLA
Date: 6/22/2009
Scale: 1 inch equals 1333 feet



VICINITY MAP
LATOUR DEMONSTRATION STATE FOREST

Scale 1:100,000

0111
324

Whitmore
35

THP
AREA

Manzanita

Chalk Mountain
1794

Bonnie
Craggs

Cavite

**DEPARTMENT OF FORESTRY AND FIRE PROTECTION**

875 CYPRESS AVE
REDDING, CA 96001
Website: www.fire.ca.gov
(530) 225-2506



July 10, 2009

**Sierra Pacific Industries
Sierra Pacific Holding Company
PO Box 496014
Redding, CA 96049**

To Whom it May Concern:


LaTour Demonstration State Forest is in the process of preparing a Timber Harvesting Plan (THP). The location of the THP is in Shasta Country, in Sections 13 and 24, T 32N, R 2 E, and Sections 17, and 18, T 32 N, R 3 E; Mount Diablo Base Meridian. The THP is approximately 13 air miles east of the community of Whitmore, California, 22 miles south of Burney and Seventeen miles northeast of Lassen Volcanic National Park.

The California Code of Regulations, Title 14 Section 1032.10 requires that the THP Submitter provide notice by letter to all other landowners within 1000 feet downstream of the THP Boundary whose ownership adjoins or includes a Class I, II or IV watercourse which receives surface drainage from the proposed timber operations.

This notice is to request information about surface domestic water use from South Cow Creek, Beal Creek and Upper Battle Creek and within 1000 feet of the THP boundary. If you have any information about domestic water use in the area specified, please contact Bruce Beck, Ben Rowe or Gabriel Schultz within 10 days of receipt of this notice at the address or phone number listed below.


Thank you very much,

GABRIEL V. SCHULTZ
Forester I RPF#2749
Shasta-Trinity Unit, Redding
875 Cypress Ave.
Redding, CA 96001
530-225-2506



Location: 040° 37' 03.03" N 121° 40' 37.87" W NAD27
 Caption: LDSF, Buck Butte THP
 T 32 N, R 23 E, Sect 7, 13, 17, 18, 24.

Name: VIOLA
 Date: 6/22/2009
 Scale: 1 inch equals 1333 feet



VICINITY MAP
LATOUR DEMONSTRATION STATE FOREST
Scale 1:100,000

khorn
T32N

71
Whitmore
T33N

Manzanita
T32N



DEPARTMENT OF FORESTRY AND FIRE PROTECTION

875 CYPRESS AVE
REDDING, CA 96001
Website: www.fire.ca.gov
(530) 225-2506



July 10, 2009

Carl J. and Jo Ann Davis
PO Box 142
Whitmore, CA 96069

Certified Mail, Return Receipt Requested
7007 2560 0003 2533 2735

Dear Jack & Jo:


As part of LaTour's next timber harvest plan that I am preparing, the licensed timber operator will once again, as many years in the past, be using Roaring Springs as a drafting location to maintain Bateman Road. The use of Roaring Springs is required for both dust abatement and maintaining the roads surface in a stable condition. The Fore Practice Rules require you to be included as a timberland owner on LaTour Demonstration State Forest "Buck Butte" timber harvest plan. Your inclusion as a timberland owner assumes no responsibility for timber operations on your part and is for water drafting only as Roaring Springs along Bateman Road. Water drafting is considered timber operations per Public Resource Code 4527 and as such all timberland owners where water drafting will occur must be included in the plan.

Per Public Resource Code 4582, if the person filing the plan is not the owner of the timberland, the plan submitter shall notify the timberland owner by certified mail that the plan has been submitted and shall certify that mailing to the Department.

As the Registered Professional Forester preparing this plan I am required to inform you of your responsibilities as the timberland owner. The Department of Forestry & Fire Protection has a right-of-way agreement for the use of Bateman Road. This agreement requires the Department to maintain the road in good condition. As such, the Department will assume the erosion control maintenance for the use of the water drafting location used under this THP.

All water drafting operations performed under this THP on your property will conform to the Forest Practice Act and Board of Forestry Rules. Note that the Department of Forestry & Fire Protection has adjudicated water rights to Roaring Springs under the Cow Creek Adjudication Decree No. 38577 of the Superior Court for Shasta County.

Sincerely,



GABRIEL V. SCHULTZ
Forester I RPF#2749
Shasta-Trinity Unit, Redding
875 Cypress Ave.
Redding, CA 96001
530-225-2506

U.S. Postal ServiceTM
CERTIFIED MAILTM RECEIPT
 (Domestic Mail Only; No Insurance Coverage Provided)
 For delivery information visit our website at www.usps.com

OFFICIAL USE

Postage	\$ 44.
Certified Fee	2.80
Return Receipt Fee (Endorsement Required)	2.30
Restricted Delivery Fee (Endorsement Required)	
Total Postage & Fees	\$ 5.54

Postmark Here

Sent to
 Carl E. Bann Davis
 Street, Apt. No.,
 or PO Box No. P.O. Box 142
 City, State, ZIP+4[®] Whitmore, CA 96069
 PS Form 3800, August 2005 See Reverse for Instructions

STATE OF CALIFORNIA
 DEPARTMENT OF
 FORESTRY AND FIRE PROTECTION
 RESOURCE MANAGEMENT
 875 CYPRESS AVENUE
 REDDING, CA 96001

SENDER: COMPLETE THIS SECTION

- Complete items 1, 2, and 3. Also complete item 4 if Restricted Delivery is desired.
- Print your name and address on the reverse so that we can return the card to you.
- Attach this card to the back of the mailpiece, or on the front if space permits.

1. Article Addressed to:
 Carl and Ann Davis
 P.O. Box 142
 Whitmore, CA 96069

2. Article Number
 (Transfer from service) 7007 2560 0003 2533 2735
 PS Form 3811, February 2004 Domestic Return Receipt

CERTIFIED MAIL



7007 2560 0003 2533 2735

COMPLETE THIS SECTION ON DELIVERY


A. Signature ☐ Agent ☐ Addressee

B. Received by (Printed Name) C. Date of Delivery

D. Is delivery address different from item 1? ☐ Yes ☐ No
 If YES, enter delivery address below:

3. Service Type ☒ Certified Mail ☐ Express Mail
☐ Registered ☐ Return Receipt for Merchandise
☐ Insured Mail ☐ C.O.D.

4. Restricted Delivery? (Extra Fee) ☐ Yes ☐ No



Carl and Ann Davis
 P.O. Box 142
 Whitmore, CA 96069

**DEPARTMENT OF FORESTRY AND FIRE PROTECTION**

875 CYPRESS AVE
REDDING, CA 96001
Website: www.fire.ca.gov
(530) 225-2506



July 10, 2009

Pete Johnson
C/O W.M. Beaty & Associates
Brooks Walker et. Al.
PO Box 990898
Redding, CA 96099

Certified Mail, Return Receipt Requested
7007 2560 0003 2533 2742

Dear Pete:

As discussed, W.M. Beaty & Associated will be included as a timber land owner on LaTour Demonstartions State Forest "Buck Butte" timber harvest plan. The inclusion of W.M. Beaty & Associates is for water drafting at one location along Bateman Road at Atkins Creek in the Brooks Walker ownership. Water drafting are considered timber operations per Public Resources Code 4527 and as such all timberland owners must be included in the plan.

Per Public Resource Code 4582, if the person filing the plan is not the owner of the timberland, the plan submitter shall notify the timberland owner by certified mail that the plan has been submitted and shall certify that mailing to the Department.

As the Registered Professional Forester preparing this plan I am required to inform you of your responsibilities as the timberland owner. LaTour Demonstration State Forest will assume the erosion control maintenance for the use of the water drafting location used under this THP. The Department of Forestry & Fire Protection has a right of way agreement for the use of the Bateman Road. This agreement requires the Department to maintain the road in good condition.

All water drafting operations performed under this THP on property managed by W.M. Beaty & Associates will conform to the Forest Practice Act and Board of Forestry Rules and you Programmatic Streambed Alteration Agreement with the Department of Fish & Game.

Sincerely,



GABRIEL V. SCHULTZ
Forester I RPF#2749
Shasta-Trinity Unit, Redding
875 Cypress Ave.
Redding, CA 96001
530-225-2506

Pete Johnson
C/o Wm Beaty & Associates
Brooks Walker et. AL.
P.O. Box 996898
Redding, CA 96099

2422 EES2 E000 09.52 2002 77

PART OF PLAN

Pages 78-80 left intentionally blank

FOR ADMIN. USE ONLY
Amendments-date & S or M**TIMBER HARVESTING PLAN**STATE OF CALIFORNIA
DEPARTMENT OF FORESTRY
AND FIRE PROTECTION
RM-63 (02-03)

FOR ADMIN. USE ONLY

THP No. **2-09-084-SHA (4)**Dates Rec'd **OCT 07 2009**THP Name: **Rim Road**

(In the CDF FPS, this is "THP Description")

If this is a Modified THP, check box: ☐Date Filed **OCT 17 2009**Date Approved **DEC 1 12 2009**Date Expires **DEC 1 0 2012**Extensions 1) ☐ 2) ☐

This Timber Harvesting Plan (THP) form, when properly completed, is designed to comply with the Forest Practice Act (FPA) and Board of Forestry and Fire Protection rules. See separate instructions for information on completing this form. NOTE: The form must be printed legibly in ink or typewritten. The THP is divided into six sections. If more space is necessary to answer a question, continue the answer at the end of the appropriate section of your THP. If writing an electronic version, insert additional space for your answer. Please distinguish answers from questions by *font change*, **bold** or underline.

SECTION I - GENERAL INFORMATION

This THP conforms to my/our plan and upon approval, I/we agree to conduct harvesting in accordance therewith. Consent is hereby given to the Director of Forestry and Fire Protection, and his or her agents and employees, to enter the premises to inspect timber operations for compliance with the Forest Practice Act and Forest Practice Rules.

1. TIMBER OWNER(S) OF RECORD: Name:
- California Department of Forestry and Fire Protection**

Address **875 Cypress Avenue**City **Redding** State **CA** Zip **96001** Phone **(530) 225-2505**Signature Bruce A. Beck 10-6-09 Date

NOTE: The timber owner is responsible for payment of a yield tax. Timber Yield Tax information may be obtained at the Timber Tax Section, MIC: 60, State Board of Equalization, P.O. Box 942879, Sacramento, California 94279-0060; phone 1-800-400-7115; BOE Web Page at <http://www.boe.ca.gov>.

2. TIMBERLAND OWNER(S) OF RECORD: Name:
- California Department of Forestry and Fire Protection**

Address **875 Cypress Avenue**City **Redding** State **CA** Zip **96001** Phone **(530) 225-2505**Signature Bruce A. Beck 10-6-09 Date

3. TIMBERLAND OWNER(S) OF RECORD:
- Brooks Walker et al. C/O W. M. Beaty & Associates (Water drafting only)**

Address: **P.O. Box 990898**City **Redding** State **CA** Zip **96099-0898** Phone **(530) 243-2783**Signature: See attached letter Section V Date: _____**RECEIVED****OCT 07 2009****REDDING
FOREST PRACTICE**

Section 1

Rim Road THP

^ TIMBERLAND OWNER(S) OF RECORD: **Carl J. & Jo Ann Davis** (*Water drafting only*)

Address: **P.O. Box 142**

City **Whitmore** State **CA** Zip **96069** Phone **none**

Signature: See attached letter Section V Date: _____

3. LICENSED TIMBER OPERATOR(S): Name **California Department of Forestry and Fire Protection** Lic. No. **C1275**
(If unknown, so state. You must notify CDF of LTO prior to start of operations)

Address **875 Cypress Avenue**

City **Redding** State **CA** Zip **96001** Phone **(530) 225-2505**

Signature *Bruce W Beck* *10-6-09* Date

4. PLAN SUBMITTER(S): Name: **California Department of Forestry and Fire Protection**

Address **875 Cypress Avenue**

City **Redding** State **CA** Zip **96001** Phone **(530) 225-2505**

(Submitter must be from 1, 2, or 3 above. He/she must sign below. Ref. Title 14 CCR 1032.7 (a))

Signature *Bruce W Beck* *10-6-09* Date

Section 1

Rim Road THP

5. a. List person to contact on-site who is responsible for the conduct of the operation. If unknown, so state and name must be provided for inclusion in the THP prior to start of timber operations.

Name **The Plan Submitter or designated RPF will notify CAL FIRE of responsible person prior to start of operations.**

Address

City State Zip Phone

- b. ☒ Yes ☐ No Will the timber operator be employed for the construction and maintenance of roads and landings during conduct of timber operations? If no, who is responsible?

Work

c. Who is responsible for erosion control maintenance after timber operations have ceased and until certification of the Completion Report? If not the LTO, then a written agreement must be provided per 14 CCR 1050 (c).

The Licensed Timber Operator. Pursuant to 14 CCR 936.9(p), "The erosion control maintenance period on permanent and seasonal roads and associated landings that are not abandoned in accordance with 14 CCR 923.8 shall be three years."

6. a. Expected date of commencement of timber operations:

☒ date of THP conformance, or ☐ (date)

- b. Expected date of completion of timber operations:

☒ 3 years from date of THP conformance, or ☐ (date)

7. The timber operation will occur within the:

- ☐ COAST FOREST DISTRICT ☐ The Tahoe Regional Planning Authority Jurisdiction
☐ Southern Subdistrict of the Coast F. D. ☐ A County with Special Regulations, identify:
☐ SOUTHERN FOREST DISTRICT ☐ Coastal Zone, no Special Treatment Area
☐ High use subdistrict of the Southern F. D. ☐ Special Treatment Area(s), type and identify
☒ NORTHERN FOREST DISTRICT
☐ Other

8. Location of the timber operation by legal description: covered by USGS 7.5 minute Quad. **Jacks Backbone CA 1995**
 Base and Meridian: ☒ Mount Diablo ☐ Humboldt ☐ San Bernardino

Section (Optional)	Township	Range	Acreage	County	Assessor's Parcel Number
6	32N	3E	143	Shasta	
7	32N	3E	57	Shasta	

TOTAL ACREAGE **200** (Logging Area Only)

Planning Watershed: CALWATER Version, Identification Number, and Name

Version 2.2 Cal Water Planning Watersheds		
Name	Number	Acres w/in watershed
Huckleberry	5507.320102	7
Beal	5507.310103	193

Section 1

Rim Road THP

9. ☐ Yes ☒ No Has a Timberland Conversion been submitted? If yes, list expected approval date or permit number and expiration date if already approved.
10. ☐ Yes ☒ No Is there an approved Sustained Yield Plan for this property? Number _____ Date app. _____
☐ Yes ☒ No Has a Sustained Yield Plan been submitted but not approved? Number _____ Date sub. _____
11. ☐ Yes ☒ No Is there a THP or NTMP on file with CDF for any portion of the plan area for which a Report of Satisfactory Stocking has not been issued by CDF?
 If yes, identify the THP or NTMP number(s): _____
☐ Yes ☒ No Is there a contiguous even aged unit with regeneration less than five years old or less than five feet tall? If yes, explain. Ref. Title 14 CCR 913.1 (933.1, 953.1) (a)(4).
12. ☒ Yes ☐ No Is a Notice of Intent necessary for this THP?
☒ Yes ☐ No If yes, was the Notice of Intent posted as required by 14 CCR 1032.7 (g)?
13. RPF preparing the THP: Name **Benjamin C. Rowe** RPF Number **2686** ✓
 Address **875 Cypress Avenue**
 City **Redding** State **CA** Zip **96001** Phone **(530) 225-2508**
- a. ☐ Yes ☒ No I have notified the plan submitter(s), in writing, of their responsibilities pursuant to 14 CCR 1035 of the Forest Practice Rules.
☐ Yes ☒ No I have notified the timber owner and the timberland owner of their responsibilities for compliance with the Forest Practice Act and rules, specifically the stocking requirements of the rules and the maintenance of erosion control structures of the rules.

The timberland is owned by the California Department of Forestry and Fire Protection and managed by the LaTour Demonstration State Forest (LDSF). Mr. Bruce Beck is the manager of LDSF and is the Plan Submitter.

- b. ☒ Yes ☐ No I will provide the timber operator with a copy of the portions of the approved THP as listed in 14 CCR 1035 (f). If "no", who will provide the LTO a copy of the approved THP?

I or my supervised designee will meet with the LTO prior to commencement of operations to advise of sensitive conditions and provisions of the plan pursuant to 14 CCR 1035.2.

- c. I have the following authority and responsibilities for preparation and administration of the THP and timber operation. (Include both work completed and work remaining to be done):

I am responsible for the preparation of the THP including layout, flagging of WLPZ's, designation of timber to be harvested or retained and any additional work deemed necessary for plan approval. Additionally it is my responsibility to administer the operations described in the THP and explain to the LTO his responsibilities to ensure conformance with the requirements of the plan and the Forest Practice Act and Rules.

I will be present, or ensure that that my designee is present, on the logging area at a sufficient frequency to know the progress of operations and to advise the LTO and timberland owner, but not less than once during the life of the plan.

I will immediately furnish written notification to the LTO, the plan submitter, and the Department of a decision to withdraw professional services from the plan.

- d. Additional required work requiring an RPF, which I do not have the authority or responsibility to perform:
 NONE

Section 1

Rim Road THP

e. After considering the rules of the Board of Forestry and Fire Protection and the mitigation measures incorporated in this THP, I have determined that the timber operation:

- ☐ will have a significant adverse impact on the environment. (Statement of reasons for overriding considerations contained in Section III).
- ☒ will not have a significant adverse impact on the environment.

Registered Professional Forester: I certify that I, or my supervised designee, personally inspected the THP area, and this plan complies with the Forest Practice Act, the Forest Practice Rules and the Professional Foresters Law. If this is a Modified THP, I also, certify that: 1) the conditions or facts stated in 14 CCR 1051 (a) (1) - (16) exist on the THP area at the time of submission, preparation, mitigation, and analysis of the THP and no identified potential significant effects remain undisclosed; and 2) I, or my supervised designee, will meet with the LTO at the THP site, before timber operations commence, to review and discuss the contents and implementation of the Modified THP.

Signature

Byron C Rowe

Date

10/6/09

SECTION II - PLAN OF TIMBER OPERATIONS

NOTE: If a provision of this THP is proposed that is different than the standard rule, the explanation and justification should normally be included in Section III unless it is clearer and better understood as part of Section II.

14. a. Check the Silvicultural methods or treatments allowed by the rules that are to be applied under this THP. Specify the option chosen to demonstrate Maximum Sustained Production (MSP) according to 14 CCR 913 (933, 953) .11. If more than one method or treatment will be used show boundaries on map and list approximate acreage for each.

<input type="checkbox"/> Clearcutting	ac.	<input type="checkbox"/> Shelterwood Prep. Step	ac.	<input type="checkbox"/> Seed Tree Seed Step	ac.
		<input type="checkbox"/> Shelterwood Seed Step	ac.	<input type="checkbox"/> Seed Tree Removal Step	ac.
		<input type="checkbox"/> Shelterwood Removal Step	ac.		
<input checked="" type="checkbox"/> Selection	142 ac.	<input type="checkbox"/> Group Selection	ac.	<input type="checkbox"/> Transition	ac.
<input type="checkbox"/> Commercial Thinning	ac.	<input type="checkbox"/> Road Right of Way	ac.	<input type="checkbox"/> Sanitation Salvage	ac.
<input type="checkbox"/> Special Treatment Area	ac.	<input type="checkbox"/> Rehab. of Understocked Area	ac.	<input type="checkbox"/> Fuelbreak	ac.
<input type="checkbox"/> Alternative	ac.	<input checked="" type="checkbox"/> Variable retention	55 ac.	<input checked="" type="checkbox"/> Other	3 ac.

meadow Restoration

Total acreage **200** ac.: Explain if total is different from that in 8. MSP option chosen: (a) ☒ (b) ☐ (c) ☐

THP 2-02-187 SHA South Cow THP

- b. If Selection, Group Selection, Commercial Thinning, Sanitation Salvage or Alternative methods are selected the post harvest stocking levels (differentiated by site if applicable) must be stated. Note mapping requirements of 1034 (x) (12).

Selection: Immediately upon completion of operations the area shall meet the stocking standards of CCR 933.2(a)(2)(A)(2), 75 square feet per acre of basal area shall be retained for Site III lands. The residual stand shall contain sufficient 18 inch DBH trees to meet at least the 15 sq/ft basal area, size, and phenotypic quality of tree requirement specified under the seed tree method as specified in CCR 933.1(c)(1)(A)(1.). Post harvest stocking will be met with group A species.

- c. ☐ Yes ☒ No Will evenage regeneration step units be larger than those specified in the rules (20 acres tractor, 30 acres cable)? If yes, provide substantial evidence that the THP contains measures to accomplish any of subsections (A) - (E) of 14 CCR 913 (933, 953) .1 (a) (2) in Section III of the THP. List below any instructions to the LTO necessary to meet (A) - (E) not found elsewhere in the THP. These units must be designated on map and listed by size.
- d. Trees to be harvested or retained must be marked by or marked under the supervision of the RPF. Specify how the trees will be marked and whether harvested or retained.

All harvest trees shall be marked in Orange paint with a horizontal stripe near breast height and a mark at the stump. A sample area will be marked prior to the preharvest inspection.

- ☐ Yes ☒ No Is a waiver of marking by the RPF requirement requested? If yes, how will LTO determine which trees will be harvested or retained? If yes and more than one silvicultural method, or Group Selection is to be used, how will LTO determine boundaries of different methods or groups?

- e. Forest products to be harvested:

Sawlogs, cull logs, chips, pulp logs, and fuel-wood, poles.

- f. ☐ Yes ☒ No Are group B species proposed for management?
☐ Yes ☒ No Are group B or non-indigenous A species to be used to meet stocking standards?
☐ Yes ☒ No Will group B species need to be reduced to maintain relative site occupancy of A species?

If any answer is yes, list the species, describe treatment, and provide the LTO with necessary felling and slash treatment guidance. Explain who is responsible and what additional follow-up measures of manual treatment or herbicide treatment are to be expected to maintain relative site occupancy of A species. Explain when a licensed Pest Control Advisor shall be involved in this process.

g. Other instructions to LTO concerning felling operations

Check all road location flagging, watercourse flagging, WLPZ boundary flagging, EEZ and ELZ flagging, and skid trail flagging prior to the commencement of any falling operations. Have the responsible RPF or supervised designee replace any flagging that is incomplete or unclear.

Trees designated for removal within the EEZ or ELZ shall be directionally felled towards the perimeter and away from the protection zone and endlined, so as to keep heavy equipment out of the protection zone. In the ELZ of Class III watercourses, trees may be felled bridging the watercourse and endlined from outside the ELZ. The purpose of this measure is to allow for trees that if not directionally felled across the ELZ would fall into the ELZ or damage the residual stand.

- h. ☒ Yes ☐ No Will artificial regeneration be required to meet stocking standards?
- i. ☐ Yes ☒ No Will site preparation be used to meet stocking standards? If yes, provide the information required for a site preparation addendum, as per 14 CCR 915.4 (935.4, 955.4).

Site Preparation Addendum per 14 CCR 935.4 (a)-(h) & Regeneration Plan

- a) Site preparation within the Variable Retention (VR) unit may occur, but will not be required to meet stocking.
 - b) Methods of site preparation may include manual slashing of sub-merchantable unharvested material, brushraking logging slash and brush into burn piles, and contour ripping.
 - c) Mechanical equipment – excavator, bulldozer with rippers.
 - d) All retention trees in the dispersed retention area have been marked with a white stripe at dbh and all clusters within the aggregate retention area have been identified with red and white stripped flagging. All site preparation activities shall stay out of the retention clusters and retention trees shall not be removed. Site preparation activities are prohibited within the ELZ of the Class III watercourse.
 - e) No exceptions or alternatives to the standard rules are requested.
 - f) The Variable Retention Unit is the only area where site preparation may occur.
 - g) LTO shall be amended into the plan prior to the start of any site preparation.
 - h) All mechanical site preparation shall be conducted between May 1 and November 15
 - i) Pile construction and burning shall adhere to Item 31 within this THP.
 - j) Unit shall be planted with group A species within two years of completion of operations.
- j. If the rehabilitation method is chosen provide a regeneration plan as required by 14 CCR 913 (933, 953) .4 (b).

PESTS

15. a. ☐ Yes ☒ No Is this THP within an area that the Board of Forestry and Fire Protection has declared a Zone of Infestation or Infection, pursuant to PRC 4712 - 4718? If yes, identify feasible measures being taken to mitigate adverse infestation or infection impacts from the timber operation. See 14 CCR 917 (937, 957) .9 (a).
- b. ☒ Yes ☐ No If outside a declared zone, are there any insect, disease or pest problems of significance in the THP area? If yes, describe the proposed measures to improve the health, vigor, and productivity of the stand(s).

Located throughout the THP area and adjacent to the THP on the Lassen National forest, there are pockets of Red Fir that are heavily infected with dwarf mistletoe and *Cytospora spp.* Additionally the Western White pine on the THP is infected with blister rust and is experiencing a heavy die off.

HARVESTING PRACTICES

16. Indicate type of yarding system and equipment to be used:

- | GROUND BASED* | CABLE | SPECIAL |
|---|--|--|
| a. <input checked="" type="checkbox"/> Tractor, including end/long lining | d. <input type="checkbox"/> Cable, ground lead | g. <input type="checkbox"/> Animal |
| b. <input checked="" type="checkbox"/> Rubber tired skidder, Forwarder | e. <input type="checkbox"/> Cable, high lead | h. <input type="checkbox"/> Helicopter |
| c. <input checked="" type="checkbox"/> Feller buncher | f. <input type="checkbox"/> Cable, Skyline | i. <input type="checkbox"/> Other |
- * All tractor operations restrictions apply to ground based equipment.

17. Erosion Hazard Rating: Indicate Erosion Hazard Ratings present on THP. (Must match EHR worksheets)

☒ Low ☒ Moderate ☐ High ☐ Extreme

If more than one rating is checked, areas must be delineated on map down to 20 acres in size (10 acres for high and Extreme EHRs in the Coast District).

18. Soil Stabilization: In addition to the standard waterbreak requirements describe soil stabilization measures or additional erosion control measures to be implemented and the location of their application. See requirements of 14 CCR 916.7 (936.7, 956.7), and 923.2 (943.2, 963.2) (m), and 923.5 (943.5, 963.5) (f).
1. Stabilization measures shall be selected that will prevent significant soil loss or sediment transport into Class II and Class III waters and may include, but need not be limited to, mulching, rip-rapping, grass seeding, or chemical stabilizers. Preference to which stabilization measure to be used, if the need occurs, shall be based upon on site conditions and the availability of treatment materials. If appropriate for the site, mulching will be the method of choice.
 2. Mulch shall consist of straw or other material that is less than 3 inches in diameter (i.e. logging slash or brush). Straw mulch shall cover > 90% of the exposed area at an applied depth of > 2 inches. If logging slash or brush is used for mulch it shall be compacted by equipment and cover 90% of the exposed area.
 3. Where the undisturbed natural ground cover cannot effectively protect beneficial uses of water from timber operations, the ground shall be treated by measures including, but not limited to, seeding, mulching, or replanting, in order to retain and improve its natural ability to filter sediment, minimize soil erosion, and stabilize banks of watercourses and lakes. Treatments shall meet the standards described in item 1 and 2 above.

4. Waterbreaks shall be constructed as soon as practical upon conclusion of use of skid trails, roads, and landings, which do not have permanent and adequate drainage facilities, or drainage structures.

The maximum distance between waterbreaks on all roads and skid trails within the THP area shall not exceed the following standards except where natural drainage will occur, i.e., low spots, draws, and depressions. In these areas, any berm on the downhill side of the road or skid trail shall be removed to allow drainage and a drainage facility shall not be constructed.

Road or Trail Gradient (%)	10 or Less	11-25	26-50
Low EHR	300 ft	200 ft.	150 ft.
Moderate EHR	200 ft.	150 ft.	100 ft.

Waterbreaks shall be cut diagonally a minimum of 6 inches into the firm roadbed or skid trail surface and shall have a continuous firm embankment of at least 6 inches in height immediately adjacent to the lower edge of the waterbreak cut.

Waterbreaks shall be located to allow water to be discharged into some form of vegetative cover, duff, slash, rocks, or less erodible material wherever practical, and shall be constructed to provide for unrestricted discharge at the lower end of the waterbreak so that water will be discharged and spread in such a manner that erosion and sediment transport shall be minimized. Where waterbreaks cannot effectively disperse surface runoff, including where waterbreaks on roads and skid trails cause surface runoff to be concentrated on down-slopes, roads, or skid trails, other erosion control methods, as described in 1 above, shall be installed as needed to comply with 14 CCR 934.

5. Soil stabilization of logging roads - Permanent drainage facilities (rolling dips or drivable waterbars) shall be constructed on appurtenant seasonal roads used for this operation. These drainage facilities shall be constructed prior to the completion of hauling on all road segments where practical. Where pre-haul drainage facilities are not feasible, the standard waterbreak construction and spacing specifications will be used.
6. All outside berms along roads created from grading or truck traffic during operations shall be pulled back onto the road surface prior to completion of use and final road grading. Where feasible, and to the extent that can reasonably be done with minor road dressing and grading, existing side-hill roads shall be outslopped.
7. The traveled surface of logging roads shall be treated to prevent waterborne transport of sediment and concentration of runoff that results from timber operations. Consequently, during timber operations, road running surfaces in the logging area shall be treated as necessary to prevent excessive loss of road surface materials by watering.
8. The erosion control maintenance period on permanent and seasonal roads and associated landings that are not abandoned in accordance with 14 CCR 943.8 shall be three years.
9. Pursuant to 14 CCR 936.9(n), exposed areas, >100 square feet, approaches to watercourse crossings between the drainage facilities closest the watercourse, and road cuts and fills within the WLPZ, and within any EEZ or ELZ designated for watercourse or lake protection, shall be treated to stabilize soils, minimize soil erosion, and prevent the discharge of sediment into waters in amounts deleterious to the beneficial uses of water. Treatments shall meet the standards described in item 1 and 2 above.

10. Timing requirements for all erosion prevention activities.

1. For areas disturbed from May 1 through October 15, treatment shall be completed prior to the start of any rain that causes overland flow across or along the disturbed surface.
2. For areas disturbed from October 16 through April 30, treatment shall be completed prior to any day for which a chance of rain of 30 percent or greater is forecast by the National Weather Service or within 10 days, whichever is earlier.
3. All tractor roads shall have drainage facilities installed as soon as practical following yarding and any day with a National Weather Service forecast of chance of rain 30 percent or more, a flash flood warning, or a flash food watch as specified in CCR 14 936.9(m).

19. ☐ Yes ☒ No Are tractor or skidder constructed layouts to be used? If yes, specify the location and extent of use:

20. ☐ Yes ☒ No Will ground based equipment be used within the area(s) designated for cable yarding? If yes, specify the location and for what purpose the equipment will be used. See 14 CCR 934.3 (e).

21.

Within the THP area will ground based equipment be used on:

- a. ☐ Yes ☒ No Unstable soils or slide areas? Only allowed if unavoidable.
- b. ☐ Yes ☒ No Slopes over 65%?
- c. ☐ Yes ☒ No Slopes over 50% with high or extreme EHR?
- d. ☐ Yes ☒ No Slopes between 50% and 65% with moderate EHR where heavy equipment use will not be restricted to the limits described in 14 CCR 914 (934, 954) .2 (f) (2) (i) or (ii)?
- e. ☐ Yes ☒ No Slopes over 50% which lead without flattening to sufficiently dissipate water flow and trap sediment before it reaches a watercourse or lake?

If "a". is yes, provide site specific measures to minimize effect of operations on slope stability below. Provide explanation and justification in section III as required per 14 CCR 914 (934, 954) .2 (d). CDF requests the RPF consider flagging tractor road locations if "a." is yes.

If b., c., d. or e. is yes:

- 1) the location of tractor roads must be flagged on the ground prior to the PHI or start of operations if a PHI is not required, and
- 2) you must clearly explain the proposed exception and justify why the standard rule is not feasible or would not comply with 14 CCR 914 (934, 954).

The location of heavy equipment operation on unstable areas or any use beyond the limitations of the standard rules must be shown on the map. List specific instructions to the LTO below.

22. ☐ Yes ☒ No Are any alternative practices to the standard harvesting or erosion control rules proposed for this plan? If yes, provide all the information as required by 14 CCR 914 (934, 954) .9 in Section III. List specific instructions to the LTO below.

23. a. ☒ Yes [] No Will timber operations occur during the winter period? If yes, complete "b, c, or d." State in space provided if exempt because yarding method will be cable, helicopter, or balloon.
- b. [] Yes ☒ No Will mechanical site preparation be conducted during the winter period? If yes, complete "d".
- c. [] I choose the in-lieu option as allowed in 14 CCR 914 (934, 954) .7 (c). Specify below the procedures listed in subsections (1) and (2), and list the site specific measures for operations in the WLPZ and unstable areas as required by subsection (3), if there will be no winter operations in these areas, so state.
- d. ☒ I choose to prepare a winter operating plan per 14 CCR 914 (934, 954) .7 (b).

The following winter operation plan is for all timber operations taking place between October 15 to May 1.

1. The harvesting activities that may occur during the operational period include but not limited to felling timber, yarding with ground-based equipment, decking logs and hauling logs. Road construction and abandonment shall not occur during the Winter Period.

WINTER OPERATING PLAN

1. The erosion hazard rating in the THP is low and moderate.
2. No mechanical site preparation is proposed during the Winter Period.
3. The yarding system is ground based.
4. The operational period may be at any time between October 15 to May 1 when dry, rainless, or hard frozen conditions exist and when soils are not saturated. Use of heavy equipment or trucks on roads and landings shall be limited to a stable operating surface. Refer to "Definitions" below for the definitions of hard frozen conditions, stable operating surface and saturated soil conditions.
5. Erosion control facilities timing. This Winter Operating Plan shall be effective from October 15 to May 1. The installation of erosion controls utilizing drainage facilities is required from October 15 to May 1 on all seasonal roads, constructed skid trails and tractor roads prior to sunset if the National Weather Service forecast is a "chance" (30% or more) of rain within the next 24 hours, a flash flood warning or flash flood watch within the next 24 hours and prior to any weekend shut down periods.
6. Precipitation - Consideration in form of rain or snow. Precipitation in the THP area is primarily in the form of snow between October 31 and April 1. Spring rains usually fall onto a substantial snow pack and snow persists until middle to late May with drifts present until mid June. No hauling or ground based operations shall occur when saturated soil conditions are present. Drainage facilities shall be kept in effective condition throughout operations conducted during the winter period.
7. Ground conditions (soil moisture condition, frozen). Use of logging roads, tractor roads or landings shall not take place at any location where saturated soil conditions exist, where a stable logging road or landing operating surface does not exist, or when visibly turbid water from the road, landing, or skid trail or inside ditch may reach a watercourse or lake.
8. Silvicultural system-ground cover. Healthy regeneration, slash, needle cast and existing ground cover will ensure adequate ground cover to dissipate rainfall impact and runoff.
9. Operations within the WLPZ. Designated harvest trees within the WLPZ of Class II watercourses are to be felled toward the perimeter of the zone and end-lined out. All watercourse crossing facilities not constructed to permanent crossing standards shall be removed before November 15.
10. Equipment use limitations. No ground-based operations shall occur during locally saturated soil conditions and shall be limited to stable operating surface. Refer to "Definitions" below for the definitions of hard frozen conditions, stable operating surface and saturated soil conditions.

11. Known Unstable Areas. No known unstable areas are within the plan area.

Definitions (14 CCR 895.1):

Low Antecedent Soil Wetness is defined as conditions not meeting the threshold of saturated soil conditions.

Hard Frozen Conditions means those frozen soil conditions where loaded or unloaded vehicles can travel without sinking into the road surfaces to a depth of more than six inches over a distance of more than 25 feet.

Saturated Soil Conditions means that site conditions are sufficiently wet that timber operations displace soils in yarding or mechanical site preparation areas or displace road and landing surface materials in amounts sufficient to cause a turbidity increase in drainage facilities that discharge into Class I, II, III, or IV waters, or in downstream Class I, II, III, or IV waters that is visible or would violate applicable water quality requirements.

In yarding and site preparation areas, this condition may be evidenced by: a) reduced traction by equipment as indicated by spinning or churning of wheels or tracks in excess of normal performance, b) inadequate traction without blading wet soil, c) soil displacement in amounts that cause visible increase in turbidity of the downstream waters in a receiving Class I, II, III, or IV waters, or in amounts sufficient to cause a turbidity increase in drainage facilities that discharge into Class I, II, III, or IV waters, or d) creation of ruts greater than would be normal following a light rainfall.

On logging roads and landing surfaces, this condition may be evidenced by a) reduced traction by equipment as indicated by spinning or churning of wheels or tracks in excess of normal performance, b) inadequate traction without blading wet soil, c) soil displacement in amounts that cause visible increase in turbidity of the downstream waters in receiving Class I, II, III, or IV waters, or in amounts sufficient to cause a turbidity increase in drainage facilities that discharge into Class I, II, III, or IV waters, d) pumping of road surface materials by traffic, or e) creation of ruts greater than would be created by traffic following normal road watering, which transports surface material to a drainage facility that discharges directly into a watercourse.

Soils or road and landing surfaces that are hard frozen are excluded from this definition.

Stable operating surface means that throughout the period of use, the operating surface of a logging road or landing does not either (1) generate waterborne sediment in amounts sufficient to cause a turbidity increase in downstream Class I, II, III, or IV waters, or in amounts sufficient to cause a turbidity increase in drainage facilities that discharge into Class I, II, III, or IV waters or, that is visible or would violate applicable water quality requirements; or (2) channel water for more than 50 feet that is discharged into Class I, II, III, or IV waters.

Winter period means the period between November 15 and April 1, except as noted under special County Rules at Title 14 CCR 925.1, 926.18, 927.1, and 965.5... (a) except as otherwise provided in the rules: (1) All waterbreaks shall be installed no later than the beginning of the winter period of the current year of timber operations. (2) Installation of drainage facilities and structures is required from October 15 to November 15 and April 1 to May 1 on all constructed skid trails and tractor roads prior to sunset if the National Weather Service forecast is a "chance" (30% or more) of rain within the next 24 hours.

Section 2
ROADS AND LANDINGS

Rim Road THP

24. Will any roads be constructed? ☐ Yes ☒ No, or reconstructed? ☐ Yes ☒ No. If yes, check items "a." through "g."
Will any landings be constructed? ☒ Yes ☐ No, or reconstructed? ☐ Yes ☒ No. If yes, check items "h." through "k."
- a. ☐ Yes ☒ No Will new or reconstructed roads be wider than single lane with turnouts?
- b. ☐ Yes ☒ No Are logging roads proposed in areas of unstable soils or known slide-prone areas?
- c. ☐ Yes ☒ No Will new roads exceed a grade of 15% or have pitches of up to 20% for distances greater than 500 feet? Map must identify any new or reconstructed road segments that exceed an average 15% grade for over 200 feet.
- d. ☐ Yes ☒ No Are roads to be constructed or reconstructed, other than crossings, within the WLPZ of a watercourse? If yes, completion of THP Item 27 a. will satisfy required documentation.
- e. ☐ Yes ☒ No Will roads be located across more than 100 feet of lineal distance on slopes over 65%, or on slopes over 50% which are within 100 feet of the boundary of a WLPZ?
- f. ☐ Yes ☒ No Will any roads or watercourse crossings be abandoned?
- g. ☐ Yes ☒ No Are exceptions proposed for flagging or otherwise identifying the location of roads to be constructed?
- h. ☐ Yes ☒ No Will any landings exceed one half acre in size? If any landing exceeds one quarter acre in size or requires substantial excavation the location must be shown on the map.
- i. ☐ Yes ☒ No Are any landings proposed in areas of unstable soils or known slide prone areas?
- j. ☐ Yes ☒ No Will any landings be located on slopes over 65% or on slopes over 50% which are within 100 feet of the boundary of a WLPZ?
- k. ☐ Yes ☒ No Will any landings be abandoned?
25. If any section in "item 24" above is answered yes, specify site-specific measures to reduce adverse impacts and list any additional or special information needed by the LTO concerning the construction, maintenance, and/or abandonment of roads or landings, as required by 14 CCR Article 12. Include required explanation and justification in THP Section III.

WATERCOURSE AND LAKE PROTECTION ZONE (WLPZ) AND DOMESTIC WATER SUPPLY PROTECTION MEASURES

26. a. ☒ Yes ☐ No Are there any watercourse or lakes which contain Class I through IV waters on or adjacent to the plan area? If yes, list the class, WLPZ or ELZ width, and protective measures determined from Table I and/or 14 CCR 916 (936, 956) .4 (c) of the WLPZ rules for each watercourse. Specify if Class III or IV watercourses have WLPZ, ELZ or both.

Class II watercourses

The Class II watercourses have been flagged with blue and white striped flagging. Consistent with 14 CCR 936.5 all of the class II watercourses have at least the minimum widths as shown in the table below.

Slope Class %	< 30%	30% - 50%
WLPZ width in feet	50 ft.	75 ft.

Pursuant to 14 CCR 936.5(e) "E", to ensure retention of shade canopy filter strip properties and the maintenance of wildlife values described in 14 CCR 936.4(b) a base mark shall be placed below the cut line of the harvest trees within the zone in advance of the PHI by an RPF or supervised designee. Additionally, pursuant to 14 CCR 936.5(e) "I" To protect water temperature, filter strip properties, upslope stability, and fish & wildlife values, at least 50% of the total canopy covering the ground shall be left in a well distributed multi-storied stand configuration composed of a diversity of species similar to that found before the start of operations. The residual overstory canopy shall be composed of at least 25% of the existing overstory conifers. All class II watercourses shall comply with 14 CCR 936.3(g) recruitment of large woody debris for instream habitat shall be provided by retaining at least two living conifers per acre at least 16 inches dbh and 50ft. tall within 50 ft.

Class III watercourses

Pursuant to 14 CCR 936.4(c)(1), Class III watercourses shall have a 25-foot ELZ on slopes less than 30% and a 50-foot ELZ on slopes greater than 30%.

Class III watercourse ELZs shall be flagged with blue and white striped flagging prior to start of operations. The ELZs shall be flagged by the RPF or supervised designee. Within the ELZ of Class III watercourses, equipment shall be allowed to operate on existing roads, prepared crossings and designated tractor road crossings. At least 50% of the understory vegetation present before timber operations shall be left living and well distributed within the ELZ to maintain soil stability. Note: "ELZ" means, "Equipment Limitation Zone" and shall be defined as follows: a) all heavy equipment is to be excluded from operating within the ELZ except on existing skid trails, skid trail crossings and existing haul roads, b) approved existing skid trails and existing skid trail crossings have been identified on the ground with yellow flagging. c) Approved skid trail crossings shall only be used when dry.

Non Classified Draw

No draws, swales, or channels shall be used as skid trails. Skid trail crossings of these non-classified draws, swales, and channels shall be kept to a minimum. Existing crossings shall be used where feasible and shall be as close to a 90-degree angle as possible.

- b. ☒ Yes ☐ No Are there any watercourse crossings that require mapping per 14 CCR 1034 (x) (7)?
 c. ☐ Yes ☒ No Will tractor road watercourse crossings involve the use of a culvert? If yes state minimum diameter and length for each culvert (may be shown on map).
 d. ☐ Yes ☒ No Is this THP Review Process to be used to meet Department of Fish and Game CEQA review requirements? If yes, attach the 1603 Addendum below or at the end of this Section II; provide the background information and analysis in Section III; list instructions for LTO below for the installation, protection measures, and mitigation measures; as per THP Form Instructions or CDF Mass Mailing, 07/02/1999, "Fish and Game Code 1603 Agreements and THP Documentation".

During the preparation of the THP, and the implementation of LaTour Demonstration State Forest's 2008 Management Plan (State Clearinghouse number 2008062009) all road segments and watercourse crossings have been evaluated and rated to the risk to water quality. The evaluation included, but not limited to, erosion potential, watercourse crossing types, frequency and placement of drainage structures, and the condition of all road watercourse crossings and drainage features. All watercourse crossings and drainage features are functioning properly.

Section 2

Rim Road THP

27. Are site specific practices proposed in-lieu of the following standard WLPZ practices?

- a. ☒ Yes ☐ No Prohibition of the construction or reconstruction of roads, construction or use of tractor roads or landings in Class I, II, III, or IV watercourses, WLPZs, marshes, wet meadows, and other wet areas except as follows:
- (1) At prepared tractor road crossings.
 - (2) Crossings of Class III watercourses which are dry at time of timber operations.
 - (3) At existing road crossings.
 - (4) At new tractor and road crossings approved by Department of Fish and Game.
- b. ☐ Yes ☒ No Retention of non-commercial vegetation bordering and covering meadows and wet areas?
- c. ☐ Yes ☒ No Directional felling of trees within the WLPZ away from the watercourse or lake?
- d. ☐ Yes ☒ No Decrease of width(s) of the WLPZ(s)?
- e. ☐ Yes ☒ No Protection of watercourses which conduct class IV waters?
- f. ☐ Yes ☒ No Exclusion of heavy equipment from the WLPZ except as follows:
- (1) At prepared tractor road crossings.
 - (2) Crossings of Class III watercourses which are dry at time of timber operations.
 - (3) At existing road crossings.
 - (4) At new tractor and road crossings approved by Department of Fish and Game.
- g. ☐ Yes ☒ No Establishment of ELZ for Class III watercourses unless sideslopes are <30% and EHR is low?
- h. ☐ Yes ☒ No Retention of at least 50% of the overstory canopy in the WLPZ?
- i. ☐ Yes ☒ No Retention of at least 50% of the understory in the WLPZ?
- j. ☐ Yes ☒ No Are any additional in-lieu or any alternative practices proposed for watercourse or lake protection?

NOTE: A yes answer to any of items "a." through "j." constitutes an in-lieu practice. If any item is answered yes, refer to 14 CCR 916 (936, 956).1 and address the following for each item checked yes:

1. The RPF shall state the standard rule;
2. Explain and describe each proposed practice;
3. Explain how the proposed practice differs from the standard practice;
4. The specific location where it shall be applied, see map requirements of 14 CCR 1034 (x) (15) and (16);
5. Provide in THP Section III an explanation and justification as to how the protection provided is equal to the standard rule and provides for the protection of the beneficial uses of water, as per 14 CCR 916 (936, 956) .1 (a). Reference the in-lieu and location to the specific watercourse to which it will be applied.

Roads within WLPZ

Though not an in-lieu practice road segments exist that are adjacent to and fall within the WLPZ of a Class II watercourse. These segments are to be used for normal vehicular traffic, and log hauling. Equipment will also be allowed to travel on these roads and perform the necessary road maintenance. Road segments are delineated on the THP Map.

The portion of the Rim Road beginning at the intersection with the Huckleberry Road and extending 300 feet to the east (segment within the WLPZ), shall not be utilized during the Winter Period unless the segment is rocked. The rock shall be a minimum 3 inches compacted depth. Rock source is the LDSF rock pit along the Batman Road.

In preparing the THP these road segments were reviewed and assessed for any negative impacts to the beneficial uses of water. There are currently no apparent negative impacts and none are anticipated as a result of the proposed operations. These road segments are well established and stable, and the watercourses appear stable with canopy cover exceeding 50%.

Section 2

Rim Road THP

28. a. ☐ Yes ☒ No Are there any landowners within 1000 feet downstream of the THP boundary whose ownership adjoins or includes a class I, II, or IV watercourse(s) which receives surface drainage from the proposed timber operations? If yes, the requirements of 14 CCR 1032.10 apply. Proof of notice by letter and newspaper should be included in THP Section V. If No, "28 b." need not be answered.
- b. ☐ Yes ☐ No Is an exemption requested of the notification requirements of 14 CCR 1032.10? If yes, an explanation and justification for the exemption must appear in THP Section III. Specify if requesting an exemption from the letter, the newspaper notice or both.
- c. ☐ Yes ☒ No Was any information received on domestic water supplies that required additional mitigation beyond that required by standard Watercourse and Lake Protection rules? If yes, list site specific measures to be implemented by the LTO.
29. ☐ Yes ☒ No Is any part of the THP area within a Sensitive Watershed as designated by the Board of Forestry and Fire Protection? If yes, identify the watershed and list any special rules, operating procedures or mitigation that will be used to protect the resources identified at risk?

HAZARD REDUCTION

30. a. ☒ Yes ☐ No Are there roads or improvements which require slash treatment adjacent to them? If yes, specify the type of improvement, treatment distance, and treatment method.
- b. ☐ Yes ☒ No Are any alternatives to the rules for slash treatment along roads and within 200 feet of structures requested? If yes, RPF must explain and justify how alternative provides equal fire protection. Include a description of the alternative and where it will be utilized below.

Within 100 feet of the edge of the traveled surface of public roads, slash created and trees knocked down by timber operations shall be treated for fire hazard reduction by lopping, piling and burning, chipping, burying or removal from the zone. All treatments, except burning, shall be completed prior to the completion of timber operations. The timing of burning shall adhere to item 31 below.

All appurtenant roads and roads within the THP boundary are public roads.

31. ☒ Yes ☐ No Will piling and burning be used for hazard reduction? See 14 CCR 917.1-.11, 937.1-.10, or 957.1-.10, for specific requirements. Note: LTO is responsible for slash disposal. This responsibility cannot be transferred.

LTO is responsible for slash disposal. Any landing slash that is not spread back onto skid trails shall be piled near the center of the landing. Piles shall not exceed 50 x 50 x 20 feet with a fire line completely around the pile that has a width at least 1.5 times the height of the pile to a maximum of 30 feet. Efforts shall be made to ensure that these piles are as compact and free of soil as practical. Material shall be piled at or near its final location to minimize the amount of movement necessary and subsequent soil deposition in the piles. Slash piles created prior to September 1 of each year shall be burned that fall when safe burning conditions occur. Slash piles created after September 1 of each year may be burned the following fall, prior to December 31, when safe burning conditions occur. See Section III, Item 31.

The local representative of the Director shall be notified in advance of the time and place of any burning of logging slash.

BIOLOGICAL AND CULTURAL RESOURCES

32. a. ☒ Yes ☐ No Are any plant or animal species, including their habitat, which are listed as rare, threatened or endangered under federal or state law, or a sensitive species by the Board, associated with the THP area? If yes, identify the species and the provisions to be taken for the protection of the species.
- b. ☐ Yes ☒ No Are there any non-listed species which will be significantly impacted by the operation? If yes, identify the species and the provisions to be taken for the protection of the species.

NOTE: See THP Form Instructions or the CDF Mass Mailing, 07/02/1999, section on "CDF Guidelines for Species Surveys and Mitigations" to complete these questions.

All trees and snags with visible nesting sites of any threatened, endangered, or board sensitive species will be left standing as prescribed under 14 CCR 939.1 and 939.2(d). If during timber operations within the critical period, the timber operator discovers a snag or tree with a nesting threatened, endangered, or board sensitive species the operator shall protect the nest tree, screen trees, perch trees and replacement trees and shall cease operations within .25 miles, and notify the RPF, the Department of Fish and Game (DFG) and Cal Fire. The RPF shall consult with DFG and develop site specific mitigations and protection measures.

LISTED:

Northern Goshawk: the nearest Northern Goshawk activity center located approximately 1 .5 miles southeast of the THP, NE ¼, Section 13, T32N, R2E. The activity center was originally located in 2001 and has been active every year since. The activity center has fledged offspring in 2001, 2002, 2005-2006. There has been 4 different nest trees all within 300 yards of each other. The THP contains habitat for the Northern Goshawks and in the event that goshawks are discovered or suspected of inhabiting the THP area, efforts will be made to verify their presence. If any goshawks are observed nesting within the THP area the LTO shall cease all operations within .25 miles of the nest and contact the RPF, CAL FIRE inspector, and DFG. Specific nest protection measures will be developed in consultation with DFG. At a minimum, all goshawk nest sites will be protected according to 14 CCR 939.3.

NON-LISTED:

Pacific Fisher (STATE CANIDATE):

On April 27, 2009 the Pacific Fisher became a candidate for listing under the California Endangered Species Act. Emergency regulations were developed by the Fish and Game Commission for this species in order to allow incidental take of fisher for specified activities including timber operations (Section 749.5, Title 14, CCR). This emergency regulation was approved by the Office of Administrative Law on April 27, 2009 and will be in effect until October 27, 2009.

The critical period for fishers is March 1 through July 31, where reproduction and caring for young occurs and when the highest potential for disturbance exists

LDSF contains habitats for the Pacific Fishers and it was detected in a 1990 furbearer presence survey. No subsequent detections have occurred. The elevation of the plan is generally considered above the range of the pacific fisher, but contains habitat for the Pacific Fisher. The plan will maintain habitat post harvest. If Pacific Fishers are observed within the THP area the LTO shall cease all operations within .25 miles of the observation site and contact the LDSF staff, CAL FIRE inspector, and DFG. The Redding DFG Timberland Planning office shall be notified of the detection and observations of the pacific fisher, including any along the appurtenant roads. The notification shall include the time, date, and map location.

Additionally observations, detections, and take shall be reported to the Department of Fish and Game, Wildlife Branch, Attn: Fisher Observations, 1812 Ninth St., Sacramento, CA 95811, or by email submission to fisherdata@dfg.ca.gov. Information reported to the Department pursuant to this

Section 2

Rim Road THP

subdivision shall include as available: a contact name; the date and location (GPS coordinate preferred) of the observation, detection, or take; and details regarding the animal(s) observed (Title 14 CCR, Section 749.5(c)).

Pine Marten: The Pine Marten has been detected in the southeastern portions of the forest (Section 24), within the assessment area, during the forest carnivore surveys conducted by LDSF staff in 2005, 2006 and 2007. The THP will maintain habitat for the Pine Marten. LDSF staff is continuing a monitoring program to evaluate the presence and continued use of known mid-sized forest carnivores.

See Section III for additional discussion of biological review.

33. ☒ Yes ☐ No Are there any snags which must be felled for fire protection or safety reasons? If yes, describe which snags are going to be felled and why.

Snags greater than 20 feet tall and 16 inches DBH which are within 100 feet of permanent or seasonal roads or landings will be felled if they lean towards the road or landing and present a safety hazard, or if they are a potential hindrance to future access for initial attack of wildfire as per 14 CCR 939.1(a)(2). Additionally, any snag thought to contain sound volume may be harvested as allowed under 14 CCR 939.1(d).

34. ☐ Yes ☒ No Are any Late Succession Forest Stands proposed for harvest? If yes, describe the measures to be implemented by the LTO that avoid long-term significant adverse effects on fish, wildlife and listed species known to be primarily associated with late succession forests.

35. ☐ Yes ☒ No Are any other provisions for wildlife protection required by the rules? If yes, describe.

All trees and snags with visible nesting sites of any non-listed raptor will be left standing as prescribed under 14 CCR 939.1 and 939.2(d). If during timber operations, the timber operator discovers a snag or tree with a nesting of any non-listed raptor the operator shall protect the nest tree, screen trees, perch trees and replacement trees, and cease operations within 500' of the nest, notify the RPF, DFG, Cal Fire. DFG shall have ten (10) days to respond and develop a consultation based on site specific conditions. If a consultation is not developed within the ten (10) days, all non-listed raptors shall have the nest tree, screen trees, perch trees, and replacement trees protected.

Other trees within the THP area that have special value to wildlife will similarly be retained. These trees have been marked with a "W" at dbh. Additionally all snags that do not met the criteria in Item 33 above shall be retained for the benefit of wildlife

36. a. ☒ Yes ☐ No Has an archaeological survey been made of the THP area?
b. ☒ Yes ☐ No Has a current archaeological records check been conducted for the THP area?
c. ☐ Yes ☒ No Are there any archaeological or historical sites located in the THP area? Specific site locations and protection measures are contained in the Confidential Archaeological Addendum in Section VI of the THP, which is not available for general public review.
37. ☐ Yes ☒ No Has any inventory or growth and yield information designated "trade secret" been submitted in a separate confidential envelope in Section VI of this THP?

38. Describe any special instructions or constraints that are not listed elsewhere in Section II.

Water drafting plan

Drafting locations are Beaver Creek crossing on South Cow Creek Road, Roaring Spring crossing on Bateman Road, Atkins Creek crossing on the Bateman Road, and Old Cow Creek crossing at Old Cow Creek campground.

It is estimated that water usage will be approximately 40,000 gallons per day distributed among the drafting locations during active timber operations.

Water drafting shall not occur at any of these locations when:

- (A) bypass flows are less than 2 cubic feet per second (cfs), or 1 cfs at Roaring Springs
- (B) pool volume at the water drafting site would be reduced by 10%, or
- (C) diversion rate exceeds 350 gallons per minute, or
- (D) diversion rate exceeds 10% of the above surface flow.

The following are requirements when drafting:

- a. Openings in perforated plate or woven wire mesh screens shall not exceed 3/32 inches (2.38 millimeters).
- b. The approach velocity (water moving through the screen) shall not exceed 0.33 feet/second.
- c. Flow in the source stream shall be at least 2 cfs.
- d. Reduction in pool volume shall not exceed 10 percent.
- e. The screen surface shall have at least 2.33 square feet of openings and the diversion rate shall not exceed 350 gallons per minute (gpm) or 10 percent of the surface flow.
- f. If an alternative screen surface area or diversion rate is desired, the following formula can be used: $\text{diversion rate (gpm)} \times 0.00676 = \text{square feet of screen surface area}$. The diversion rate can be calculated by dividing the tank capacity by the fastest filling time (i.e., 3000 gallons / 15 minutes = 200 gpm).
- g. The drafting operator shall actively observe the drafting operation. Pumping shall cease and the screen cleaned if it becomes more than 10 percent obstructed with debris.
- h. All drafting locations shall include measures (such as drip pans or absorbent fiber pads) to prevent petroleum-based products originating from vehicles from reaching surface water, groundwater, and soil. These items shall be disposed of properly.

Check all WLPZ, EEZ and ELZ flagging, and skid trail flagging prior to the commencement of any falling operations. Have the responsible RPF or supervised designee replace any flagging that is incomplete or unclear.

Review any restrictions in yarding equipment access which may cause a need for directional falling toward the lead where the logs will be yarded. Trees designated for removal within the WLPZ of a watercourse shall be directionally felled away from the watercourse and longlined, so as to keep heavy equipment out of the protection zone. In the ELZ of Class III watercourses, trees may be felled bridging the watercourse and endlined from outside the ELZ. The purpose of this measure is to allow for trees that if not directionally felled across the ELZ would fall into the ELZ or damage the residual stand.

Use only designated skid trails and tractor road crossing within WLPZs. Designated skid trails and tractor road crossings are delineated with yellow flagging.

All trees marked with a "W", a "No" or a "L" shall be retained.

Review the Winter Operations Plan and the Site Preparation/Regeneration Plan Addendum

and Landings, 14 CCR 943.6.

The LTO shall carefully review the Forest Practice Rules regarding Wildlife Protection Practices contained in 14 CCR 939.2 and 939.3.

All trees and snags with visible nesting sites of eagles, hawks, owls, waterfowl, or any rare or endangered species shall be left standing.

The THP boundary has been designated in red "Sale Boundary" flagging.

The Plan submitter shall notify the Department of the commencement of timber operations at the following address:

TEHAMA-GLENN UNIT
Unit Forester
CAL FIRE
604 Antelope Boulevard
Red Bluff, CA 96080
530-528-5106

This Timber Harvesting Plan conforms to the rules and regulations of the Board of Forestry and Fire Protection and the Forest Practice Act:

By: William E. Schultz
(Signature)

December 11, 2009
(Date)

William E. Schultz, RPF #1974
(Printed Name)

Deputy Chief Forest Practice
(Title)

Rim Road THP

THP boundary

Appurtenant Roads


Drafting locations

Scale 1:30000

Contour interval: 40 feet

Magnetic Declination


16° E



Rim Road THP

Roads and Watercourses MAP

- Class II
 - Class III
 - Primary roads
 - THP boundary
 - WLPZ Road
 - Secondary roads
(all roads are seasonal)
- Scale 1:12000
- Contour interval: 40 feet




Rim Road THP


EHR MAP



THP boundary




Low



Moderate



Primary roads




Secondary roads
(all roads are seasonal)

Scale 1:12000


Contour interval: 40 feet

U R

Magnetic Declination



16° E




Rim Road THP

Silviculture Map

- | | | | |
|--|------------------|--|---|
| | THP boundary | | Selection |
| | VR aggregate | | VR dispersed |
| | Cluster location | | Meadow Restoration |
| | Primary roads | | Secondary roads
(all roads are seasonal) |

Scale 1:12000

Contour interval: 40 feet



SECTION III

Support Documentation

Feasibility of Alternatives

No significant adverse effects from the proposed operations under this THP are expected to occur. However, an analysis of THP alternatives follows.

Purpose

The legislative authority for the State Forest System is contained in Public Resources Code (PRC) §4631-4658. CAL FIRE is responsible for the management of LDSF. As part of this oversight, the LDSF staff operates under a management plan, which provides general objectives and goals. The plan is required pursuant to Public Resources Code (PRC) §4645 and Article 8 of the California Board of Forestry and Fire Protection (Board) policy.

LDSF has a management plan (SCH # 2008062009), approved by the board, which provides direction and guidance for the managed uses of forest resources with an emphasis on forest demonstration, research, recreation, maintenance of wildlife habitat, and water quality protection. Timber harvesting is one of the mechanisms used to implement forest management goals and foster maintenance and enhancement of other non-timber resources. Guided by the statutes, the Board of Forestry and Fire Protection establishes policy, which governs LDSF and other state forests. Board policy states that the primary purpose of the state forest program is to conduct innovative demonstrations, experiments, and education in forest management.

Objectives

- Demonstrate sound forest management.
- Demonstrate Board approved Variable Retention Silviculture
- Reduce fuel loading thus reducing the risks of wildfires
- Avoid the waste of timber resources
- Enhance growth and vigor of timber resources
- Improvement of the forest road system
- Improve wildlife habitat, and watershed values promoted by the resulting healthy stands

The project as proposed meets is in conformance with the 2008 LDSF Management Plan (SCH # 2008062009), LDSF's Option A for Long Term Sustained Yield (LTSY), and the Board's policy. The project also meets the following objectives:

Achieve a balance between growth and harvest over time consistent with the harvesting methods within the rules of the Board.

Harvesting the trees that are infected with Cytospora sp. and white pine blister rust. Thus improving forest health and reducing tree mortality and fuel loading.

Maintain functional wildlife habitat in sufficient condition for continued use by the existing wildlife community within the planning watershed.

Maintain growing stock, genetic diversity, and soil productivity.

Applies and gives a visual demonstration of the Variable Retention Silviculture.

Alternatives Considered

NO PROJECT

Site would remain as is.

No economic benefits would be realized.

Stand vigor would decrease do to the *Cytospora sp.* and the white pine blister rust.

Mortality not harvested would be wasted.

Increased risk to stand replacing wildfires resulting from the stand conditions and increasing fuel loads.

Forest management and timber harvest demonstrations will not be carried out.

PROJECT TIMING

The proposed project will be completed within the next 5 years.

Delaying the project to another decade was considered.

A delay of the proposed timber harvest would result in the waste of timber resources through stand mortality and allow for the continual risk of wildfire.

A delay in harvest and income timing would substantially reduce the present net worth of the proposed project.

The landowners manage their land on a 10 to 15 year cutting cycle. Delaying the project will increase the acres to be treated in future years to maintain the stand treatment schedule.

ALTERNATIVE SITE

This alternative is not necessary, as any significant negative effect from the proposed operations has been mitigated in the THP.

ALTERNATIVE SILVICULTURE

Using more even-aged silviculture prescriptions is not suitable for this THP. LDSF has an Option A plan that defines the LSY of the forest. The LSY was determined by modeling timber growth for LDSF using specific silvicultural prescriptions. The LSY was calculated primarily using un-evened aged silviculture. Even though even-aged silviculture is available to use, the minimal acres modeled are better suited for different locations on the forest, within stands of high disease and mortality, or marginal stocking.

Upon review of the alternatives considered, the proposed project is the landowner's best alternative to meet the above stated objectives

General Project Description

Location: The THP is located in Shasta County on LDSF in sections 6 and 7, T 32 N, R 3 E. The elevation of the THP ranges from 6040 feet to 6,360 feet. The THP is approximately 14 air miles east of the community of Whitmore, California, 22 miles south of Burney and Seventeen miles northeast of Lassen Volcanic National Park.

Soils and Topography

There is one predominant soil series within the harvest boundary, Windy - McCarthy stony sandy loam. Soils in the Windy-McCarthy series make up about 95% of the soil types in the plan area. Windy - McCarthy soils are made up of Windy and McCarthy soils in equal proportions. These soils are stony sandy loams with a depth of up to 60 inches. The soils are well-drained with moderate to rapid permeability.

Elevation in the harvest area ranges from 6060 to 6300 feet. The topography is varies from flat to moderately steep slopes. The average slope within the harvest units is approximately 20% but ranges from 0 to 55%.

The following are soil types that are found within the THP boundary:

<u>Soil Type</u>	<u>Slopes</u>	<u>Depth</u>	<u>Permeability</u>
Windy-McCarthy stoney sandy loam (WeD)	0-30%	40-60 inches	Mod-Rapid
Windy-McCarthy stoney sandy loam (WfE)	30-50%	40-60 inches	Mod-Rapid
Windy-McCarthy stoney sandy loam (WfG)	50-75%	40-60 inches	Mod-Rapid
Windy-McCarthy stoney sandy loam (WgE)	8-50%	40-60 inches	Mod-Rapid

Vegetation and Stand Conditions

The predominant vegetation types in the harvest area are True fir and Sierra mixed conifer. Previous management activities have resulted in the THP area having both even-aged and uneven-aged stands. Species composition of the true fir stands is predominately White fir and Red fir with a minor component of Lodgepole pine, Jeffrey pine, Sugar pine, Western White pine, and Mountain hemlock. The stocking density in the majority of the true fir stands has resulted in little vegetation or regeneration in the understory, but where stocking is less dense the understory is dominated by chinquapin.

Sierra mixed conifer stands are uneven-aged with all size classes represented. Red fir and White fir comprise approximately 50 percent of the stand, Jeffrey pine ranges from 10 to 25 percent of the stand and the Sugar pine and western white pine both comprise between 5 to 15 percent of the stand. Lodgepole pine and Mountain hemlock are also found within the mixed conifer stands. Regeneration exists in the understory especially in areas where past harvest activities have created openings in the canopy.

The disease problems observed in the harvest area largely consist of dwarf mistletoe and cytospora or fir canker. Pockets of dead trees exist in the harvest area from fir canker infection. Infection of White Pine Blister Rust is affecting intolerant sugar pine and the western white pine and is very prevalent throughout the THP. Endemic insect populations of Mountain Pine Beetle and Ips in the pine species and Scolytis in the fir were also observed.

Despite the disease problems the selection area are well stocked with an average basal area of approximately 180 square feet and ranges for 100 to 220 square feet of basal area. The target average basal area post harvest in the selection area is 120 square feet. There are two different stocking levels within the Variable Retention area. One portion has a basal area of 100 to 140 sq. feet of mature timber, with little to no regeneration in the under story. The second area is more variable with portions having less than 100 sq feet of basal area with an understory of manzanita and chinquapin, other portions are comprised with dense stands 300+ square feet of advanced regeneration to small pole sized timber, and other areas contain are uneven-aged stand with basal area ranging from 170-240 sq feet of basal area. Portions of the Variable Retention unit are heavily infected with fir canker and blister rust and it is very difficult to find a countable tree as defined by 14 CCR 895.1. Post harvest the stocking with meet the retention standards of 14 CCR 933.4 (d), and within five years following harvest the entire Variable Retention unit shall meet 300 point count as per 14 CCR 932.7(b)

Watershed and Stream Conditions

LDSF is the headwaters source of two major streams, Old Cow Creek and South Cow Creek. A Tributary to the North Fork Battle Creek and South fork Bear Creek drain small portions of the south side of LDSF.

The THP is primarily located Beal watershed (Cal Water version 2.2 #5507.320103), with approximately 5 acres within the Huckleberry Watershed (Cal Water version 2.2 #5507.320102). The primary watercourses within these watersheds are South Cow Creek and Old Cow Creek respectively. The headwaters of Bullhock Creek, a tributary to South Cow Creek, is located within the THP. Bullhock Creek changes from a Class II to a Class III watercourse just east of the Rim Road within the THP boundary. Approximately 2.5 miles downstream Bullhock Creek transitions to a Class I watercourse. There is only one other watercourse within the THP boundary and it is a Class III located near the southern portion of the THP.

South Cow Creek and Old Cow Creek contains generally complex habitat with deep pools, riffles, and boulders forming step pools. The creek appears to have good channel conditions in the lower portion of the planning watersheds and impacts from timber operations were not significant to those portions of South Cow Creek and Old Cow Creek. Further evaluation of the watercourses occurred in the summer of 2000 from the *LaTour Demonstration State Forest Watershed Monitoring Project*, Stream Channel and Fish Habitat Assessment prepared by the Sacramento Watersheds Action Group (SWAG) under contract with the Department of Forestry and Fire Protection. In this report South Cow Creek, Bullhock Creek and Old Cow Creek were assessed within LDSF boundaries.

The SWAG report evaluated the Class I reaches of all three creeks and concluded nearly all of the watercourses are stable with some instability observed at the upper reaches in the meadows and the first 300 feet of Old Cow creek where it exits LDSF. Banks were stabilized primarily by large cobbles, boulders, and riparian vegetation. Bullock Creek shows evidence the watercourse has supported large flood events. Some bank scouring, erosion and depositional features are present in the upper reaches in the Class II segment adjacent to the THP. These features are largely due to the 1997 rain-on-snow event that caused significant runoff in the watershed.

Plan addendum # 14

Selection: pursuant to 14CCR 933.2(a)(2)(A), selection will occur on 142 acres of the plan area. Three silvicultural considerations were observed within the existing stands (1) high stand density in the true fir stands (2) lack of regeneration, and (3) disease and mistletoe infection. In the selection area the average basal area is estimated at 180 square feet per acre and ranges from 100 to 220 square feet per acre. The target average basal area post harvest in the group selection area is 120 square feet, but this THP does not limit LDSF from retaining the Forest Practice Rule standards of 75 square feet. The site classification in the area to be harvested is Dunning Site III

Variable Retention: pursuant to 14CCR 933.4(d), Variable Retention will occur on 55 acres of the plan. Aggregate Retention will occur on 30 acres and Dispersed Retention will occur on 25 acres. The existing stand is declining in health and vigor. Disease problems such as dwarf mistletoe, *cytospora spp.*, and blister rust are infecting the Red Fir and Western White pine. The mistletoe and *cytospora spp.* have been transferred from the overstory to the understory. The intent of this prescription is to capture future tree mortality, improve forest health, and establish a healthy timber stand, while providing biological and structural elements of the pre-harvest stand for integration into the future stand. Retention standards shall be met immediately after harvest. The maximum retention sample size shall be 20 acres and the retention standards shall be met on each 20-acre area. The stocking standards of 14 CCR § 912.7 [932.7, 952.7](b)(1) shall be met within five years following completion of operations and retention trees, that meet the definition of "countable tree" (14 CCR 895.1) will be used to meet stocking.

Aggregate retention standards: a minimum of ten percent of the aggregate retention area shall be retained in clusters. Eleven individual clusters have been identified on the ground and flagged with red and white stripped flagging. The clusters range in size from .1 acres to .4 acres. The locations of the clusters are shown on the THP map. One or more of the following criteria was used to identify the clusters: 1) provide a visual cover/break from the Rim Road to the rest of the unit, 2) contain several trees greater than 24 inch dbh trees for snag recruitment, 3) contain snags and or large woody debris, 4) provide a brush component for the future stand, 5) contain several healthy mature seed trees of multiple species, 6) juxtaposition to other clusters, 7) advanced healthy regeneration, 8) minimal operational constraints.

Dispersed retention standards: on the 25 acres of dispersed retention area the minimum basal area retained shall be 20 percent of the Resource Conservation Standards basal area levels stated in 14 CCR 932.7(b)(2), which is 10 square feet of basal area for Site III lands. Leave trees have been designated with white paint and one or more of the following criteria was used to identify the retention trees: 1) Large live culls (decadent and deformed trees > 24 inch dbh), 2) Healthy mature seed trees, 3) Lodge pole pine > 20 inch dbh for snag recruitment, 4) juxtaposition - no spot within the harvest area shall be further than 300 feet from a retention tree, 5) species preference - White fir, Jeffery pine, western white pine, mountain hemlock, red fir.

Estimated Basal Area per Acre - Pre and Post Harvest

Species		Basal area (ft ²) by diameter class						
		0-6" dbh	7-12" dbh	13-18" dbh	19-24" dbh	25-30" dbh	31-36" dbh	37-42" dbh
White fir	Pre	5	10	25	15	12	3	1
	Post			1	3	1		
Red Fir	Pre	1	7	12	8	2	1	
	Post				1	<1		
Jeffery pine	Pre			1	1			
	Post							
Western White pine	Pre		3	12	7	3		
	Post				1	1		
Lodge pole pine	Pre	1	2	5	2			
	Post				1			
Sugar pine	Pre		2	5	10	3	1	
	Post				1	1		
Mountain Hemlock	Pre		<1					
	Post		<1					

Meadow Restoration: Approximately 3 acre of a historic seasonal wet meadow will be restored as per 14 CCR 939.15. The seasonal meadow is located at the headwaters of Bullhock Creek. Year round springs are located on the down stream edge of the meadow. The seasonally wet portion of the meadow is occupied with a very dense stand of 6 to 8 foot tall lodge pole pine. The uniform age of the Lodgepole pine and evidence of piling and burning in the past it appears that previous management has tried to restore the meadow in the past. The ground disturbance caused by the equipment used to pile the meadow caused a very suitable seed bed for the Lodgepole pine and the restoration effort failed. NO equipment will be used within the seasonal meadow. An EEZ (red and white stripped flagging) has been flagged around the meadow restoration perimeter. The Lodgepole pine stand will be hand cut and piled. To the extent feasible, the number of piles will be kept to the minimum necessary to accommodate the material created and allow for safe burning. Additionally, to the extent feasible, material shall be piled towards to the outer edge and/or outside the unit. Burning of the piles shall adhere to item 31 of the THP.

LaTour DSF has historically worked in cooperation with Redding DFG on meadow restoration projects, dating back to the 2003 South Cow Creek THP. LaTour DSF and Redding DFG staffs are continuing to work in cooperation on research and demonstrations pertaining to meadow restoration projects.

Vegetation control: control of competing vegetation may be required to insure the survival of the regeneration within the Variable Retention units. The primary competing vegetation with the regeneration is Chinquapin, manzanita, and grasses. The competing vegetation may be controlled by manual, mechanical or chemical treatments.

Mechanical treatments: All equipment utilized for the control of competing vegetation shall adhere to the protection measures described within this THP including ELZs, and the Winter Operations Plan.

Chemical treatments: The registration of herbicides in California is a CEQA equivalent process, and when applied according to the label instructions, no significant adverse impacts to wildlife and water resources should occur. Herbicides use is regulated by the Department of Pesticide Regulation (DPR) and enforced by the County Agricultural Commissioner. The use, type and the timing of the herbicide shall be determined and recommended by a Licensed Pest Control Advisor (PCA) and the application shall adhere to the PCA's recommendation, the herbicide label instructions, and the Mitigated Negative Declaration, State Clearing House (SCH) # 2008062009 for LDSF Management Plan 2008.

Plan addendum #17 - Erosion Hazard Rating (EHR)

The Soil Survey of Shasta County California and field observations were used to determine the erosion hazard rating (EHR) for this THP area. The EHR areas were delineated according to soil type and ground observations with regard to slope, ground cover, and physical characteristics. The EHRs for the THP area are low and moderate. The EHR types are delineated on the EHR Map.

Plan addendum #31 - Piling and burning for hazard reduction

The standard rules 14 CCR 937.2(a) and 937.5(b) state slash to be treated by piling and burning shall be treated no later than April 1 of the year following creation, or within 30 days following climatic access, or as justified in the plan. The piles and concentrations shall be burned at a safe time during the first wet fall or winter weather or other safe period following piling and according to laws and regulations.

An alternative to the standard rule is proposed to allow treatment of landing slash accumulations that result from the use of chipping and/or de-limbing equipment created after September 1 of each year. This material may be burned the following fall when safe burning conditions occur. This alternative practice shall be applied over the entire THP area.

This practice differs from the standard practice in that piles will remain in place over the spring and summer and will be treated in the fall, rather than in the winter or early spring following their creation.

This alternative will provide equal or greater hazard reduction. Slash will be concentrated in the landings so that it is no longer a fuel component of the forested stands. There will be protective space around the piles as specified in Section II, Item 31. Also, there have been several incidents of burnt piles rekindling and even escaping following spring burning in this general region. Allowing fall burning of these piles will assure better consumption of the material and a cooling off period through the winter months.

All other provisions of 14 CCR 937.5 will be complied with. Piles will be constructed so that they are sufficiently free of soil for effective burning. These piles will be burned at a safe time during wet fall or winter weather according to other applicable laws and regulations. Piles that fail to burn sufficiently to remove the fire hazard shall be further treated to eliminate the hazard. All necessary precautions shall be taken to confine such burning to the piles.

Although some scorching of surrounding trees may occur, the extent of this damage will not result in conditions that do not meet the silvicultural and stocking requirements of this THP. No excessive buildup of bark beetle populations is expected to occur as a result of this proposed alternative.

Plan addendum #33 - Snag Falling / Hazard Reduction

Felling of snags for hazard reduction within 100 feet of all public roads, seasonal roads, and landings will not result in the loss of habitat elements associated with late seral stage timber stands. There are standing dead trees in later stages of decay throughout the THP. All snags with visible nesting sites of eagles, hawks, owls, waterfowl, or any rare or endangered species will be left standing as prescribed under 14 CCR 939.1 and 939.2(d). Special attention will be focused on retaining snags within WLPZs that may be recruited as large woody debris (LWD).

DEMONSTRATIONS AND EXPERIMENTS

According to statute and Board policy, the purpose of the state forest program is to investigate and demonstrate the economic feasibility of artificial reforestation and the productive and economic possibilities of forest management practices which are designed to promote continuous forest production, with due regard to conservation of soil, watershed, scenic, wildlife, and recreational values. PRC 4645 authorizes the Department of Forestry and Fire Protection to manage State Forests and states, "The department, in accordance with plans approved by the board, may engage in the management, protection, and reforestation of state forests." The primary current use of state forests is to demonstrate economical silvicultural practices and timber harvesting procedures that protect environmental values.

State forests have been established to furnish land for needed investigation, demonstrations, and education in such things as the economic feasibility of artificial reforestation, good forest practices, maintenance of forest land in a productive condition, study of effects of improved cutting methods, proper management and harvesting methods, and economical forest management.

The following demonstrations are associated with this timber harvesting plan:

1. Continuous Forest Production and economical silvicultural practices.

Timber harvesting and forest production has occurred on LDSF since 1952. Approximately 150 million board feet of timber has been harvested from the Forest. Since the Forest's establishment, the estimated standing volume of timber has increased from 102 million board feet to 197 million board feet (based on TAI inventory conducted from 1994-2001). This harvest will continue to demonstrate forest production to achieve maximum sustained production of high quality forest products while giving consideration to other values relating to recreation, watershed, wildlife, range and forage, fisheries, and aesthetic enjoyment.

2. Demonstration of the Board approved Variable Retention Silviculture.

3. Evaluation of yarding systems in selection silvicultural systems

An on going demonstration project is being conducted by LDSF Staff. Three yarding systems, (tractor, cable and helicopter) are being evaluated in harvesting forest stands utilizing selection silviculture. Costs, feasibility, and residual stand damage are evaluated to determine applicability for the small forest landowner.

4. Avian use of pre and post harvested timber stands

LSDF staff in cooperation with the DFG is doing a comparative evaluation of avian species use of timber stands and brush fields. Additionally within the study, a comparison of pre and post harvest avian use is being evaluated by silvicultural treatment.

SECTION IV

CUMMULATIVE IMPACTS

STATE OF CALIFORNIA
BOARD OF FORESTRY
CUMULATIVE IMPACTS ASSESSMENT

- (1) Do the assessment area(s) of resources that may be affected by the proposed project contain any past, present, or reasonably foreseeable probable future projects? ☒ Yes ☐ No
If the answer is yes, identify the project(s) and the effected resource subject(s).
- (2) Are there any continuing, significant adverse impacts from past land use activities that may add to the impacts of the proposed project? ☐ Yes ☒ No
If the answer is yes, identify the activities, describing their location, impacts, and the affected resource subject(s).
- (3) Will the proposed project, as presented, in combination with the past, present, or reasonably foreseeable probable future projects identified in items (1) and (2) above, have a reasonable potential to cause or add to significant cumulative impacts in any of the following resource subjects?

Impact Assessment	Yes After Mitigation (a)	No After Mitigation (b)	No Reasonably Potential Significant Effects (c)
1. Watershed			X
2. Soil Productivity			X
3. Biological			X
4. Recreation			X
5. Visual			X
6. Traffic			X
7. Other			
<p>a. Yes, means that potential significant adverse cumulative impact are left after application of the forest practice rules and mitigations or alternatives proposed by the plan submitter.</p> <p>b. No after mitigation means that any potential for the proposed timber operation to cause or add to significant adverse cumulative impacts by itself or in combination with other projects has been reduced to insignificance or avoided by mitigation measures or alternatives proposed in the THP and application of the forest practice rules.</p> <p>c. No reasonably potential significant cumulative effects means that the operations proposed under the THP do not have a reasonable potential to join with the impacts of any other project to cause, add to, or constitute significant adverse cumulative impacts.</p>			

- (4) If column (a) is checked in (3) above, describe why the expected impacts cannot be feasibly mitigated or avoided and what mitigation measures or alternatives were considered to reach this determination. If column (b) is checked in (3) above describe what mitigation measures have been selected which will substantially reduce or avoid reasonably potential cumulative impacts except for those mitigation measures or alternatives mandated by the application of the rules of the Board of Forestry.
- (5) Provide a brief description of the assessment area used for each resource subject.
- (6) List and briefly describe the individuals, organizations, and records consulted in the assessment of cumulative impacts for each resource subject. Records of the information used in the assessment shall be provided to the Director upon request.

Past and Future Activities

The assessment area for past and future activities consists of the Huckleberry (5507.320102) and Beal (5507.310103) Cal Water Planning Watersheds, version 2.2

For assessment purposes, the following is a table of past projects that have been approved within the Huckleberry and Beal planning watersheds. The data was obtained from the CAL FIRE Cumulative Effects Database. Due to the limitations of the CDF database the acres listed below tend to be over estimates. If part of a THP is within the assessment area, then all of the acres of the THP are included in the database, unless noted otherwise.

Timber Harvest Plans in the Assessment Area

THP Number	yarding method	status	Acres by Prescription										Total
			NT	FB	AP	R/W	CC	SWR	SEL	SS	CT	GSEL	
2-99-222	tractor/skidder	completed			198		99	22		86			405
2-02-033	tractor/skidder	completed					31						31
2-02-225	tractor/skidder	completed			70	3	44					557	674
2-03-172	tractor/skidder	completed							458				458
2-04-177	tractor/skidder	active		40					1133		11		1184
2-05-111	tractor/skidder	active				2	213		10				225
2-05-149	tractor/skidder	active	39	14					95	200		1914	2262
2-06-129	tractor/skidder	active			344	2							346
2-06-138	tractor/skidder	active			167		239						406
2-98-239	tractor/skidder	completed									527	329	856
2-99-253	tractor/skidder	completed					5	83				368	456
2-01-037	tractor/skidder	completed				1			300	50	1025		1376
2-03-188	tractor/skidder	completed		57			485	2			237		781
2-03-050	tractor/skidder	completed							1185				1185
2-02-214	tractor/skidder	completed	13	112			494	54	3		410		1086
2-02-187	cable, tractor/skidder	completed						344				1288	1632
2-01-161	tractor/skidder	completed									50	611	661
2-08-071	tractor/skidder	active				2		7				341	350
2-09-064	tractor/skidder	review				6	266		12				284
2-09-063	tractor/skidder	review							1768	64			1832
2-09-059	tractor/skidder	review	15			1			320	101			437
*SCH # 2008062009	active		9,033 acre LDSF management Plan										
**Total Acreage			67	223	779	17	1,876	512	5,284	501	2,260	5,408	16,927
**Percent of Assessment Area			0.39%	1.31%	4.6%	0.1%	11.08%	3.02%	31.21%	2.96%	13.35%	31.94%	69.28%

CC	Clear Cut	SEL	Selection
SWS	Shelterwood Seed	SS	Sanitation-Salvage
SWP	Shelterwood Prep	CT	Commercial Thinning
SWR	Shelterwood Removal	Trans	Transition Method
STS	Seed Tree Seed	Rehab	Rehabilitation of Understocked Area
STR	Seed Tree Removal	GSEL	Group Selection
R/W	Right of Way	NT	Non Timberland

* This is a CEQA compliant Mitigated Negative Declaration of LaTour Demonstration State Forest's Management Plan 2008.

** Acres and percentages shown within these tables may be increased are over actual acres harvested within the assessment area. Due to the limitations of CAL FIRES' database, if portion of a THP is within the assessment area, then all the acres of the THP are included in the data base.

Based on the CAL FIRE Database Check 16,927 acres (69%) of the assessment area has been harvested or planned for harvest. Of the total area harvested, 3184 acres (18% of the assessment area) were treated with evenaged silviculture methods. The majority of the assessment area that was harvested was treated using unevenaged and intermediate silvicultural methods (13,743 acres). No long-term site impacts have resulted from the harvesting with in the assessment area.

Present projects

For the purpose of assessing present projects the entire THP area is being treated with selection and Variable Retention silviculture methods and there is three acres of meadow restoration. There are no other known California Environmental Quality Act projects currently proposed within the assessment area.

Future Projects

Future projects include the ongoing production and removal of high quality forest products through scheduled periodic harvesting on the commercial timberlands. LDSF will continue to manage the State's timberlands on periodic entries (18 year re-entry cycle) using predominantly un-evenaged silviculture. Within the next 5 years LDSF has 1 additional THP planned within the Beal watershed and one within the Huckleberry watershed. No increased impacts are expected to result from these ongoing forest management activities.

A. ASSESMENT AREAS

Watershed Resources

The watershed assessment area consists of the Beal and Huckleberry Cal Wat 2.2 watersheds and is shown on the attached Watershed Assessment Map. The THP boundary lies within the headwaters of both watersheds. The watersheds are third order watersheds and Cow Creek is tributary to the Sacramento River. This assessment area was chosen because the key cumulative impact issues, related to timber harvest, typically express themselves at the scale of planning watersheds or a subset of the planning watershed area.

Beal watershed (planning watershed 5507.310103) is the headwaters of South Cow Creek and drains a basin of 11,598 acres, of which 5,928 acres are contained within the boundaries of LDSF. Elevation ranges from 6,740 at LaTour Butte to 2,920 feet at the junction with Atkins Creek. Major tributaries include Beaver, Bullhock and Beal Creeks. South Cow is a third order stream before the junction with Atkins Creek (and fourth order below Atkins). There are approximately 9 miles of Class I watercourses along the main channel of South Cow Creek. Ownership in the lower elevations of the watershed is predominately private commercial timberlands

Huckleberry (planning watershed 5507.320102) includes the headwaters portion of Old Cow Creek and drains a basin of 12,836 acres, of which 1,452 acres are contained within the boundaries of LDSF. Elevation ranges from 7,064 (Huckleberry Mountain) to 4,520 feet about 1/4 mile below the junction with Hunt Creek. Old Cow Creek originates from Huckleberry Lake in the Lassen National Forest. Additional major tributaries include Huckleberry Creek, Peavine Gulch, and White Fawn Gulch. Old Cow Creek below Hunt Creek is a fourth order stream. There are about 7.5 miles of Class I watercourse along the main channel of Old Cow Creek.

Soil Productivity

The assessment area will be the boundary of the THP. This will be adequate to cover impacts from timber operations.

Biological Resources

The biological assessment area (BAA) coincides with the watershed assessment area. The BAA has high biodiversity based on the elevation range, and multiple types of vegetation and habitat. Rational for selection of the BAA is that the watershed assessment area serves as a distinct boundary for collecting and observing wildlife data. This area provides a large enough area adjacent to the THP to assess cumulative impacts to wildlife.

Recreational Resources

The assessment area for recreational resources will be the harvest area plus 300 feet from the plan boundary. This area is appropriate due to the limited recreational use the area receives.

Visual Resources

The visual assessment area is the plan area that is readily visible to significant numbers of people within 3 miles of the THP. This was selected due to the distance of the harvest area from communities and well traveled roads.

Vehicular Traffic Impacts

The assessment area includes the two main haul routes from the THP area.

- a) Cutter Road to the Lassen National Forest Road A16, North to the Tamarack Rd (Shasta County Rd.)
- b) Bateman Road from the harvest boundary to the end of the county road portion on the Bateman Road.
The county road ends at the Atkins Creek watercourse crossing.

The extent of the assessment area was determined based on these routes are the most logical routes off the harvest area and the assessment area terminates at the first county road.

B. Watershed Impact Assessment

LDSF is located at the top of a range and is the headwaters for one major drainage, South Cow Creek and part of the headwaters of Old Cow Creek. Beal and Huckleberry watersheds are the headwaters of these two major drainages. Precipitation averages 46 inches a year with most of it as snow (74%) between November and March. Summer rainfall in the form of thunderstorms is unpredictable.

The harvest area lies within the Beal and Huckleberry watersheds. Tributaries to South Cow Creek, part of the Beal Watershed, are within the plan area although the WLPZ of South Cow Creek is outside the plan. Numerous skid trails and landings exist in the harvest area from past selection harvests. Slopes of the harvest area within the Beal Watershed are moderate with the average being approximately 25-30%.

Various portions of the plan area were initially harvested in the early 1960's. A second entry occurred in the 1980s, which covered most of the plan area. Past harvests used the selection silvicultural system.

South Cow Creek is a third order watercourse and a fourth order watercourse downstream of the junction of Atkins Creek. South Cow Creek is in good condition. South Cow Creek contains generally complex habitat with deep pools, riffles, and boulders forming step pools. The creek appears to have good channel conditions in the lower portion of the planning watershed and impacts from timber operations were not significant to those portions of South Cow Creek.

Further evaluation of the South Cow Creek and Old Cow Creek occurred in the summer of 2000 from the *LaTour Demonstration State Forest Watershed Monitoring Project*, Stream Channel and Fish Habitat Assessment prepared by the Sacramento Watersheds Action Group (SWAG) under contract with the Department of Forestry and Fire Protection. In this report South Cow Creek, Bullhock Creek and Old Cow Creek were assessed within the LDSF boundaries. The SWAG report assessed 16,579 feet of South Cow Creek, 15,376 feet of Bullhock creek and 7,380 feet of Old Cow Creek within the LDSF Boundaries. The report concluded 91% of S. Cow Creek was stabile with some instability noted at the upper reaches in a meadow. The report noted that 99% of Old Cow Creek was stabile with the first 300 feet of Old Cow Creek being rated as stability at risk. Banks were stabilized primarily by large cobbles, boulders, and riparian vegetation. By length habitat within these two creek is approximately 40% riffle, 40% flatwater and 20% pools. Bullhock creek lies entirely within the LDSF Boundary. The 4500-foot class I segment of this watercourse was also rated as being stabile and begins at its confluence with South Cow Creek. The channel is steep with the banks being stabilized with large boulders and diverse woody riparian vegetation. By length habitat is 36% riffles, 58% flatwater, and 6% pools. Bullhock Creek has a steep gradient and has evidence of supporting large flood events. The habitat within all three Class I watercourses are boulder dominated.

Sediment Effects

Sediment-induced cumulative watershed effects (CWE) occur when earth materials transported by surface or mass wasting erosion enter a stream or stream system at separate locations and are then combined at a downstream location to produce a change in water quality or channel condition. Sediment effects result from many factors such as weather, geology, soil erosion potential, road location, silviculture, vegetation retention, and heavy equipment operations adjacent to watercourses. Sedimentation has occurred to tributaries of the South

Cow Creek during the winter storms of 1997, when rain-on-snow events caused significant runoff resulting in culvert crossing failures and road fill washing into the drainage system.

The management of LDSF has a goal of reducing sedimentation to watercourses. The LDSF has developed and implemented a Road Management Plan (RMP) in compliance with the California Environmental Quality Act (CEQA) that will reduce erosion and sediment from the permanent road system. Implementation of the RMP involves systematic survey of the road system and all watercourse crossings.

Since 1999 over 10 miles of roads in the Beal Watershed have been treated to improve drainage and reduce erosion. This treatment has included outsloping and installing rolling dips on 5.5 miles of road that were previously insloped with an inside ditch. Where road surface runoff is a concern the traveled surface is rocked. At the headwaters of South Cow Creek, 0.5 miles of South Cow Creek road was abandoned and five crossings permanently removed. Watercourse crossings are evaluated as to their potential to fail or contribute sediment from improper installation. Twelve crossings have been replaced since 1999. All of these actions have or will reduce potential sediment inputs into the Beal Watershed. Approximately 1 mile of LDSF roads have been rocked within the Huckleberry watershed since the implementation of the RMP.

Water Temperature/Thermal Loading Effects

Water temperature related CWEs are changes in water chemistry or biological properties caused by the combination of solar warmed water from two or more locations (in contrast to an individual effect that results from impacts along a single stream segment) where natural cover has been removed. Due to the elevation of the plan area the two major factors that would affect water temperature are water source and canopy cover. The contribution of water from the plan area within both watersheds, during the summer months, is spring-fed watercourses from streams with gradients that result in high flow velocities. Stream reaches with low flow velocities and full solar exposure that would result in an increase in water temperature are uncommon on the LDSF within these watersheds. Past harvests have maintained canopy cover over watercourses. The SWAG report found that the Class I watercourses within the Beal and Huckleberry watersheds had an average of 69% canopy cover, measured with a solar pathfinder, within the LDSF boundaries. Ninety four (94) percent of this cover consisted of coniferous vegetation.

This THP will maintain streamside vegetation that will continue to shade watercourses from solar radiation and prevent water temperature increases.

Organic Debris/LWD Effects

Large woody debris can have both positive and negative effects on a watercourse. Large woody debris is an important stabilizing agent in steep gradient channels. The sudden introduction of large, unstable volumes of bigger debris (such as logs, chunks, and larger limbs produced during a logging operation) can obstruct and divert stream flow against erodible banks, block fish migration, and may cause debris torrents during periods of high flow. Removing streamside vegetation can reduce the natural, annual inputs of litter to the stream (after decomposition of logging-related litter). This can cause both a drop in food supply, and resultant productivity, and a change in types of food available for organisms.

Based upon the California Department of Fish and Game's *California Salmonid Stream Habitat Restoration Manual - Third Edition*, the SWAG study found that on average there were 22 pieces of large woody debris per 100 feet of watercourse segment in the Class I watercourses on the LDSF. Watercourse protection provided in the plan will continue to provide both LWD for streamside habitat and prevent the sudden introduction of debris from harvesting practices.

Chemical Contamination Effects

Sources of chemical contamination include run-off from roads treated with oil or other dust-retarding materials, direct application or run-off from pesticide treatments, contamination by equipment fuels and oils, and the introduction of nutrients released during slash burning.

The use of oil or dust retarding materials is not planned for this THP. Accidental contamination of equipment fuel

or oil is unlikely. Fuel is stored in an area where it cannot contaminate a watercourse if a leak occurs. Additionally, equipment shall be serviced outside the protection zone of watercourses.

The use, type and the timing of the herbicide shall be determined and recommended by a PCA and the application shall adhere to the PCA's recommendation, the herbicide label instructions, and the Mitigated Negative Declaration, State Clearing House (SCH) # 2008062009 for LDSF Management Plan 2008 to DPR regulations, the PCA recommendation, the instructions on the herbicide label. The label is a comprehensive document about the herbicide, any associated hazards, active and inactive agents, and the proper use and handling of the herbicide. To speculate on potential impacts that could occur if the label, PCA recommendations, and DPR regulations are not followed is beyond the scope of this document.

No cumulative watershed effect, with regards to chemical contamination, is predicted for this THP.

Peak Flow Effects

Peak flow increases may result from management activities that reduce vegetative water use or produce openings where snow can accumulate (such as clear-cutting and site preparation) or that change the timing of flows by producing more efficient runoff routing (such as insloped roads).

The assessment area has experienced high peak flows from rain-on-snow events. These events, such as occurred in 1997, are unpredictable. The proposed silvicultural prescriptions will maintain vegetation over the plan area that will enhance infiltration of precipitation and maintain peak flows. Groups within the selection area will be less than 2.5 acres and will be planted to establish vegetation in the opening. There are no new roads planned for this timber harvesting plan that would reroute and concentrate runoff. As stated above for sediments effects, the drainage of existing roads is being improved through implementation of LaTour's Road Management Plan. The potential for this plan to increase peak flows is insignificant.

This harvest will have no impact on water temperature, organic debris, chemical contamination, or peak flow cumulative watershed effects. Sediments effects from road use and harvesting activities may occur but will be insignificant. No new road construction is planned nor will large openings be created. Nearly all tractor roads needed for this harvest exist. All watercourses and springs within and adjacent to the harvest area will be protected. Post harvest streamside vegetation will continue to provide filter strip properties and shading. Water drafting is proposed at four locations. Drafting locations will be rocked to prevent the introduction of sediment into the watercourse during drafting operations. Additionally the vehicles will be inspected to ensure chemical contaminants are not introduced into the watercourses. The silvicultural systems being applied should have no effect on peak flow. The vigorous residual stand will continue to maintain infiltration capacities and hold soil in place.

303(d) Listing

South Cow Creek is 303(d) listed based on the pollutant of Fecal Coliform. The possible sources of fecal coliform include agriculture, grazing related sources and others. Although LaTour may acquire an occasional lost cow on the property, it is not considered a highly desirable grazing area due to steep slopes, dense timber cover and minimal meadow grazing potential. In addition, weather conditions also attribute to the loss of grazing potential (moderate to heavy snow loads in the Winter and Spring). This THP does not propose cattle grazing, or the installation of septic tanks, nor will timber harvesting increase or decrease fecal coliform potential.

C. Soil Productivity Assessment

Windy - McCarthy sandy loam, with varying amounts of stones and rock, is only soil series within the harvest boundary. Windy - McCarthy soils are a complex of made up of Windy and McCarthy soils in equal proportions. These soils are stony to rocky sandy loams with a depth of up to 60 inches. The soils are well-drained with moderate to rapid permeability.

The primary factors influencing soil productivity to be assessed are:

1. Organic matter loss
2. Surface soil loss
3. Soil compaction
4. Growing space loss

Organic matter loss

The entire harvest area will be logged by tractor and disturbance of organic matter will occur. Throughout the harvest area there are many existing skid trails that will be utilized for this harvest. Few new skid trails will be constructed. When these skid trails are utilized organic matter will be displaced from them. To minimize disturbance, equipment will utilize designated skid trails and trees will be felled to these skid trails.

Replacement of organic matter will occur through logging residue, tree tops and limbs that will be left behind after harvest and from natural needle fall. Existing skid trails not pertinent to the harvest will not be utilized.

Existing down woody material throughout the harvest area will remain. Retaining unmerchantable material in the harvest area will recruit woody material. In addition to providing wildlife habitat, leaving woody material will add organic matter to the forest floor. Increases of organic matter to the forest floor will also occur from the planned lop and scatter slash treatment throughout the entire plan area.

Surface soil loss

Surface soil loss will occur by displacement of soil from skid trail construction and log skidding. There are many existing skid trails from past harvests and the need to construct new ones is minimal. Only one new landing is planned. The loss of surface soil from construction will be slight. Surface soil loss from erosion will be nominal due to the silvicultural systems being applied, lack of road construction, and installation of waterbreaks on skid trails and landings after completion of use.

Soil Compaction

Soil compaction will occur from the tractor skidding operation. Compaction will be greatest on main skid trails.

To reduce compaction over the harvest area and eliminate random wandering by equipment operators, main skid trails will be kept to the minimum needed to carry out the harvest. Skid trails will be designated prior to timber operations and equipment will be required to use designated trails, which will reduce the impact from compaction to the harvest area. Harvest activities will occur when soil moisture is low. When soils are saturated timber operations will be suspended. Timber operations will not occur during the winter period.

Growing Space Loss

Growing space loss from skid trail construction will occur, however, it will be minimal. All roads, landings, and skid trails are considered permanent. New skid trails are constructed so that they can be utilized in future harvests. The use of existing skid trails will be required. There may be a need for the construction of a few new skid trails for this harvest. All roads needed for this harvest exist and no new roads are planned.

D. Biological Assessment

Anadromy

There are no known anadromous salmonids identified within the biological assessment area. The Beal watershed is listed as a threatened and impaired for Chinook and Steelhead. No anadromous salmonids occur on LaTour nor are there historical records of observations in the Beal Creek Watershed. From information within the *Cow Creek Watershed Assessment* prepared by SHN Consulting Engineers & Geologists Inc. fall run Chinook have occurred in the lower reaches of South Cow Creek below Wagoner Canyon approximately 10 miles west of the Forest. Steelhead were reported at the crossing of South Cow Creek by Ponderosa Way, approximately 9.5 miles west of the plan boundary. Historical data indicates salmon

above Wagoner Canyon were scarce due to a natural barrier in the Canyon and a dam constructed across South Cow Creek by PG&E in 1908. The barrier was removed by blasting and a fish ladder was constructed at the dam in the 1970's by the Department of Fish and Game. However, local residents state there was no significant increase in the number of fish above the dam. The Cow Creek report suggests one of the key limiting factors is adequate stream flow to provide passage of adult fish. Water is diverted from South Cow Creek for irrigation and power use during critical passage periods.

No physical barriers exist on South Cow Creek upstream of the Ponderosa Way crossing, as such Steelhead could potentially migrate upstream. It is unlikely they occur within in Bullhock creek due to low flows during the summer and fall.

From dives performed in 2000 for the fish habitat assessment of the SWAG report, only rainbow trout were observed in South Cow Creek, Old Cow Creek and Bullhock Creek on the LDSF. There are no Class I watercourses on or adjacent to the THP.

Per 936.9(b) there will be no significant cumulative watershed effects on the populations and habitat of anadromous salmonids from implementation of this plan nor are any cumulative effects known. The Watershed assessment (section B) addresses sediment, thermal loading, large woody debris, and peak flow. Mitigation in the water drafting plan will prevent a take, if Steelhead are present in Atkins Creek. Harvesting activities along watercourses have been conservative in the past to provide good shade cover. With the implementation of the protection afforded the watercourses in the plan coupled with the requirements of the Forest Practice act and Board of Forestry rules there should be no adverse cumulative impact to aquatic species or habitat.

Scoping

The Natural Diversity Data Base (NDDB) was used as a scoping tool to check if any rare, threatened, endangered, or special concern species and/or their habitat are located on or surrounding the THP area. A nine quadrangle query was conducted, which included Jacks Backbone 7.5 minute quad, its surrounding eight quads. The following is a list of rare, threatened, endangered species, and/or their habitat that occurs within the THP area. There are no recorded occurrences of threatened or endangered species on LDSF.

Northern Goshawk. As discussed in Item #32 of the THP, the harvest area contains habitat for the Northern Goshawk. Protection measures are discussed in Section III of the plan. The silvicultural prescriptions proposed will have a very low impact on the Northern Goshawk's habitat requirements. The type of harvest being conducted may even improve forage habitat conditions for the goshawk where dense stands are opened.

Sierra Red Fox: The assessment area and the THP do contain the vegetation types considered habitat for the Sierra Red Fox. Observations of the red fox have occurred within the scoping area and primarily around Lassen Volcanic National Park. The closest observation to the THP is near Highway 44 and Scharch Meadow. LDSF staff has been conducting forest carnivore surveys the last three years and the Sierra Red Fox has not been detected. The project will maintain habitat for the Sierra Red Fox.

California Wolverine (State Threatened): The California wolverine has been detected within the scoping area. The assessment area and the THP do contain the vegetation types that are considered habitat for the wolverine. LDSF staff has been conducting forest carnivore surveys the last three years and the wolverine has not been detected. The project will maintain habitat for the California Wolverine.

Pine Marten: The assessment area and the THP do contain habitat the Pine Marten. Pine Martin were detected on LDSF in a 1990 furbearer presence survey. The Pine Marten has been detected in the southeastern portions of the forest, within the assessment area, during the forest carnivore surveys being conducted by LDSF staff in 2005 and 2006 and 2007. The THP will maintain habitat for both the Pine Marten and the Pacific Fisher.

Pacific Fisher (State Canidate): LDSF contains habitats for the Pacific Fishers and it was detected in a 1990

furbearer presence survey. No subsequent detections have occurred. The elevation of the plan is generally considered above the range of the pacific fisher, but contains habitat for the Pacific Fisher. The plan will maintain habitat post harvest. Protection measures are discussed in Section III of the plan.

Nodding vanilla grass, *Hierochloe odorata* (CNPS 2.3): The assessment area and the THP have the general habitat types associated with the known occurrences of vanilla grass. Vanilla grass is located within wet meadows and seeps above 5400 feet in elevation. The THP provides protection for all meadows and seeps and the THP also restores potential habitat for vanilla grass.

Rayless mountain ragwort, *Packera indecora* (CNPS 2.2): Rayless mountain ragwort is located in meadows and seeps on mesic sites between 5200 and 6500 feet in elevation. The assessment area and the THP has the general habitat types associated with the known occurrences of Rayless mountain ragwort. The THP has potential habitat along the class II watercourses, meadows, springs and seeps. The THP provides protection for all meadows, seeps, and watercourses. The THP also restores potential habitat for Rayless mountain ragwort.

Scalloped moonwort, *Botrychium crenulatum* (CNPS 2.2): The assessment area and the THP have the general habitat types associated with the known occurrences of scalloped moonwort. Scalloped moonwort is located along moist meadows and near creeks of lower montane coniferous forests and freshwater marshes above 4500 feet in elevation. The THP provides protection for all meadows, seeps, and watercourses.

Long-stiped champion, *Silene occidentalis spp longistipitata* (CNPS 1B.2): CNPS identifies habitat as between 1000-2000 meters in Lower and Upper Montane coniferous forests and the NDDDB add no further information. In the non published *Conservation Assessment and Strategy for Long-stiped Champion...*, a USFS Forest Service, Pacific southwest Region and Lassen National Forest document, the key habitat an biological parameters are: 1) occurs in openings of mid elevation mixed conifer forests as well as on ridgetops in black oak, 2) low canopy closure 3) survives in disturbed habitats and disturbance may be a important factor, 4) occurs in thin soils with clay and have various amounts of sand and rock. This document was provided to LaTour Demonstration State Forest from DFG. The THP does have the clay soils and is above the elevation range.

The following table shows additional species scoped by the CNDDDB on Jan 30 2008, Feb 27 2008 & September 26 2009 that retain no habitat in the THP area.

Scientific Name	Common Name	Status	CNPS List	Comments
<i>Fritillaria eastwoodiae</i>	Butte County fritillary	None	3.2	THP is above elevation
<i>Cryptantha crinita</i>	silky cryptantha	None	1B.2	THP is above elevation
<i>Potentilla newberryi</i>	Newberry's cinquefoil	None	2.3	Marshes and swamps
<i>Potamogeton praelongus</i>	White-stemmed pondweed	None	2.3	Marshes and swamps
<i>Asplenium septentrionale</i>	Northern Spleenwort	none	2.3	Granite like outcrops
<i>Smelowskia ovalis</i> var <i>congesta</i>	Lassen Peak smelowskia	None	1B.2	Alpine bolder and rock field
<i>Silene suksdorfii</i>	Cascade alpine campion	None	2.3	Alpine bolder and rock field
<i>Astragalus pulsiferea</i> var <i>suksdorfii</i>	Suksdorf's milk-vetch	None	1B.2	Lower Montane Coniferous
<i>Collomia larsenii</i>	Talus collomia	None	2.2	Loose volcanic material
<i>Botrychium virginianum</i>	Rattlesnake fern	None	2.2	THP is above elevation
<i>Hulsea nana</i>	Little hulsea	None	2.3	Rocky or gravely volcanic Sub-Alpine forests
<i>Eriogonum pyrolifolium</i>	Pyrola-leaved buckwheat	None	2.3	Alpine bolder and rock field
<i>Juncus digitatus</i>	Finger rush	None	1B.1	THP is above elevation
<i>Calochortus longebarbatus</i> var <i>longebarbatus</i>	Long haired star tulip	None	1B.2	Heavy clay soils
<i>Cryptantha crinita</i>	Silky cryptantha	None	1B.2	THP is above elevation
<i>Stachys palustris</i> ssp. <i>Pilosa</i>	Hairy marsh hedge-nettle	None	2.3	THP is above elevation
<i>Rana boylei</i>	Foothill yellow-legged	Special	N/A	THP is above elevation, outside range
<i>Pandion haliaetus</i>	Osprey	Special	N/A	No good fish producing body of water
<i>Haliaeetus leucocephalus</i>	Bald eagle	Endanger	N/A	No good body of water near
<i>Falco peregrinus anatum</i>	American peregrine falcon	Endanger	N/A	No habitat for nesting
<i>Oncorhynchus tshawytscha</i>	Spring run Chinook salmon	Threat	N/A	No occurrences in watershed.

There are numerous other wildlife species that exist on LDSF, including the THP, that are not listed as threatened, rare, or endangered. The South Cow Creek deer herd uses LDSF as summer range and fawning area. In the past, certain designated brush fields have been burned to improve forage habitat for the deer. There are other brush fields that may be burned in the future.

Habitat types

The forest inventory on LDSF indicates there are 7130 acres of merchantable sized timber stands and 677 acres of plantation (1978 Whitmore burn). The remainder of the Forest is brush, rocky areas, meadows, and open areas with scattered trees

Timber types and WHR habitat types for LDSF have been determined through aerial photo interpretation, vegetation inventory, and the use of a database program written by the Forest Staff which determines WHR types from forest inventory data. Plot data from the inventory represents a 2.5-acre area and the WHR type was determined for each plot. Within the plan area the tree size classes ranged from 3 to 5 and with a range of canopy closure from open to dense. The predominant WHR types were Sierra Mixed Conifer and White Fir 4D and 4M. WHR 5M, 5D exist in the plan area. However, these stands are scattered and do not have the continuity to qualify as late succession forest stands per rule definition. The desired forest structure on LDSF is described within *LDSF 2008 Management Plan*, "The overall goal is to maintain LDSF as a mid-seral forest type characteristic of the southern Cascades. Early and late seral stands will be represented but overall the Forest will maintain the characteristics of a mid-seral forest. This goal is not discretionary, but rather follows directly from the research and demonstration mandate for LDSF. Rather than a park or reserve, the legislated mandate for the Forest is that of a working forest property for demonstration and research purposes, serving a clientele of small to medium size land owners.

In order to remain relevant as a research forest, LDSF aims to create and maintain a wide range of forest types, ages, size classes, successional stages and structural characteristics. It is going to be very difficult to maintain pure stands of each of these characteristics on a Forest the size of LDSF. As a result, LDSF's approach will be to incorporate a continuum of types, age classes, successional stages and structures mixed within stands across the Forest as far as possible."

Snags and large down woody material are present on the THP and within the assessment area. Additional recruitment of snags and downed woody material will be accomplished through the retention of green cull trees and unmerchantable material in the forest stands.

Hardwoods

Hardwoods are not a large component of the stands on the LDSF, which is true for the THP area. The THP is located above 5400 feet in elevation, which is generally above the upper elevation limit at which oaks grow. Harvesting of oaks will not occur within the THP area.

Road density

Road density, which can have a potential effect on wildlife, are moderate on LDSF and within the assessment area. The average density per section is 4 to 5 miles of seasonal and rockered seasonal roads on LDSF. Although accessible to the public, these roads receive little traffic most of the year. There is no new road construction proposed within the THP.

E. RECREATIONAL ASSESSMENT

The recreational activities that normally occur in the recreational assessment area is deer hunting, camping, fishing, snowmobile riding, and site seeing. Mountain bike riders occasionally use the forest but are rare and infrequent. Additionally, the forest is used by the public for fuelwood cutting. The rock pit harvest unit is will occur along the main forest access road, Bateman Road. The road may be blocked to traffic for short periods of time during active timber operations. A sign will be posted on the Bateman road at the west entrance to the LDSF to warn the public of logging activities in the area and the Licensed Timber Operator will be advised to watch for recreationists and to allow thru traffic on Bateman Road.

The primary use within the recreational assessment area is deer hunting. Impact to hunting may occur during any year the THP is operated since, for safety reasons, no hunting will be permitted in the vicinity of timber operations

An agreement exists with the Lassen National Forest to allow the grooming of approximately 30 miles of Forest roads during the winter for snowmobile use. This recreational activity will not be adversely affected by timber operations.

F. VISUAL RESOURCE ASSESSMENT

This timber harvest cannot be seen by significant numbers of people since the harvest area is not visible from any well-traveled roads or communities. The closest paved public road is the paved section of Bateman Road, 11 miles to the west of the LDSF boundary. Adjacent ownerships are accustomed to timber production, however, one home is approximately 1/4 mile west of LDSF boundary. The harvest area cannot be viewed from the home, however, logging traffic will likely travel by the home enroute to/from Redding. There will be no adverse effect on the visual resource. The prescribed silviculture will not adversely change the visual aspect of the assessment area. The greatest visual impact will be from within the stand after harvest.

G. VEHICULAR TRAFFIC IMPACTS

Forest products from the harvest area will be hauled out over two potential routes. This will cause a slight increase in vehicular traffic.

a. Cutter Road and the Lassen National Forest Road A 16

This road network has a gravel surface with permanent culverts at watercourse crossings. Those portions of the road network which are not graveled have high coarse fragment contents in the native soil; these roads will not be used when soils are saturated. These roads will only be used during the non-winter months and a maintenance agreement and permit will be obtained prior to use for all private or federally owned roads. These roads will be graded as needed and watered during the operation (if used for log hauling).

b. Bateman Road.

This haul route will result in traveling down the Bateman Road. The Bateman Road is a private road and is graveled from Atkins Creek (end of the county road) to the harvest boundary. The one homeowner on the graveled portion of the road has posted 10 MPH signs near his home. The LTO will be advised to comply with the 10 MPH limit when passing by the home. The primary use of the road is from logging operations, recreation and access to the residence. Eleven miles of dirt and gravel roads will be used following this route. Bateman road will be graded as needed and watered during the operation (if used for log hauling).

Since the main use of these haul routes is logging traffic the impact to people who use them on a regular basis will be almost non-existent. The greatest impact from the increase in traffic will be on recreationists using these roads. Since weekend operations are not planned the impact will be minor.

H. OTHER**Climate Change and Forestry Practice**

This THP complies with LDSF approved Management Plan, Mitigated Negative Declaration and Option A analysis. The following information is part of LDSF Mitigated Negative Declaration for LaTour Demonstration State Forest (SCH#2008062009) and the LDSF Management Plan:

In 2007 the State of California passed the Global Warming Solutions Act (AB 32), which set targets to reduce greenhouse gas emissions to 1990 levels by 2020 and 80 percent below 1990 levels by 2050. The California Air Resources Board was tasked with obtaining compliance with the cap through regulatory and market approaches. Planning is currently underway and definitive decisions by the Board have not yet been taken, however, it appears that forests will play a significant role in non-regulated strategies to meet targets. This is anticipated to occur both as offsets within a cap and trade system and through voluntary measures.

Recognized strategies to mitigate GHG emissions and enhance terrestrial sequestration include reforestation, forest management and fuels treatments to avoid catastrophic losses. LDSF will contribute to the targets of AB32 by increasing the resiliency of the Forest to catastrophic mortality by improving the general health of stands, pre-fire implementation of a shaded fuel break and maintenance of firefighting infrastructure such as roads, signage and water sources. The long-term carbon stocks of the Forest are anticipated to increase over time. For example, the Option A Plan indicates that the timber inventory on the Forest will increase from about 22.7 MBF per acre in 2005 to 34.4 MBF per acre in 2105.

Forest products produced from LDSF will sequester carbon during their life cycle. Biomass fuels produced on the Forest also provide an opportunity to replace fossil fuels with an alternative energy source that is close to carbon neutral.

This analysis evaluates whether climate change and greenhouse gas (GHG) issues related to management of LDSF have the potential to be a significant environmental effect, either on a project basis or cumulatively. Table 2 summarizes estimated net carbon dioxide sequestration levels under proposed management at LDSF over a 100-year planning interval¹. The analysis shows substantial positive carbon sequestration benefits. Proposed management at LDSF will sequester a net CO₂ equivalent of 3,773,000 tons of carbon at the end of 100 years.

Table 2. Estimated carbon sequestration at LDSF over the next 100 years.

1	2	3	4	5	6	7
Current standing inventory	CO ₂ stored in current standing timber ²	Standing inventory at end of 100-year planning interval	CO ₂ stored in standing timber at end of 100-year planning interval	Total harvest over 100-year planning interval	Total CO ₂ sequestered in forest products at end of 100-year planning interval	Total net CO ₂ sequestered at end of 100-year planning interval (4-2+6)
MBF*	M* tons	MBF	M tons	MBF	M tons	M tons
196,931	1,575	308,096	2,465	360,460	2,884	3,773

* MBF is thousand board feet and M is thousand.

² A conversion factor of 8.0 was used to convert thousand board feet to tons of CO₂ including soil root biomass, duff, litter, canopy and non-bole tree parts (Smith et al, 2002, GTR NE-298).

¹ A 100-year look-ahead period is necessary in forested ecosystems, where trees can take more than 50 years to reach maturity. The 100-year planning interval allows a minimum period necessary to evaluate long-term steady-state behavior of forested ecosystem while not exceeding the range of applicability of mathematical simulation models.

Accounting for emissions from the Forest includes vehicles and buildings used by the Department that are associated with management. It also includes emissions from harvesting and manufacturing. We chose to do the downstream accounting. This will be the most conservative accounting approach because we are not including the negative substitution effect that occurs when alternative higher-GHG-impact building materials such as steel and concrete are used instead of wood products. Emissions from vehicles and buildings are estimated as follows:

Vehicles: 0.02 thousand (M) tons per year x 100-year planning horizon = 2 M tons

Building: 0.00003 M tons per year x 100-year planning horizon = 0.003 M tons

This is a total of 2.003 M tons for the 100-year planning horizon.

Harvesting emissions include in-woods emissions from equipment and vehicles and transportation to a mill. Mill emissions estimates from processing are included because long-term storage of wood products is included in the analysis. Mill emissions include sawing, drying, energy generation, and planing. Also, transport to final destination is included. The entire life cycle for green-dried lumber is included (Puettmann and Wilson 2005). This results in a total emission estimate of 0.13 metric tons CO₂ equivalent per thousand board feet (MBF).

Given the total harvest of 360,460 MBF over the 100-year planning horizon in table 1, this equates to 46,859 tons of CO₂ equivalent from harvesting emissions. Including vehicle and building emissions, the total GHG emissions estimate for LDSF is 46,861 tons of CO₂ equivalents.

These emissions including full life-cycle of wood, vehicle, and building emissions, represent 1.24 percent of the total carbon sequestered (column 7 in Table 2). The conclusion from the above analysis is that there is a substantial positive carbon sequestration benefit and a net negative emission of GHGs at LDSF under the guidance of the Project. Orders of magnitude more biomass is being conserved than is being harvested. In other words, the management plan proposes to harvest less biomass (and to emit less CO₂) than growth.

Climate change science is still in its infancy. There are likely wide error bars around the above estimates, given the general level of the analysis and the relatively new estimation equations in the literature. The result that positive sequestration benefits exceed emissions by orders of magnitude however, lends validity to the general conclusion that sequestration will be much greater than emissions. Our conclusion is also supported by estimates from the Air Resources Board, which indicate that forest land use in California results in a net decrease in atmospheric carbon, not an increase (http://www.arb.ca.gov/cc/inventory/data/tables/net_co2_flux_2007-11-19.pdf).

Since the net amount of carbon that would be sequestered under the Project is greatly higher than the amount of carbon that will be released by LDSF management activities, there are no potential significant adverse environmental impacts, single or cumulative. In fact, significant beneficial impacts of net carbon sequestration will occur.

I. CONCLUSION

This harvest will not have any significant cumulative impacts to the resources.

J. REFERENCE MATERIAL

PERSONS

Mike Aronson, Forester
Sierra Pacific Industries
P.O. Box 496014
Redding, CA 96049

Pete Johnson, Forester
W.M. Beatty and Associates
P.O. Box 898
Redding, CA 96099 Ph: (530) 243-2783

Kelly Dreesmann, Division Chief
CAL FIRE
875 Cypress Ave
Redding, CA 96001, (530) 225-2418

LITERATURE AND MODELS

California Wildlife Habitat Relationship System Version 7.0
Cow Creek Watershed Assessment, prepared by SHN Consulting Engineers & Geologist, Inc.
LaTour Demonstration State Forest Watershed Monitoring Project, Stream Channel and Fish Habitat Assessment, Final Report, prepared by Sacramento Watershed Action Group.
A Guide to Wildlife Habitats of California California Wildlife - Volumes II & III
Pine Marten - Pacific Fisher Study Phase II Report 1992
Dept. of Fish and Game Natural Diversity Data Base
Soil Survey of Shasta County., U. S. Dept. of Agriculture
CDF Timber Harvest Plan Records
Aerial Photographs - Latour Demonstration State Forest
LaTour Demonstration State Forest Option A
LaTour Demonstration State Forest Management Plan 2008
Mitigated Negative Dec. (SCH# 2008062009), LaTour Demonstration State Forest Management Plan 2008
Conservation Assessment and Strategy for Long-stiped Campion ..., prepared by Colin Dillingham and Allison Sanger, USFS Lassen National Forest, 2007.

ESTIMATED SURFACE SOIL EROSION HAZARD

RM-87 (4/84)

**STATE OF CALIFORNIA
BOARD OF FORESTRY****I. SOIL FACTORS**

				FACTOR RATING BY AREA		
A. SOIL TEXTURE	Fine	Medium	Coarse	A	B	C
1. DETACHABILITY	Low	Moderate	High			
Rating	1-9	10-18	19-30	23	23	23
2. PERMEABILITY	Slow	Moderate	Rapid			
Rating	5-4	3-2	1	1	1	1

A –
Windy/McCarthy
> 30% slope

B –
Windy/McCarthy
< 30% slope

C – Variable
Retention Unit

B. DEPTH TO RESTRICTIVE LAYER OR BEDROCK

	Shallow	Moderate	Deep			
	1"-19"	20"-39"	40"-60 (+)			
Rating	10-6	5-3	3-1	2	2	2

**C. PERCENT SURFACE COARSE FRAGMENTS GREATER THAN 2 MM IN SIZE INCLUDING
ROCKS OR STONES cx**

	Low	Moderate	High				FACTOR RATING BY AREA		
	(-)10-39%	40-70%	71-100%				A	B	C
Rating	10-6	5-3	2-1	5	4	3			
							31	30	29
SUBTOTAL									

II. SLOPE FACTOR

Slope	5-15%	16-30%	31-40%	41-50%	51-70%	71-80%(+)			
Rating	1-3	4-6	7-10	11-15	16-25	26-35	12	3	4

III. PROTECTIVE VEGETATIVE COVER REMAINING AFTER DISTURBANCE


	Low	Moderate	High			
	0-40%	41-80%	81-100%			
Rating	15-8	7-4	3-1	3	3	8

IV. TWO-YEAR, ONE-HOUR RAINFALL INTENSITY (Hundredths Inch)









	Low	Moderate	High	Extreme			
	(-) 30-39	40-59	60-69	70-80 (+)			
Rating	1-3	4-7	8-11	12-15	12	12	12
TOTAL SUM OF FACTORS					58	48	53

EROSION HAZARD RATING


	<50	50-65	66-75	>75			
	LOW (L)	MODERATE (M)	HIGH (H)	EXTREME (E)			
	TERMINATION IS				M	L	M



AB 47 Cumulative Map

-  THP Boundary
-  LDSF Boundary
-  Watershed Assessment Area
-  THP 02-187
-  THP 09-059
-  THP 01-161
-  THP 08-071
-  THP 99-253

Scale: 1 mile





DEPARTMENT OF FORESTRY AND FIRE PROTECTION

875 CYPRESS AVENUE
REDDING, CA 96001-
(530) 225-2508
Website: www.fire.ca.gov



Certified Mail, Return Receipt Requested
7007 3020 0003 0354 5106

October 5, 2009

RECEIVED
OCT 05 2009
Shasta-Trinity
Resource Management

Pete Johnson
C/O W.M. Beaty and Associates
Brooks Walker et. al.
Post Office Box 990898
Redding, CA 96099-0898

Dear Pete:

As we discussed, W.M. Beaty and Associates will be included as a timberland owner on LaTour Demonstration State Forests' "Rim Road" timber harvesting plan. The inclusion of W.M. Beaty and Associates is for water drafting at one location along Bateman Road at Atkins Creek in the Brooks Walker ownership. Water drafting are considered timber operations per Public Resources Code 4527 and as such all timberland owners must be included in the plan.

Per Public Resources Code 4582, if the person filing the plan is not the owner of the timberland, the plan submitter shall notify the timberland owner by certified mail that the plan has been submitted and shall certify that mailing to the Department.

As the Plan Submitter, I am informing you of your responsibilities as the timberland owner. Post harvest stocking and erosion control maintenance is the responsibility of the timberland owner. LaTour Demonstration State Forest will assume erosion control maintenance responsibility for the water drafting location following timber operations. Stocking will not be an issue. The Department of Forestry and Fire Protection will enter a right-of-way agreement for the use of Bateman Road. This to maintain the road in good condition.

U.S. Postal Service	
CERTIFIED MAIL RECEIPT	
(Domestic Mail Only, No Insurance Coverage Provided)	
For delivery information visit our website at www.usps.com	
OFFICIAL OCT 05 2009	
Postage	\$ 4.44
Certified Fee	2.80
Return Receipt Fee (Endorsement Required)	2.30
Restricted Delivery Fee (Endorsement Required)	
Total Postage & Fees	\$ 5.54

Postmark Here

7007 3020 0003 0354 5106


Sent To: Pete Johnson W.M. Beaty & Associates
Street, Apt. No., or PO Box No.: PO Box 990898

Pete Johnson
October 5, 2009
Page Two

All water drafting operations performed under this THP on property managed W.M. Beaty and Associates will conform to the Forest Practice act and Board of Forestry rules and your Master Streambed Alteration Agreement with the Department of Fish and Game.

Thank you for your time.

Sincerely,

A handwritten signature in cursive script that reads "Benjamin Rowe". The signature is written in dark ink and is positioned above the printed name and title.

BENJAMIN ROWE
Forester I, RPF #2686
Assistant Forest Manager
LaTour Demonstration State Forest



DEPARTMENT OF FORESTRY AND FIRE PROTECTION

875 CYPRESS AVENUE
REDDING, CA 96001-
(530) 225-2508
Website: www.fire.ca.gov



Certified Mail, Return Receipt Requested
7007 3030 0003 0354 5113

October 5, 2009

RECEIVED
OCT 6 5 2009
Shasta-Trinity
Resource Management

Carl J. and Jo Ann Davis
P.O. Box 142
Whitmore, CA 96069

Dear Jack and Jo:

As part of LaTour's next timber harvesting plan that I am preparing, the licensed timber operator will once again, as many years in the past, be using Roaring Springs as a drafting location to maintain Bateman Road. The use of Roaring Springs is required for both dust abatement and maintaining the roads surface in a stable condition. The Forest Practice rules require you to be included as a timberland owner on LaTour Demonstration State Forests' "Rim Road" timber harvesting plan. Your inclusion as a timberland owner assumes no responsibility for timber operations on your part and is for water drafting only at Roaring Springs along Bateman Road. Water drafting is considered timber operations per Public Resources Code 4527 and as such all timberland owners where water drafting will occur must be included in the plan.

Per Public Resources Code 4582, if the person filing the plan is not the owner of the timberland, the plan submitter shall notify the timberland owner by certified mail that the plan has been submitted and shall certify that mailing to the Department.

As the Registered Professional Forester preparing the plan I am required to inform you of your responsibilities as the timberland owner. The Department of Forestry and Fire Protection has a right-of-way agreement for the use of Bateman Road. The agreement requires the Department to maintain the road in good condition. The agreement will assume the erosion control maintenance for the use of Bateman Road under this THP.


U.S. Postal Service	
CERTIFIED MAIL RECEIPT	
(Domestic Mail Only; Not for Insurance Coverage; Provided)	
For delivery information, visit our website at www.usps.com	
OFFICIAL OCT 5 2009	
Postage	\$.44
Certified Fee	2.80
Return Receipt Fee (Endorsement Required)	2.30
Restricted Delivery Fee (Endorsement Required)	
Total Postage & Fees	\$ 5.54
Shasta-Trinity Resource Management	
Postmark Here	
Sent by <u>Carl J. Davis</u>	
Direct, Apt. No. <u>PO Box 142</u>	
or PO Box No.	

Carl J. and Jo Ann Davis
October 5, 2009
Page Two

All water drafting operations performed under this THP on your property will conform to the Forest Practice act and Board of Forestry rules. Note that the Department of Forestry and Fire Protection has adjudicated water rights to Roaring Springs under the Cow Creek Adjudication Decree No. 38577 of the Superior Court for Shasta County.

Thank you very much.

Sincerely,

A handwritten signature in cursive script that reads "Benjamin C. Rowe". The signature is written in dark ink and is positioned above the printed name and title.

BENJAMIN ROWE
Forester I, RPF #2686
Assistant Forest Manager
LaTour Demonstration State Forest

FOR ADMIN. USE ONLY
Amendments-date & S or M

TIMBER HARVESTING PLAN
STATE OF CALIFORNIA
DEPARTMENT OF FORESTRY
AND FIRE PROTECTION
RM-63 (02-03)

FOR ADMIN. USE ONLY

THP No.

2-10-049-SHA (4)

Dates Rec'd 10/1/2010

1. SHU 7. Darley
2. FGI 8. _____
3. WQ5 9. _____
4. SHA-PW 10. _____
5. CGS 11. _____
6. RT 12. _____

THP Name: **North McMullen Mt.**

(In the CDF FPS, this is "THP Description")

If this is a Modified THP, check box:

☐ ☐

Date Filed **OCT 08 2010**

Date Approved **MAY 24 2011**

Date Expires **MAY 23 2014**

Extensions 1) ☐ 2) ☐

This Timber Harvesting Plan (THP) form, when properly completed, is designed to comply with the Forest Practice Act (FPA) and Board of Forestry and Fire Protection rules. See separate instructions for information on completing this form. NOTE: The form must be printed legibly in ink or typewritten. The THP is divided into six sections. If more space is necessary to answer a question, continue the answer at the end of the appropriate section of your THP. If writing an electronic version, insert additional space for your answer. Please distinguish answers from questions by *font change*, **bold** or underline.

SECTION I - GENERAL INFORMATION

This THP conforms to my/our plan and upon approval, I/we agree to conduct harvesting in accordance therewith. Consent is hereby given to the Director of Forestry and Fire Protection, and his or her agents and employees, to enter the premises to inspect timber operations for compliance with the Forest Practice Act and Forest Practice Rules.

1. TIMBER OWNER(S) OF RECORD: Name: **California Department of Forestry and Fire Protection**

Address **875 Cypress Avenue**

City **Redding** State **CA** Zip **96001** Phone **(530) 225-2505**

Signature

Date **9/30/10**

NOTE: The timber owner is responsible for payment of a yield tax. Timber Yield Tax information may be obtained at the Timber Tax Section, MIC: 60, State Board of Equalization, P.O. Box 942879, Sacramento, California 94279-0060; phone 1-800-400-7115; BOE Web Page at <http://www.boe.ca.gov>.

2. TIMBERLAND OWNER(S) OF RECORD: Name: **California Department of Forestry and Fire Protection**

Address **875 Cypress Avenue**

City **Redding** State **CA** Zip **96001** Phone **(530) 225-2505**

Signature

Date **9/30/10**

TIMBERLAND OWNER(S) OF RECORD: **Carl J. & Jo Ann Davis (Water drafting only)**

Address: **P.O. Box 142**

City Whitmore State CA Zip 96069 Phone none

Signature: See attached letter Section V Date: _____

RECEIVED
OCT 01 2010
REDDING
FOREST PRACTICE

Section 1

North McMullen Mountain THP

3. LICENSED TIMBER OPERATOR(S): Name Unknown
(If unknown, so state. You must notify CDF of LTO prior to start of operations)

Address _____

City _____ State _____ Zip _____ Phone _____

Signature _____ Date _____

4. PLAN SUBMITTER(S): Name: **California Department of Forestry and Fire Protection**

Address **875 Cypress Avenue**

City **Redding** State **CA** Zip **96001** Phone **(530) 225-2505**

(Submitter must be from 1, 2, or 3 above. He/she must sign below. Ref. Title 14 CCR 1032.7 (a))

Signature Bruce Beech Date 9/20/10

5. a. List person to contact on-site who is responsible for the conduct of the operation. If unknown, so state and name must be provided for inclusion in the THP prior to start of timber operations.

Name **The Plan Submitter or designated RPF will notify CAL FIRE of responsible person prior to start of operations.**

Address _____

City _____ State _____ Zip _____ Phone _____

- b. ☒ Yes ☐ No Will the timber operator be employed for the construction and maintenance of roads and landings during conduct of timber operations? If no, who is responsible?

c. Who is responsible for erosion control maintenance after timber operations have ceased and until certification of the Work Completion Report? If not the LTO, then a written agreement must be provided per 14 CCR 1050 (c).

~~The Licensed Timber Operator. Pursuant to 14 CCR 936.9(p), "The erosion control maintenance period on permanent and seasonal roads and associated landings that are not abandoned in accordance with 14 CCR 923.8 shall be three years."~~ See Revised Page 2.1

6. a. Expected date of commencement of timber operations:

☒ date of THP conformance, or ☐ (date)

- b. Expected date of completion of timber operations:

☒ 3 years from date of THP conformance, or ☐ (date)

7. The timber operation will occur within the:

☐ COAST FOREST DISTRICT

☐ Southern Subdistrict of the Coast F. D.

☐ SOUTHERN FOREST DISTRICT

☐ High use subdistrict of the Southern F. D.

☒ NORTHERN FOREST DISTRICT

☐ The Tahoe Regional Planning Authority Jurisdiction

☐ A County with Special Regulations, identify:

☐ Coastal Zone, no Special Treatment Area

☐ Special Treatment Area(s), type and identify

☐ Other

PART OF PLAN

Revised Item # 5

- c. Who is responsible for erosion control maintenance after timber operations have ceased and until certification of the Work Completion Report? If not the LTO, then a written agreement must be provided per 14 CCR 1050 (c).

The Licensed Timber Operator. Pursuant to 14 CCR 936.9(p), "The erosion control maintenance period on permanent and seasonal roads and associated landings that are not abandoned in accordance with 14 CCR 943.8 shall be three years."

Section 1

PART OF PLAN

North McMullen Mountain THP

8. Location of the timber operation by legal description: covered by USGS 7.5 minute Quad. **Jacks Backbone CA 1995**Base and Meridian: ☒ Mount Diablo ☐ Humboldt ☐ San Bernardino

Section	Township	Range	Acreage	County	Assessor's Parcel Number (Optional)
1 - 3, 11, 12	32N	2E	870	Shasta	

870 TOTAL ACREAGE (Logging Area Only)

Planning Watershed: CALWATER Version, Identification Number, and Name

Version 2.2 Cal Water Planning Watersheds		
Name	Number	Acres w/in watershed
Huckleberry	5507.320102	450 acres
Beal	5507.310103	48 acres
Atkins Creek	5507.310101	372 acres

9. ☐ Yes ☒ No Has a Timberland Conversion been submitted? If yes, list expected approval date or permit number and expiration date if already approved.
10. ☐ Yes ☒ No Is there an approved Sustained Yield Plan for this property? Number Date app.
☐ Yes ☒ No Has a Sustained Yield Plan been submitted but not approved? Number Date sub.
11. ☐ Yes ☒ No Is there a THP or NTMP on file with CDF for any portion of the plan area for which a Report of Satisfactory Stocking has not been issued by CDF?
 If yes, identify the THP or NTMP number(s):
☐ Yes ☒ No Is there a contiguous even aged unit with regeneration less than five years old or less than five feet tall? If yes, explain. Ref. Title 14 CCR 913.1 (933.1, 953.1) (a)(4).
12. ☒ Yes ☐ No Is a Notice of Intent necessary for this THP?
☒ Yes ☐ No If yes, was the Notice of Intent posted as required by 14 CCR 1032.7 (g)?
13. RPF preparing the THP: Name **Benjamin C. Rowe** RPF Number **2686**

Address **875 Cypress Avenue**City **Redding** State **CA** Zip **96001** Phone **(530) 225-2508**

- a. ☐ Yes ☒ No I have notified the plan submitter(s), in writing, of their responsibilities pursuant to 14 CCR 1035 of the Forest Practice Rules.
☐ Yes ☒ No I have notified the timber owner and the timberland owner of their responsibilities for compliance with the Forest Practice Act and rules, specifically the stocking requirements of the rules and the maintenance of erosion control structures of the rules.

The timberland is owned by the California Department of Forestry and Fire Protection and managed by the LaTour Demonstration State Forest (LDSF). The California Department of Forestry and Fire Protection is also the Plan Submitter.

- b. ☒ Yes ☐ No I will provide the timber operator with a copy of the portions of the approved THP as listed in 14 CCR 1035 (f). If "no", who will provide the LTO a copy of the approved THP?

I or my supervised designee will meet with the LTO prior to commencement of operations to advice of sensitive conditions and provisions of the plan pursuant to 14 CCR 1035.2.

- c. I have the following authority and responsibilities for preparation and administration of the THP and timber operation. (Include both work completed and work remaining to be done):

I am responsible for the preparation of the THP including layout, flagging of WLPZ's, designation of timber to be harvested or retained and any additional work deemed necessary for plan approval.

PART OF PLAN

Section 1

North McMullen Mountain THP

Additionally it is my responsibility as the RPF of record to oversee and administer the timber operations described in the THP, explain to the LTO his responsibilities, ensure conformance with the requirements of the plan and the Forest Practice Act and Rules.

I will be present, or ensure that that my designee is present, on the logging area at a sufficient frequency to know the progress of operations and to advise the LTO and timberland owner, but not less than once during the life of the plan.

I am the RPF of record until the department is notified otherwise. I will immediately furnish written notification to the LTO, the plan submitter, and the Department of a decision to withdraw professional services from the plan.

d. Additional required work requiring an RPF, which I do not have the authority or responsibility to perform:

NONE

e. After considering the rules of the Board of Forestry and Fire Protection and the mitigation measures incorporated in this THP, I have determined that the timber operation:

☐ will have a significant adverse impact on the environment. (Statement of reasons for overriding considerations contained in Section III).

☒ will not have a significant adverse impact on the environment.

Registered Professional Forester: I certify that I, or my supervised designee, personally inspected the THP area, and this plan complies with the Forest Practice Act, the Forest Practice Rules and the Professional Foresters Law. If this is a Modified THP, I also, certify that: 1) the conditions or facts stated in 14 CCR 1051 (a) (1) - (16) exist on the THP area at the time of submission, preparation, mitigation, and analysis of the THP and no identified potential significant effects remain undisclosed; and 2) I, or my supervised designee, will meet with the LTO at the THP site, before timber operations commence, to review and discuss the contents and implementation of the Modified THP.

Signature

Byron C Rowe RPF# 2686

Date

9/30/10

SECTION II - PLAN OF TIMBER OPERATIONS

NOTE: If a provision of this THP is proposed that is different than the standard rule, the explanation and justification should normally be included in Section III unless it is clearer and better understood as part of Section II.

14. a. Check the Silvicultural methods or treatments allowed by the rules that are to be applied under this THP. Specify the option chosen to demonstrate Maximum Sustained Production (MSP) according to 14 CCR 913 (933, 953) .11. If more than one method or treatment will be used show boundaries on map and list approximate acreage for each.

<input type="checkbox"/> Clearcutting	ac.	<input type="checkbox"/> Shelterwood Prep. Step	ac.	<input type="checkbox"/> Seed Tree Seed Step	ac.
		<input type="checkbox"/> Shelterwood Seed Step	ac.	<input type="checkbox"/> Seed Tree Removal Step	ac.
		<input type="checkbox"/> Shelterwood Removal Step	ac.		
<input type="checkbox"/> Selection	ac.	<input checked="" type="checkbox"/> Group Selection	<u>753 ac.</u>	<input type="checkbox"/> Transition	ac.
<input type="checkbox"/> Commercial Thinning	ac.	<input type="checkbox"/> Road Right of Way	ac.	<input type="checkbox"/> Sanitation Salvage	ac.
<input type="checkbox"/> Special Treatment Area	ac.	<input checked="" type="checkbox"/> Rehab. of Understocked Area	<u>27 ac.</u>	<input checked="" type="checkbox"/> Fuelbreak	<u>10 ac.</u>
<input type="checkbox"/> Alternative	ac.	<input type="checkbox"/> Variable retention	ac.	<input checked="" type="checkbox"/> Other	<u>80 ac.</u>
				no harvest/ Brush or plantation	

Total acreage 870 ac.: Explain if total is different from that in 8. MSP option chosen: (a) ☒ (b) ☐ (c) ☐

THP 2-02-187 SHA South Cow THP

- b. If Selection, Group Selection, Commercial Thinning, Sanitation Salvage or Alternative methods are selected the post harvest stocking levels (differentiated by site if applicable) must be stated. Note mapping requirements of 1034 (x) (12).

Group Selection: Immediately upon completion of operations the area shall meet the stocking standards of CCR 933.2(a)(2)(A)(2), 75 square feet per acre of basal area shall be retained for Site III lands. The residual stand shall contain sufficient 18 inch DBH trees to meet at least the 15 sq/ft basal area, size, and phenotypic quality of tree requirement specified under the seed tree method as specified in CCR 933.1(c)(1)(A)(1.). Post harvest stocking will be met with group A species.

- c. ☐ Yes ☒ No Will evenage regeneration step units be larger than those specified in the rules (20 acres tractor, 30 acres cable)? If yes, provide substantial evidence that the THP contains measures to accomplish any of subsections (A) - (E) of 14 CCR 913 (933, 953) .1 (a) (2) in Section III of the THP. List below any instructions to the LTO necessary to meet (A) - (E) not found elsewhere in the THP. These units must be designated on map and listed by size.
- d. Trees to be harvested or retained must be marked by or marked under the supervision of the RPF. Specify how the trees will be marked and whether harvested or retained.

All harvest trees shall be marked in Orange paint with a horizontal stripe near breast height and a mark at the stump. A sample area will be marked prior to the preharvest inspection.

- ☐ Yes ☒ No Is a waiver of marking by the RPF requirement requested? If yes, how will LTO determine which trees will be harvested or retained? If yes and more than one silvicultural method, or Group Selection is to be used, how will LTO determine boundaries of different methods or groups?

- e. Forest products to be harvested:

Sawlogs, cull logs, chips, pulp logs, and fuel-wood, poles.

- f. ☐ Yes ☒ No Are group B species proposed for management?
☐ Yes ☒ No Are group B or non-indigenous A species to be used to meet stocking standards?
☐ Yes ☒ No Will group B species need to be reduced to maintain relative site occupancy of A species?

Section 2

North McMullen Mountain THP

If any answer is yes, list the species, describe treatment, and provide the LTO with necessary felling and slash treatment guidance. Explain who is responsible and what additional follow-up measures of manual treatment or herbicide treatment are to be expected to maintain relative site occupancy of A species. Explain when a licensed Pest Control Advisor shall be involved in this process.

g. Other instructions to LTO concerning felling operations

Check all road location flagging, watercourse flagging, WLPZ boundary flagging, EEZ and ELZ flagging, and skid trail flagging prior to the commencement of any falling operations. Have the responsible RPF or supervised designee replace any flagging that is incomplete or unclear.

Trees designated for removal within the EEZ or ELZ shall be directionally felled towards the perimeter and away from the protection zone and endlined, so as to keep heavy equipment out of the protection zone. In the ELZ of Class III watercourses, trees may be felled bridging the watercourse and endlined from outside the ELZ. The purpose of this measure is to allow for trees that if not directionally felled across the ELZ would fall into the ELZ or damage the residual stand.

h. ☒ Yes ☐ No Will artificial regeneration be required to meet stocking standards?

i. ☒ Yes ☐ No Will site preparation be used to meet stocking standards? If yes, provide the information required for a site preparation addendum, as per 14 CCR 915.4 (935.4, 955.4).

Site Preparation Addendum per 14 CCR 935.4 (a)-(h)

- a) Site preparation will occur within Rehabilitation Unit and may occur within the groups of the Group Selections silviculture.
 - b) Methods of site preparation may include manual slashing of sub-merchantable unharvested material, brushraking logging slash and brush into burn piles, contour ripping and chemical control of competing vegetation.
 - c) Mechanical equipment – excavator, bulldozer with rippers.
 - d) All site preparation activities are prohibited within the WLPZs of Class I and Class II watercourses, and within the ELZs designated for protection of Class III watercourses, springs and seeps.
 - e) No exceptions or alternatives to the standard rules are requested.
 - f) LTO shall be amended into the plan prior to the start of any mechanical site preparation.
 - g) All site preparation shall be conducted between May 1 and November 15
 - h) Pile construction and burning shall adhere to Item 31 within this THP.
 - i) The Rehabilitation Unit shall be planted with group A species within three years of completion of operations.
- j. If the rehabilitation method is chosen provide a regeneration plan as required by 14 CCR 913 (933, 953) .4 (b).

The Rehabilitation Unit shall be artificially regenerated. The unit shall be planted with Group A species within three years following completion of operations. An average of 300 seedlings per acre shall be planted. The seedlings shall be from the appropriate seed zone and elevation band.

Section 2
PESTS

PART OF PLAN North McMullen Mountain THP

15. a. ☐ Yes ☒ No Is this THP within an area that the Board of Forestry and Fire Protection has declared a Zone of Infestation or Infection, pursuant to PRC 4712 - 4718? If yes, identify feasible measures being taken to mitigate adverse infestation or infection impacts from the timber operation. See 14 CCR 917 (937, 957) .9 (a).
- b. ☒ Yes ☐ No If outside a declared zone, are there any insect, disease or pest problems of significance in the THP area? If yes, describe the proposed measures to improve the health, vigor, and productivity of the stand(s).

Located within the Rehabilitation unit and in smaller pockets throughout the THP, the Red Fir is heavily infected with dwarf mistletoe and *Cytospora spp* and the Western White pine is infected with blister rust. Both the Red Fir and the Western White Pine are experiencing a heavy die off.

To the extent possible the infected trees shall be marked for harvest to reduce the spread of infestation.

HARVESTING PRACTICES

16. Indicate type of yarding system and equipment to be used:

- | GROUND BASED* | CABLE | SPECIAL |
|---|--|--|
| a. <input checked="" type="checkbox"/> Tractor, including end/long lining | d. <input type="checkbox"/> Cable, ground lead | g. <input type="checkbox"/> Animal |
| b. <input checked="" type="checkbox"/> Rubber tired skidder, Forwarder | e. <input type="checkbox"/> Cable, high lead | h. <input type="checkbox"/> Helicopter |
| c. <input checked="" type="checkbox"/> Feller buncher | f. <input type="checkbox"/> Cable, Skyline | i. <input type="checkbox"/> Other |
- * All tractor operations restrictions apply to ground based equipment.

17. Erosion Hazard Rating: Indicate Erosion Hazard Ratings present on THP. (Must match EHR worksheets)

☒ Low ☒ Moderate ☐ High ☐ Extreme
If more than one rating is checked, areas must be delineated on map down to 20 acres in size (10 acres for high and Extreme EHRs in the Coast District).

18. Soil Stabilization: In addition to the standard waterbreak requirements describe soil stabilization measures or additional erosion control measures to be implemented and the location of their application. See requirements of 14 CCR 916.7 (936.7, 956.7), and 923.2 (943.2, 963.2) (m), and 923.5 (943.5, 963.5) (f).
1. Stabilization measures shall be selected that will prevent significant soil loss or sediment transport into Class I, Class II and Class III waters and may include, but need not be limited to, mulching, rip-rapping, grass seeding, or chemical stabilizers. Preference to which stabilization measure to be used, if the need occurs, shall be based upon on site conditions and the availability of treatment materials. If appropriate for the site, mulching will be the method of choice.
 2. Mulch shall consist of straw or other material that is less than 3 inches in diameter (i.e. logging slash or brush). Straw mulch shall cover > 90% of the exposed area at an applied depth of > 2 inches. If logging slash or brush is used for mulch it shall be compacted by equipment and cover 90% of the exposed area.
 3. Where the undisturbed natural ground cover cannot effectively protect beneficial uses of water from timber operations, the ground shall be treated by measures including, but not limited to, seeding, mulching, or replanting, in order to retain and improve its natural ability to filter sediment, minimize soil erosion, and stabilize banks of watercourses and lakes. Treatments shall meet the standards described in item 1 and 2 above.

4. Waterbreaks shall be constructed as soon as practical upon conclusion of use of skid trails, roads, and landings, which do not have permanent and adequate drainage facilities, or drainage structures.

The maximum distance between waterbreaks on all roads and skid trails within the THP area shall not exceed the following standards except where natural drainage will occur, i.e., low spots, draws, and depressions. In these areas, any berm on the downhill side of the road or skid trail shall be removed to allow drainage and a drainage facility shall not be constructed.

Road or Trail Gradient (%)	10 or Less	11-25	26-50
Low EHR	300 ft	200 ft.	150 ft.
Moderate EHR	200 ft.	150 ft.	100 ft.

Waterbreaks shall be cut diagonally a minimum of 6 inches into the firm roadbed or skid trail surface and shall have a continuous firm embankment of at least 6 inches in height immediately adjacent to the lower edge of the waterbreak cut.

Waterbreaks shall be located to allow water to be discharged into some form of vegetative cover, duff, slash, rocks, or less erodible material wherever practical, and shall be constructed to provide for unrestricted discharge at the lower end of the waterbreak so that water will be discharged and spread in such a manner that erosion and sediment transport shall be minimized. Where waterbreaks cannot effectively disperse surface runoff, including where waterbreaks on roads and skid trails cause surface runoff to be concentrated on down-slopes, roads, or skid trails, other erosion control methods, as described in 1 above, shall be installed as needed to comply with 14 CCR 934.

5. Soil stabilization of logging roads - Permanent drainage facilities (rolling dips or drivable waterbars) shall be constructed on appurtenant seasonal roads used for this operation. These drainage facilities shall be constructed prior to the completion of hauling on all road segments where practical. Where pre-haul drainage facilities are not feasible, the standard waterbreak construction and spacing specifications will be used.
6. All outside berms along roads created from grading or truck traffic during operations shall be pulled back onto the road surface prior to completion of use and final road grading. Where feasible, and to the extent that can reasonably be done with minor road dressing and grading, existing side-hill roads shall be outsloped.
7. The traveled surface of logging roads shall be treated to prevent waterborne transport of sediment and concentration of runoff that results from timber operations. Consequently, during timber operations, road running surfaces in the logging area shall be treated as necessary to prevent excessive loss of road surface materials by watering as per 943.4 (h).

Additional requirements

- A. Pursuant to 14 CCR 936.9(n), exposed areas, >100 square feet, approaches to watercourse crossings between the drainage facilities closest the watercourse, and road cuts and fills within the WLPZ, and within any EEZ or ELZ designated for watercourse or lake protection, shall be treated to stabilize soils, minimize soil erosion, and prevent the discharge of sediment into waters in amounts deleterious to the beneficial uses of water. Treatments shall meet the standards described in item 1 and 2 above.

APR 25 2017

B. Timing requirements for all erosion prevention activities within ASP watersheds.

1. For areas disturbed from May 1 to October 15, treatment shall be completed prior to the start of any rain that causes overland flow across or along the disturbed surface that could deliver sediment into a watercourse or lake in quantities deleterious to the beneficial uses of water.
2. For areas disturbed from October 16 through April 30, treatment shall be completed prior to any day for which a chance of rain of 30 percent or greater is forecast by the National Weather Service or within 10 days, whichever is earlier.
3. All tractor roads shall have drainage facilities installed as soon as practical following yarding and any day with a National Weather Service forecast of chance of rain 30 percent or more, a flash flood warning, or a flash food watch as specified in CCR 14 936.9(m).

C. The erosion control maintenance period on permanent and seasonal roads and associated landings that are not abandoned in accordance with 14 CCR 936.9 (p) shall be three years.

MAY 2010

Section 2

North McMullen Mountain THP

19. ☐ Yes ☒ No Are tractor or skidder constructed layouts to be used? If yes, specify the location and extent of use:
20. ☐ Yes ☒ No Will ground based equipment be used within the area(s) designated for cable yarding? If yes, specify the location and for what purpose the equipment will be used. See 14 CCR 934.3 (e).
21. Within the THP area will ground based equipment be used on:
- a. ☐ Yes ☒ No Unstable soils or slide areas? Only allowed if unavoidable.
 - b. ☐ Yes ☒ No Slopes over 65%?
 - c. ☐ Yes ☒ No Slopes over 50% with high or extreme EHR?
 - d. ☐ Yes ☒ No Slopes between 50% and 65% with moderate EHR where heavy equipment use will not be restricted to the limits described in 14 CCR 914 (934, 954) .2 (f) (2) (i) or (ii)?
 - e. ☐ Yes ☒ No Slopes over 50% which lead without flattening to sufficiently dissipate water flow and trap sediment before it reaches a watercourse or lake?

If "a". is yes, provide site specific measures to minimize effect of operations on slope stability below. Provide explanation and justification in section III as required per 14 CCR 914 (934, 954) .2 (d). CDF requests the RPF consider flagging tractor road locations if "a." is yes.

If b., c., d. or e. is yes:

- 1) the location of tractor roads must be flagged on the ground prior to the PHI or start of operations if a PHI is not required, and
- 2) you must clearly explain the proposed exception and justify why the standard rule is not feasible or would not comply with 14 CCR 914 (934, 954).

The location of heavy equipment operation on unstable areas or any use beyond the limitations of the standard rules must be shown on the map. List specific instructions to the LTO below.

22. ☐ Yes ☒ No Are any alternative practices to the standard harvesting or erosion control rules proposed for this plan? If yes, provide all the information as required by 14 CCR 914 (934, 954) .9 in Section III. List specific instructions to the LTO below.

Section 2
WINTER OPERATIONS

North McMullen Mountain THP

23. a. ☒ Yes [] No Will timber operations occur during the winter period? If yes, complete "b, c, or d." State in space provided if exempt because yarding method will be cable, helicopter, or balloon.
- b. [] Yes ☒ No Will mechanical site preparation be conducted during the winter period? If yes, complete "d".
- c. [] I choose the in-lieu option as allowed in 14 CCR 914 (934, 954) .7 (c). Specify below the procedures listed in subsections (1) and (2), and list the site specific measures for operations in the WLPZ and unstable areas as required by subsection (3), if there will be no winter operations in these areas, so state.
- d. ☒ I choose to prepare a winter operating plan per 14 CCR 914 (934, 954) .7 (b).

The following winter operation plan is for all timber operations taking place between the dates of October 15 to May 1 in any year of operations. The harvesting activities that may occur during the operational period include but not limited to felling timber, yarding with ground-based equipment, decking logs and hauling logs. Road construction and abandonment shall not occur during the Winter Period.

WINTER OPERATING PLAN

1. The erosion hazard rating in the THP is low and moderate.
2. No mechanical site preparation is proposed during the Winter Period.
3. The yarding system is ground based.
4. The operational period for this plan is between October 15 to May 1. Operations will be allowed under the following conditions: 1) when dry, 2) rainless, 3) hard frozen conditions exist, 4) and when soils are not saturated. Use of heavy equipment or trucks on roads and landings shall be limited to a stable operating surface. Refer to "Definitions" below for the definitions of hard frozen conditions, stable operating surface and saturated soil conditions.
5. Erosion control facilities timing: All erosion controls and drainage facilities shall installed as soon as practical following yarding and prior to either (1) the start of any rain which causes overland flow across or along the disturbed surface within a WLPZ or within any ELZ or EEZ designated for watercourse or lake protection, or (2) any day with a National Weather Service forecast of a chance of rain of 30 percent or more, a flash flood warning, or a flash flood and prior to any weekend shut down periods.
6. Precipitation (Consideration in form of rain or snow): Precipitation in the THP area is primarily in the form of snow between October 31 and April 30. Spring rains usually fall onto a substantial snow pack and snow persists until middle to late May with snow drifts present until mid June. Drainage facilities shall be kept in effective condition throughout operations conducted during the winter period.
7. Ground conditions (soil moisture condition, frozen): Suitable ground conditions that will allow for timber operations are hard frozen conditions, soils with low antecedent soil wetness and the roads and landings must maintain a stable operating surface.
8. Silvicultural system-ground cover. Healthy regeneration, slash, needle cast and existing ground cover will ensure adequate ground cover to dissipate rainfall impact and runoff.
9. Operations within the WLPZ: Designated harvest trees within the WLPZ of Class II watercourses are to be felled toward the perimeter of the zone and end-lined out. All watercourse crossing facilities not constructed to permanent crossing standards shall be removed before November 15.

10. Equipment use limitations:

14 CCR 936.9 (l), (3), Logging roads, landings and tractor roads shall not be used when sediment from the logging road, landing or tractor road surface may be transported to a watercourse or a drainage facility in quantities sufficient to cause a visible increase in turbidity of downstream waters in receiving Class I, II, III or IV waters or that violate Water Quality Requirements.

14 CCR 936.9 (l), (4), Logging roads and landings shall not be used for log hauling when saturated soil conditions may produce sediment in quantities sufficient to cause a visible increase in turbidity of downstream waters in receiving Class I, II, III or IV waters or that violate Water Quality Requirements.

11. Known Unstable Areas. No known unstable areas are within the plan area.

Definitions

Low Antecedent Soil Wetness is defined as conditions not meeting the threshold of saturated soil conditions.

14 CCR 895.1 (Definitions):

Hard Frozen Conditions means those frozen soil conditions where loaded or unloaded vehicles can travel without sinking into the road surfaces to a depth of more than six inches over a distance of more than 25 feet.

Saturated soil conditions means that soil and/or surface material pore spaces are filled with water to such an extent that runoff is likely to occur. Indicators of saturated soil conditions may include, but are not limited to: (1) areas of ponded water, (2) pumping of fines from the soil or road surfacing material during timber operations, (3) loss of bearing strength resulting in the deflection of soil or road surfaces under a load, such as the creation of wheel ruts, (4) spinning or churning of wheels or tracks that produces a wet slurry, or (5) inadequate traction without blading wet soil or surfacing materials.

Soils or road and landing surfaces that are hard frozen are excluded from this definition.

Stable operating surface means a road or landing surface that can support vehicular traffic and has a structurally sound road base appropriate for the type, intensity and timing of intended use.

Winter period means the period between November 15 and April 1, except as noted under special County Rules at Title 14 CCR 925.1, 926.18, 927.1, and 965.5.

PART OF PLAN

24. Will any roads be constructed? ☐ Yes ☒ No, or reconstructed? ☐ Yes ☒ No. If yes, check items "a." through "g."
Will any landings be constructed? ☐ Yes ☒ No, or reconstructed? ☐ Yes ☒ No. If yes, check items "h." through "k."
- a. ☐ Yes ☒ No Will new or reconstructed roads be wider than single lane with turnouts?
b. ☐ Yes ☒ No Are logging roads proposed in areas of unstable soils or known slide-prone areas?
c. ☐ Yes ☒ No Will new roads exceed a grade of 15% or have pitches of up to 20% for distances greater than 500 feet? Map must identify any new or reconstructed road segments that exceed an average 15% grade for over 200 feet.
d. ☐ Yes ☒ No Are roads to be constructed or reconstructed, other than crossings, within the WLPZ of a watercourse? If yes, completion of THP Item 27 a. will satisfy required documentation.
e. ☐ Yes ☒ No Will roads be located across more than 100 feet of lineal distance on slopes over 65%, or on slopes over 50% which are within 100 feet of the boundary of a WLPZ?
f. ☒ Yes ☐ No Will any roads or watercourse crossings be abandoned?
g. ☐ Yes ☒ No Are exceptions proposed for flagging or otherwise identifying the location of roads to be constructed?
h. ☐ Yes ☒ No Will any landings exceed one half acre in size? If any landing exceeds one quarter acre in size or requires substantial excavation the location must be shown on the map.
i. ☐ Yes ☒ No Are any landings proposed in areas of unstable soils or known slide prone areas?
j. ☐ Yes ☒ No Will any landings be located on slopes over 65% or on slopes over 50% which are within 100 feet of the boundary of a WLPZ?
k. ☐ Yes ☒ No Will any landings be abandoned?
25. If any section in "item 24" above is answered yes, specify site-specific measures to reduce adverse impacts and list any additional or special information needed by the LTO concerning the construction, maintenance, and/or abandonment of roads or landings, as required by 14 CCR Article 12. Include required explanation and justification in THP Section III.

Road abandonment

Pursuant to 14 CCR 943.8, road abandonment shall be conducted in a manner which provides for permanent maintenance-free drainage, minimizes concentration of runoff, soil erosion and slope instability, prevents unnecessary damage to soil resources, promotes regeneration, and protects the quality and beneficial uses of water.

Approximately 1000 feet of road of the White Fawn road shall be abandoned. This segment of road is has been identified within the LDSF 2008 Management Plan as a high priority for repair. This segment of road has heavily eroded ditches on either side of the road. There are two culvert cross drains and two Class III watercourse crossing (WC 1, WC 2) that will be removed with the abandonment of the road segment. The abandoned road segment shall be blocked so that standard production four wheel-drive highway vehicles cannot pass the point of closure at the time of abandonment. Additionally to provide dispersal of water flow and prevent erosion of the abandoned road surface, large water bars (24 inches plus) shall be install along the abandoned road segment.

The Old Peavine Road has been abandoned in the past, but a segment of the road is still accessible to vehicular traffic. The road shall be barricaded, preventing passage to standard four-wheeled drive vehicles, at the intersection of the Old Peavine Road and the White Fawn Road.

Watercourse crossing abandonment

The following shall apply to the abandonment of crossings:

- 1) Fills shall be excavated to form a channel that is as close as feasible to the natural watercourse grade and orientation, and that is wider than the natural channel.
- 2) The excavated material and any resulting cut bank shall be sloped back from the channel and stabilized to prevent slumping and to minimize soil erosion. Where needed, this material shall be stabilized by seeding, mulching, rock armoring, or other suitable treatment.

WATERCOURSE AND LAKE PROTECTION ZONE (WLPZ) AND DOMESTIC WATER SUPPLY PROTECTION MEASURES

26. a. ☒ Yes ☐ No Are there any watercourse or lakes which contain Class I through IV waters on or adjacent to the plan area? If yes, list the class, WLPZ or ELZ width, and protective measures determined from Table I and/or 14 CCR 916 (936, 956) .4 (c) of the WLPZ rules for each watercourse. Specify if Class III or IV watercourses have WLPZ , ELZ or both.

NON ASP WatershedsClass II watercourses

The Class II watercourses have been flagged with blue and white striped flagging. Consistent with 14 CCR 936.5 all of the class II watercourses have at least the minimum widths as shown in the table below.

Slope Class %	< 30%	30% - 50%
WLPZ width in feet	50 ft.	75 ft.

Pursuant to 14 CCR 936.5(e) "E", to ensure retention of shade canopy filter strip properties and the maintenance of wildlife values described in 14 CCR 936.4(b) a base mark shall be placed below the cut line of the harvest trees within the zone in advance of timber operations by an RPF or supervised designee. Additionally, pursuant to 14 CCR 936.5(e) "I" To protect water temperature, filter strip properties, upslope stability, and fish & wildlife values, at least 50% of the total canopy covering the ground shall be left in a well distributed multi-storied stand configuration composed of a diversity of species similar to that found before the start of operations. The residual overstory canopy shall be composed of at least 25% of the existing overstory conifers. As is with class I watercourses, all class II watercourses shall comply with 14 CCR 936.3(g) recruitment of large woody debris for instream habitat shall be provided by retaining at least two living conifers per acre at least 16 inches dbh and 50ft. tall within 50 ft.

Class III watercourses

Pursuant to 14 CCR 936.4(c)(1), Class III watercourses shall have a 25-foot ELZ on slopes less than 30% and a 50-foot ELZ on slopes greater than 30%.

Class III watercourse ELZs shall be flagged with blue and white striped flagging prior to start of operations. The ELZs shall be flagged by the RPF or supervised designee. Within the ELZ of Class III watercourses, equipment shall be allowed to operate on existing roads, prepared crossings and designated tractor road crossings. At least 50% of the understory vegetation present before timber operations shall be left living and well distributed within the ELZ to maintain soil stability. Note: "ELZ" means, "Equipment Limitation Zone" and shall be defined as follows: a) all heavy equipment is to be excluded from operating within the ELZ except on existing skid trails, skid trail crossings and existing haul roads, b) approved existing skid trails and existing skid trail crossings have been identified on the ground with yellow flagging. c) Approved skid trail crossings shall only be used when dry.

ASP Watersheds

In accordance to 936.9 (v) and consultation with the California Department of Fish and Game, the following are the protection measures for watercourses located within ASP Watersheds. Specifically, the following protections measures will be implemented on the Class I, Class II, and Class III watercourses located in the Lee March Gulch drainage. Justification and explanation is located within Section III of this THP.

Class I watercourse (Lee March Gulch)

The Watercourse Lake and Protection Zone (WLPZ) boundary has been delineated with blue and white striped flagging. The WLPZ is a 75 feet no cut zone.

Class II (L) watercourse

All the Class II watercourses with in the Lee March Gulch drainage are spring fed and they originate within 1000 feet of the Class I reach of Lee March Gulch. Class II (L) watercourses will be protected as Class II (S) watercourses. There are no Class II (S) watercourses within the THP.

The Class II watercourses have been flagged with blue and white striped flagging. Consistent with 14 CCR 936.5 all of the Class II watercourses have at least the minimum widths as shown in the table below.

Slope Class %	< 30%	30% - 50%
WLPZ width in feet	50 ft.	75 ft.
Core width in feet	10 ft.	10 ft.

Within the Core, no harvest is proposed. Pursuant to 14 CCR 936.5(e) "E", to ensure retention of shade canopy filter strip properties and the maintenance of wildlife values described in 14 CCR 936.4(b) a base mark shall be placed below the cut line of the harvest trees within the zone in advance of timber operations by an RPF or supervised designee. Additionally, pursuant to 14 CCR 936.5(e) "I" To protect water temperature, filter strip properties, upslope stability, and fish & wildlife values, at least 50% of the total canopy covering the ground shall be left in a well distributed multi-storied stand configuration composed of a diversity of species similar to that found before the start of operations. The residual overstory canopy shall be composed of at least 25% of the existing overstory conifers. As is with class I watercourses, all class II watercourses shall comply with 14 CCR 936.3(g) recruitment of large woody debris for instream habitat shall be provided by retaining at least two living conifers per acre at least 16 inches dbh and 50ft. tall within 50 ft.

Class III watercourses

Class III watercourse ELZs shall be flagged with blue and white striped flagging prior to start of operations. The ELZs shall be flagged by the RPF or supervised designee. All Class III watercourses shall have a 25-foot ELZ on slopes less than 30% and a 50-foot ELZ on slopes greater that 30%.

Pursuant to 936.9 (h)(2-7): (2) Retain all pre-existing large wood on the ground within the ELZ that is stabilizing sediment and is necessary to prevent potential discharge into the watercourse. (3) Retain all pre-existing down wood and debris in the channel zone. (4) Retain hardwoods, where feasible, within the ELZ. (5) Retain all snags (except as required for safety) within the ELZ. (6) Retain all countable trees needed to achieve resource conservation standards in 14 CCR § 912.7 [932.7, 952.7] within the ELZ. (7) Retain all trees in the ELZ and channel zone which show visible indicators of

PART OF PLAN

Section 2

North McMullen Mountain THP

providing bank or bed stability, excluding sprouting conifers that do not have boles overlapping the channel zone. Visible indicators of stability include roots that permeate the bank or provide channel grade control.

Within the ELZ of Class III watercourses, ground-based operations are limited to existing stable tractor roads that show no visible evidence of sediment deposition being transported into the adjacent watercourse. Equipment shall be allowed to operate on pre-flagged existing roads, prepared crossings and designated tractor road crossings. At least 50% of the understory vegetation present before timber operations shall be left living and well distributed within the ELZ to maintain soil stability

Note: "ELZ" means, "Equipment Limitation Zone" and shall be defined as follows: a) all heavy equipment is to be excluded from operating within the ELZ except on pre-flagged existing skid trails, pre-flagged, skid trail crossings and existing haul roads, b) approved existing skid trails and existing skid trail crossings have been identified on the ground with yellow flagging. c) Approved skid trail crossings shall only be used when dry.

- b. ☒ Yes ☐ No Are there any watercourse crossings that require mapping per 14 CCR 1034 (x) (7)?
c. ☐ Yes ☒ No Will tractor road watercourse crossings involve the use of a culvert? If yes state minimum diameter and length for each culvert (may be shown on map).
d. ☐ Yes ☒ No Is this THP Review Process to be used to meet Department of Fish and Game CEQA review requirements? If yes, attach the 1603 Addendum below or at the end of this Section II; provide the background information and analysis in Section III; list instructions for LTO below for the installation, protection measures, and mitigation measures; as per THP Form Instructions or CDF Mass Mailing, 07/02/1999, "Fish and Game Code 1603 Agreements and THP Documentation".

During the preparation of the THP, and the implementation of LaTour Demonstration State Forest's 2008 Management Plan (State Clearinghouse number 2008062009) all road segments and watercourse crossings have been evaluated and rated as to the risk to water quality. The evaluation included, but was not limited to, erosion potential, watercourse crossing types, frequency and placement of drainage structures, and the condition of all road watercourse crossings and drainage features. All watercourse crossings and drainage features that are not designated for removal are functioning properly.

Non Classified Draw Protection

No draws, swales, or channels shall be used as skid trails. Skid trail crossings of these non-classified draws, swales, and channels shall be kept to a minimum. Existing crossings shall be used where feasible and shall be as close to a 90-degree angle as possible.

Seeps and Springs

Seeps and springs and shall be protected with a minimum 25 feet ELZ and a minimum 50 feet where side slopes are greater than 30%. Equipment shall be limited to existing pre-flagged skid trails. These trails shall be flagged by the RPF or supervised designee prior to the start of operations. Equipment at no time will be allowed within the wet area of the seeps and springs. Additionally to protect water temperature, filter strip properties, upslope stability, and fish & wildlife values, at least 50% of the total canopy covering the ground shall be left in a well distributed multi-storied stand configuration composed of a diversity of species similar to that found before the start of operations. The residual overstory canopy shall be composed of at least 25% of the existing overstory conifers

Section 2

North McMullen Mountain THP

27. Are site specific practices proposed in-lieu of the following standard WLPZ practices?

- a. ☒ Yes ☐ No Prohibition of the construction or reconstruction of roads, construction or use of tractor roads or landings in Class I, II, III, or IV watercourses, WLPZs, marshes, wet meadows, and other wet areas except as follows:
- (1) At prepared tractor road crossings.
 - (2) Crossings of Class III watercourses which are dry at time of timber operations.
 - (3) At existing road crossings.
 - (4) At new tractor and road crossings approved by Department of Fish and Game.
- b. ☐ Yes ☒ No Retention of non-commercial vegetation bordering and covering meadows and wet areas?
- c. ☐ Yes ☒ No Directional felling of trees within the WLPZ away from the watercourse or lake?
- d. ☐ Yes ☒ No Decrease of width(s) of the WLPZ(s)?
- e. ☐ Yes ☒ No Protection of watercourses which conduct class IV waters?
- f. ☒ Yes ☐ No Exclusion of heavy equipment from the WLPZ except as follows:
- (1) At prepared tractor road crossings.
 - (2) Crossings of Class III watercourses which are dry at time of timber operations.
 - (3) At existing road crossings.
 - (4) At new tractor and road crossings approved by Department of Fish and Game.
- g. ☐ Yes ☒ No Establishment of ELZ for Class III watercourses unless sideslopes are <30% and EHR is low?
- h. ☐ Yes ☒ No Retention of at least 50% of the overstory canopy in the WLPZ?
- i. ☐ Yes ☒ No Retention of at least 50% of the understory in the WLPZ?
- j. ☐ Yes ☒ No Are any additional in-lieu or any alternative practices proposed for watercourse or lake protection?

NOTE: A yes answer to any of items "a." through "j." constitutes an in-lieu practice. If any item is answered yes, refer to 14 CCR 916 (936, 956).1 and address the following for each item checked yes:

1. The RPF shall state the standard rule;
2. Explain and describe each proposed practice;
3. Explain how the proposed practice differs from the standard practice;
4. The specific location where it shall be applied, see map requirements of 14 CCR 1034 (x) (15) and (16);
5. Provide in THP Section III an explanation and justification as to how the protection provided is equal to the standard rule and provides for the protection of the beneficial uses of water, as per 14 CCR 916 (936, 956) .1 (a). Reference the in-lieu and location to the specific watercourse to which it will be applied.

Landing and Associated Skid Trails within WLPZs and Class III ELZs

There are four landings (L1- 4) and associated skid trails proposed for use that are currently within or partially within a WLPZ (Refer to Roads and Landings Map). In these areas, skidders or tractors will be allowed to skid logs into the WLPZ to the landing and return on existing skid trails only. No new construction of skid trails or roads is proposed in WLPZs. Normal landing operations including limbing, bucking, sorting, and decking may occur on the landings.

The standard rule, 14 CCR 936.3(c) states, "The timber operator shall not use landings or skid trails in the WLPZ unless explained and justified in the THP by the RPF, and approved by the Director" and 14 CCR 936.4(d) states, "Heavy equipment shall not be used in timber falling, yarding, or site preparation within the WLPZ unless such use is explained and justified in the THP and approved by the Director". The proposed in-lieu practice differs from the standard rules in that it allows limited use of designated landings and skid trails within the WLPZ.

- Only existing, pre-flagged skid trails shall be used within the WLPZ. Approved skid trails shall be flagged with yellow flagging by the RPF.
- The outside edge of the landing shall be defined by the RPF or designee with white flagging prior to operations. No operations, including decking of logs and parking equipment, shall occur beyond the flagged limits. If necessary to prevent sediment delivery to a watercourse or other wet area, brow logs will be placed between the active portion of the landing or skid trail and the watercourse.
- Existing vegetation between the outside edge of the landings (brow logs) and the watercourses shall remain undisturbed.
- No material shall be side cast off the landing or skid trail surface towards the watercourse.
- Landings and skid trails shall be stabilized as specified in Item 18 above.

L1: is located adjacent to a Class I WLPZ in SW ¼ of Section 2, Township 32 North, Range 2 East. The access road to landing is rock and all landing operations can occur outside the WLPZ by migrating the landing to the west. There is approximately 75 feet of an existing skid trail located on the east side of Lee March Gulch. The logs will be skidded down to the graveled road and then across the existing culvert road crossing to L1.

L2: is located adjacent to and partially within a Class II WLPZ (White Fawn Gulch) along the section line between Sections 1 and 2, Township 32 North, Range 2 East. Operations will be conducted as described above with brow logs being placed at the flagged landing boundary near the WLPZ and blocking old road that extends uphill and parallel to the WLPZ. The old road shall not be utilized during operations and shall be barricaded to all vehicular traffic upon completion of operations.

Additionally there is a skid trail located partially within the WLPZ, on the east side of White Fawn Gulch. The skid trail will be utilized to skid logs down to the road. Once the logs are on the road they will be skidded across an existing culvert road crossing to L2.

L3: is located on the White Fawn Road in the SW ¼ of Section 2, Township 32 North, Range 2 East. A Class III watercourse bisects the eastern side of the landing. Following the previous harvest the watercourse reestablished itself across the landing. There are also two skid trails that cross the Class III watercourse prior to entering the landing. The portion of the landing on the east side of the Class III watercourse shall not be utilized for landing operations and the two skid trails shall be joined together outside the ELZ and only utilize one skid crossing. Upon completion of use of the landing the skid crossing shall be pulled and the watercourse reestablished across the landing and the road. Upon reestablishing the watercourse across the landing the road the LTO shall armor the watercourse crossing channel and a minimum of 10 feet of each approach with fractured rock 4-6 inches in size and a compacted depth of at least 6 inches. The reestablished watercourse channel shall be at least 8 feet in width across the road. All exposed soil within the ELZ shall be stabilized as specified in Item 18 of this THP.

L4: is located adjacent to and partially within a Class II WLPZ (Peavine Gulch) in the center of Sections 1, Township 32 North, Range 2 East. Operations will be conducted as described above. A section of the Old Peavine Road will be utilized as a skid trail. Upon completion of use the Old Peavine Road shall be barricaded as described in Item 25 of this THP.

L5: is located within the ELZ of a Class III watercourse in the SW ¼ of Section 1, Township 32 North, Range 2 East. There is also one designated skid trail and two skid trail crossings associated with the use of this landing. Operations will be conducted as described above, and the skid trail crossings shall be removed as described below.

Roads within WLPZ

Though not an in-lieu practice road segments exist that are adjacent to and fall within the WLPZ of a Class I and Class II watercourse. These segments are to be used for normal vehicular traffic, and log hauling. Equipment will also be allowed to travel on these roads and perform the necessary road maintenance. These road segments are located along Lee March Gulch and are delineated on the THP Map. These segments were surfaced with rock in 1999.

In preparing the THP these road segments were reviewed and assessed for any negative impacts to the beneficial uses of water. The THP is correcting identified issues related to the road system and no negative impacts are anticipated as a result of the proposed operations. These road segments are well established, several segments have rock surfaces and all are stable.

FEB 08 2011

Tractor road skid crossings

Only Pre-Flagged, existing Class III skid trail watercourse crossing, which are dry during the time of operations shall be used. Upon completion of use the crossings shall be removed to the following standards:

- (1) Fills shall be excavated to form a channel that is as close as feasible to the natural watercourse grade and orientation, and that is wider than the natural channel.
- (2) The excavated material and any resulting cut bank shall be sloped back from the channel and stabilized to prevent slumping and to minimize soil erosion. Where needed, this material shall be stabilized as described in Item 18 of this THP.

Section 2

North McMullen Mountain THP

28. a. ☒ Yes ☐ No Are there any landowners within 1000 feet downstream of the THP boundary whose ownership adjoins or includes a class I, II, or IV watercourse(s) which receives surface drainage from the proposed timber operations? If yes, the requirements of 14 CCR 1032.10 apply. Proof of notice by letter and newspaper should be included in THP Section V. If No, "28 b." need not be answered.
- b. ☒ Yes ☐ No Is an exemption requested of the notification requirements of 14 CCR 1032.10? If yes, an explanation and justification for the exemption must appear in THP Section III. Specify if requesting an exemption from the letter, the newspaper notice or both.
- c. ☐ Yes ☒ No Was any information received on domestic water supplies that required additional mitigation beyond that required by standard Watercourse and Lake Protection rules? If yes, list site specific measures to be implemented by the LTO.
29. ☐ Yes ☒ No Is any part of the THP area within a Sensitive Watershed as designated by the Board of Forestry and Fire Protection? If yes, identify the watershed and list any special rules, operating procedures or mitigation that will be used to protect the resources identified at risk?

HAZARD REDUCTION

30. a. ☒ Yes ☐ No Are there roads or improvements which require slash treatment adjacent to them? If yes, specify the type of improvement, treatment distance, and treatment method.
- b. ☐ Yes ☒ No Are any alternatives to the rules for slash treatment along roads and within 200 feet of structures requested? If yes, RPF must explain and justify how alternative provides equal fire protection. Include a description of the alternative and where it will be utilized below.

Within 100 feet of the edge of the traveled surface of public roads, slash created and trees knocked down by timber operations shall be treated by lopping for fire hazard reduction, piling and burning, chipping, burying or removal from the zone. All roads within the THP boundary and appurtenant roads within LDSF are public roads.

31. ☒ Yes ☐ No Will piling and burning be used for hazard reduction? See 14 CCR 917.1-.11, 937.1-.10, or 957.1-.10, for specific requirements. Note: LTO is responsible for slash disposal. This responsibility cannot be transferred.

LTO is responsible for slash disposal. Any landing slash that is not spread back onto skid trails or removed as chips, shall be piled near the center of the landing. Piles shall not exceed 50 x 50 x 20 feet with a fire line completely around the pile that has a width at least 1.5 times the height of the pile to a maximum of 30 feet. Efforts shall be made to ensure that these piles are as compact and free of soil as practical. Material shall be piled at or near its final location to minimize the amount of movement necessary and subsequent soil deposition in the piles. Slash piles created prior to September 1 of each year shall be burned that fall when safe burning conditions occur. Slash piles created after September 1 of each year may be burned the following fall, prior to December 15, when safe burning conditions occur. See Section III, Item 31.

The local representative of the Director shall be notified in advance of the time and place of any burning of logging slash.

BIOLOGICAL AND CULTURAL RESOURCES

32. a. ☒ Yes ☐ No Are any plant or animal species, including their habitat, which are listed as rare, threatened or endangered under federal or state law, or a sensitive species by the Board, associated with the THP area? If yes, identify the species and the provisions to be taken for the protection of the species.
- b. ☐ Yes ☒ No Are there any non-listed species which will be significantly impacted by the operation? If yes, identify the species and the provisions to be taken for the protection of the species.

NOTE: See THP Form Instructions or the CDF Mass Mailing, 07/02/1999, section on "CDF Guidelines for Species Surveys and Mitigations" to complete these questions.

All trees and snags with visible nesting sites of any threatened, endangered, or board sensitive species will be left standing as prescribed under 14 CCR 939.1 and 939.2(d). If during timber operations within the critical period, the timber operator discovers a snag or tree with a nesting threatened, endangered, or board sensitive species the operator shall protect the nest tree, screen trees, perch trees and replacement trees and shall cease operations within .25 miles, and notify the RPF, the Department of Fish and Game (DFG) and Cal Fire. The RPF shall consult with DFG and develop site specific mitigations and protection measures.

LISTED:

Northern Goshawk: a historic northern goshawk activity center is located in section 2, Township 32 N, Range 2 E, MDBM, within the THP Boundary. Harvest restrictions were put on the 20 acres surrounding the nest. The last known use of the activity center was 1999. Observations in 2000 and 2001 had the nest and surrounding absent of Northern Goshawk use. A LDSF wide Northern Goshawk survey conducted 2006, by LDSF staff un cooperation with the California Department of Fish and Game had no use in the territory or the surrounding area. The 2006 survey results had only one Northern Goshawk activity center located on LDSF. The one activity center is located approximately 1 .5 miles southeast of the THP, NE ¼, Section 13, T32N, R2E. The activity center was originally located in 2001 and has been active every year since. The activity center has fledged offspring in 2001, 2002, 2005-2006. There have been 4 different nest trees all within 300 yards of each other. The THP contains habitat for the Northern Goshawks and in the event that goshawks are discovered or suspected of inhabiting the THP area, efforts will be made to verify their presence. If any goshawks are observed nesting within the THP area the LTO shall cease all operations within .25 miles of the nest and contact the RPF, CAL FIRE inspector, and DFG. Specific nest protection measures will be developed in consultation with DFG. At a minimum, all goshawk nest sites will be protected according to 14 CCR 939.3.

Chinook salmon (*Oncorhynchus tshawytscha*) and Central Valley steelhead (*Oncorhynchus mykiss*): There are no known occurrences of anadromous salmonids within the THP area. No anadromous salmonids occur on LaTour nor are there historical records of observations. From dives performed in 2000 for the fish habitat assessment of the SWAG report, only rainbow trout were observed in Atkins Creek. The watercourses and fish habitat are protected by the WPLZ protections described in item 26 of this THP. See Section IV for additional discussion of anadromy.

NON-LISTED:

Pacific Fisher: The critical period for fishers is March 1 through July 31, where reproduction and caring for young occurs and when the highest potential for disturbance exists

LDSF contains habitats for the Pacific Fishers and it was detected in a 1990 furbearer presence survey. No subsequent detections have occurred. The elevation of the plan is generally considered above the range of the pacific fisher, but contains habitat for the Pacific Fisher. The plan will maintain habitat post harvest. If Pacific Fishers are observed within the THP area the LTO shall cease all operations within .25 miles of the observation site and contact the LDSF staff, CAL FIRE inspector, and DFG. The Redding DFG Timberland Planning office shall be notified of the detection and observations

Section 2

of the pacific fisher, including any along the appurtenant roads. The notification shall include the time, date, and map location.

Additionally observations, detections, and take shall be reported to the Department of Fish and Game, Wildlife Branch, Attn: Fisher Observations, 1812 Ninth St., Sacramento, CA 95811, or by email submission to fisherdata@dfg.ca.gov. Information reported to the Department pursuant to this subdivision shall include as available: a contact name; the date and location (GPS coordinate preferred) of the observation, detection, or take; and details regarding the animal(s) observed (Title 14 CCR, Section 749.5(c)).

Pine Marten: The Pine Marten has been detected in the southeastern portions of the forest (Section 24), within the assessment area, during the forest carnivore surveys conducted by LDSF staff in 2005, 2006 and 2007. The THP will maintain habitat for the Pine Marten. LDSF staff is continuing a monitoring program to evaluate the presence and continued use of known mid-sized forest carnivores.

See Section IV for additional discussion of biological review.

33. ☒ Yes ☐ No Are there any snags which must be felled for fire protection or safety reasons? If yes, describe which snags are going to be felled and why.

Snags greater than 20 feet tall and 16 inches DBH which are within 100 feet of permanent or seasonal roads or landings will be felled if they lean towards the road or landing and present a safety hazard, or if they are a potential hindrance to future access for initial attack of wildfire as per 14 CCR 939.1(a)(2). Additionally, any snag thought to contain sound volume may be harvested as allowed under 14 CCR 939.1(d).

34. ☐ Yes ☒ No Are any Late Succession Forest Stands proposed for harvest? If yes, describe the measures to be implemented by the LTO that avoid long-term significant adverse effects on fish, wildlife and listed species known to be primarily associated with late succession forests.

35. ☐ Yes ☒ No Are any other provisions for wildlife protection required by the rules? If yes, describe.

All trees and snags with visible nesting sites of any non-listed raptor will be left standing as prescribed under 14 CCR 939.1 and 939.2(d). If during timber operations, the timber operator discovers a snag or tree with a nesting of any non-listed raptor the operator shall protect the nest tree, screen trees, perch trees and replacement trees, and cease operations within 500' of the nest, notify the RPF, DFG, Cal Fire. DFG shall have ten (10) days to respond and develop a consultation based on site specific conditions. If a consultation is not developed within the ten (10) days, all non-listed raptors shall have the nest tree, screen trees, perch trees, and replacement trees protected.

Other trees within the THP area that have special value to wildlife will similarly be retained. These trees have been marked with a "W" at dbh. Additionally all snags that do not met the criteria in Item 33 above shall be retained for the benefit of wildlife

36. a. ☒ Yes ☐ No Has an archaeological survey been made of the THP area?
 b. ☒ Yes ☐ No Has a current archaeological records check been conducted for the THP area?
 c. ☐ Yes ☒ No Are there any archaeological or historical sites located in the THP area? Specific site locations and protection measures are contained in the Confidential Archaeological Addendum in Section VI of the THP, which is not available for general public review.
37. ☐ Yes ☒ No Has any inventory or growth and yield information designated "trade secret" been submitted in a separate confidential envelope in Section VI of this THP?

38. Describe any special instructions or constraints that are not listed elsewhere in Section II.

Water drafting plan

Drafting locations are Beaver Creek crossing on South Cow Creek Road, Roaring Spring crossing on Bateman Road, Atkins Creek crossing a Butcher Gulch campground, and Old Cow Creek crossing at Old Cow Creek campground.

It is estimated that water usage will be approximately 40,000 gallons per day distributed among the drafting locations during active timber operations.

Water drafting shall not occur at any of these locations when:

- (A) bypass flows are less than 2 cubic feet per second, or
- (B) pool volume at the water drafting site would be reduced by 10%, or
- (C) diversion rate exceeds 350 gallons per minute, or
- (D) diversion rate exceeds 10% of the above surface flow.

The following are requirements when drafting:

- a. Openings in perforated plate or woven wire mesh screens shall not exceed 3/32 inches (2.38 millimeters).
- b. The approach velocity (water moving through the screen) shall not exceed 0.33 feet/second.
- c. Flow in the source stream shall be at least 1 cubic feet per second (cfs).
- d. Reduction in pool volume shall not exceed 10 percent.
- e. The screen surface shall have at least 2.33 square feet of openings and the diversion rate shall not exceed 350 gallons per minute (gpm) or 10 percent of the surface flow.
- f. If an alternative screen surface area or diversion rate is desired, the following formula can be used: $\text{diversion rate (gpm)} \times 0.00676 = \text{square feet of screen surface area}$. The diversion rate can be calculated by dividing the tank capacity by the fastest filling time (i.e., 3000 gallons / 15 minutes = 200 gpm).
- g. The drafting operator shall actively observe the drafting operation. Pumping shall cease and the screen cleaned if it becomes more than 10 percent obstructed with debris.
- h. All drafting locations shall include measures (such as drip pans or absorbent fiber pads) to prevent petroleum-based products originating from vehicles from reaching surface water, groundwater, and soil. These items shall be disposed of properly.

Check all WLPZ, EEZ and ELZ flagging, and skid trail flagging prior to the commencement of any falling operations. Have the responsible RPF or supervised designee replace any flagging that is incomplete or unclear.

Review any restrictions in yarding equipment access which may cause a need for directional falling toward the lead where the logs will be yarded. Trees designated for removal within the WLPZ of a watercourse shall be directionally felled away from the watercourse and longlined, so as to keep heavy equipment out of the protection zone. In the ELZ of Class III watercourses, trees may be felled bridging the watercourse and endlined from outside the ELZ. The purpose of this measure is to allow for trees that if not directionally felled across the ELZ would fall into the ELZ or damage the residual stand.

Use only designated skid trails and tractor road crossing within WLPZs. Designated skid trails and tractor road crossings are delineated with yellow flagging.

All trees marked with a "W", a "No" or a "L" shall be retained.

Review the Winter Operations Plan and the Site Preparation Addendum

Item 38 cont.

The LTO shall carefully review the Forest Practice Rules regarding Conduct of Operations on Roads and Landings, 14 CCR 943.6.

The LTO shall carefully review the Forest Practice Rules regarding Wildlife Protection Practices contained in 14 CCR 939.2 and 939.3.

All trees and snags with visible nesting sites of eagles, hawks, owls, waterfowl, or any rare or endangered species shall be left standing.

The THP boundary has been designated in red "Sale Boundary" flagging.


The Plan submitter shall notify the Department of the commencement of timber operations at the following address:

TEHAMA-GLENN UNIT
Unit Forester
CAL FIRE
604 Antelope Boulevard
Red Bluff, CA 96080
530-528-5106

DIRECTOR OF FORESTRY AND FIRE PROTECTION

This Timber Harvesting Plan conforms to the rules and regulations of the Board of Forestry and Fire Protection and the Forest Practice Act:

By:


(Signature)

MICHAEL J. BACCA, RPF #2236
(Printed Name)

MAY 24 2011

(Date)

**Forester III, Cascade,
Sierra & Southern Regions
Forest Practice Manager**

T 32 N, R 2 E MIDMB

Class I Watercourse

Class II Watercourse

Class III Watercourse


Spring/seeps



Seasonal roads

Scale 1:16000

All State Forest roads are public



North McMullen Mountain THP Map

EHR Map


T 32 N, R 2 E MDMB

PART OF PLAN




- THP Boundary
- Class I Watercourse
- Class II Watercourse
- Class III Watercourse
- Spring seeps
- Seasonal Roads
- Moderate EHR
- Low EHR

Scale 1:16000



Silviculture Map


2174-AD



INDIAN MOUNTAIN LIT MAP


Roads & Landings Map T 32 N, R 2 E MDMB

- THP Boundary
 - Class I Watercourse
 - Class II Watercourse
 - Class III Watercourse
 - Spring/seeps
 - Seasonal Road
 - Road Abandonment
 - Referenced Landings
 - Referenced Watercourse Crossings
- WC #
All State Forest roads are public
- Scale 1:16000



T 32 N, R 2 E MD MB

Drafting Location Map



SECTION III

Support Documentation

Feasibility of Alternatives

No significant adverse effects from the proposed operations under this THP are expected to occur. However, an analysis of THP alternatives follows.

Purpose

The legislative authority for the State Forest System is contained in Public Resources Code (PRC) §4631-4658. CAL FIRE is responsible for the management of LDSF. As part of this oversight, the LDSF staff operates under a management plan, which provides general objectives and goals. The plan is required pursuant to Public Resources Code (PRC) §4645 and Article 8 of the California Board of Forestry and Fire Protection (Board) policy.

LDSF has a management plan (SCH # 2008062009), approved by the board, which provides direction and guidance for the managed uses of forest resources with an emphasis on forest demonstration, research, recreation, maintenance of wildlife habitat, and water quality protection. Timber harvesting is one of the mechanisms used to implement forest management goals and foster maintenance and enhancement of other non-timber resources. Guided by the statutes, the Board of Forestry and Fire Protection establishes policy, which governs LDSF and other state forests. Board policy states that the primary purpose of the state forest program is to conduct innovative demonstrations, experiments, and education in forest management.

Objectives

- Demonstrate sound forest management.
- Reduce fuel loading thus reducing the risks of wildfires
- Avoid the waste of timber resources
- Enhance growth and vigor of timber resources
- Improvement of the forest road system
- Improve wildlife habitat, and watershed values promoted by the resulting healthy stands

The project as proposed meets is in conformance with the 2008 LDSF Management Plan (SCH # 2008062009), LDSF's Option A for Long Term Sustained Yield (LTSY), and the Board's policy. The project also meets the following objectives:

Achieve a balance between growth and harvest over time consistent with the harvesting methods within the rules of the Board.

Harvesting the trees that are infected with *Cytospora* sp. and white pine blister rust. Thus improving forest health and reducing tree mortality and fuel loading.

Maintain functional wildlife habitat in sufficient condition for continued use by the existing wildlife community within the planning watershed.

Maintain growing stock, genetic diversity, and soil productivity.

Alternatives Considered

NO PROJECT

Site would remain as is.

No economic benefits would be realized.

Stand vigor would decrease do to the *Cytospora* sp. and the white pine blister rust.

Mortality not harvested would be wasted.

Increased risk to stand replacing wildfires resulting from the stand conditions and increasing fuel loads.

Forest management and timber harvest demonstrations will not be carried out.

PROJECT TIMING

The proposed project will be completed within the next 5 years.

Delaying the project to another decade was considered.

A delay of the proposed timber harvest would result in the waste of timber resources through stand mortality and allow for the continual risk of wildfire.

A delay in harvest and income timing would substantially reduce the present net worth of the proposed project.

LDSF is managed 15 to 18 year cutting cycle. Delaying the project will increase the acres to be treated in future years to maintain the stand treatment schedule.

ALTERNATIVE SITE

This alternative is not necessary, as any significant negative effect from the proposed operations has been mitigated in the THP.

ALTERNATIVE SILVICULTURE

Using more even-aged silviculture prescriptions is not suitable for this THP. LDSF has an Option A plan that defines the LTSY of the forest. The LTSY was determined by modeling timber growth for LDSF using specific silvicultural prescriptions. The LTSY was calculated primarily using un-evened aged silviculture. Even though even-aged silviculture is available to use, the minimal acres modeled are better suited for different locations on the forest, within stands of high disease and mortality, or marginal stocking.

Upon review of the alternatives considered, the proposed project is the landowner's best alternative to meet the above stated objectives

General Project Description

Location: The THP is located in Shasta County on LDSF in sections 1, 2, 3, 11, and 12, T 32 N, R 2 E. The elevation of the THP ranges from 5,500 feet to 6,500 feet. The THP is approximately 13 air miles east of the community of Whitmore, California, 22 miles south of Burney and Seventeen miles northeast of Lassen Volcanic National Park.

Soils and Topography

The soil series within the harvest boundary are Windy - McCarthy stony sandy loam and Cohasset stoney loam. Cohasset stoney loams comprise about 80% of the plan area. Windy - McCarthy soils are made up the remaining portions of the THP. Both these soils are volcanic in origin and are stony to very stoney throughout the soil profile. They are well-drained soils with moderate to rapid permeability. Both soil series have soil depths up to 60 inches and are considered moderately productive timberland soils.

Elevation in the harvest area ranges from 5,500 to 6,500 feet. The topography is varies from flat to moderately steep slopes. The average slope within the harvest units is approximately 20% but ranges from 0 to 55%.

The following are soil types that are found within the THP boundary:

<u>Soil Type</u>	<u>Slopes</u>	<u>Depth</u>	<u>Permeability</u>
Windy-McCarthy stoney sandy loam (WeD)	0-30%	40-60 inches	Mod-Rapid
Windy-McCarthy stoney sandy loam (WfE)	30-50%	40-60 inches	Mod-Rapid
Cohasset stoney loam (CmD)	0-30%	48-60 inches	Moderate

Vegetation and Stand Conditions

The predominant vegetation types in the harvest area are True fir and Sierra mixed conifer. Previous management activites have resulted in the THP area having both even-aged and uneven-aged stands. Species composition of the true fir stands is predominately White fir and Red fir with a minor component of Lodgepole pine, Jeffrey pine, Sugar pine, and Western White pine. The stocking density in the majority of the true fir stands has resulted in little vegetation or regeneration in the understory, but where stocking is less dense the understory is dominated by chinquapin.

Sierra mixed conifer stands are uneven-aged with all size classes represented. Red fir and White fir comprise approximately 60 percent of the stand, Jeffery pine ranges from 10 to 25 percent of the stand and the Sugar pine and western white pine both comprise between 5 to 15 percent of the stand. Lodgepole pine and Incense cedar are also found within the mixed conifer stands. Regeneration exists naturally in the understory especially in areas where past harvest activities have created openings, and artificial regeneration exists in old group selection openings, areas that were Red Fir rehabilitation units and in converted brush fields. There is one 15 acre western white pine plantation and 2 white fir plantations that are part of a plantation density study.

The disease problems observed in the harvest area largely consist of dwarf mistletoe and cytospora or fir canker. Pockets of dead trees exist in the harvest area from fir canker infection. Infection of White Pine Blister Rust is affecting intolerant sugar pine and the western white pine and is throughout the THP. Endemic insect populations of Mountain Pine Beetle and Ips in the pine species and Scolytis in the fir were also observed.

Despite the disease problems, the selection area and fuel break area are well stocked with an average basal area of approximately 180 square feet and ranges for 100 to 280 square feet of basal area. The target average basal area post harvest is 140 square feet in the selection area, and 50 square feet in the Fuel break.

Watershed and Stream Conditions

LDSF is the headwaters source of two major streams, Old Cow Creek and South Cow Creek. A Tributary to the North Fork Battle Creek and South fork Bear Creek drain small portions of the south side of LDSF.

The THP is primarily located within the Huckleberry Watershed (Cal Water version 2.2 #5507.320102) and the Atkins Creek Watershed (Cal Water version 2.2 #5507.320101). There is also approximately 48 acres of the THP within the Beal watershed (Cal Water version 2.2 #5507.320103). The primary watercourses within these watersheds are Old Cow Creek, Atkins Creek and South Cow Creek respectively. Peavine Gulch and White Fawn Gulch are the two drainages within the THP that are tributary to Old Cow Creek, and Lee March Gulch is the only drainage on the THP which is tributary to Atkins creek. The THP has no watercourses located within the Beal Watershed. Peavine Gulch and White Fawn Gulch originate within and transition to Class II watercourses within the THP. Lee March Gulch originates from springs located on and adjacent to the THP. Until this year Lee March Gulch was considered and protected as a Class II watercourse. LDSF staff with cooperation from California Department of Fish and Game, electro-shocked Lee March Gulch on July 13th 2010. Fish were located approximately 2500 feet downstream from the THP and no fish were found on within the THP. Lee March Gulch annually goes dry just prior to leaving the THP area and is considered a seasonal Class I watercourse. The Class I portion of the watercourse within the THP does not have the habitat to hold fish during the summer months.

South Cow Creek and Old Cow Creek contains generally complex habitat with deep pools, riffles, and boulders forming step pools. The creeks appears to have good channel conditions in the lower portion of the planning watersheds and impacts from timber operations were not significant to those portions of South Cow Creek and Old Cow Creek. The upper reaches of Atkins Creek are primarily within meadow systems and contain a mix of habitat but primarily flat water and riffles reaches. Atkins creek is considered to be in fair and stable condition, but stability is a risk. Risks to Atkins Creek are associated with on going cattle grazing of Cutter Meadows and the surrounding area. Impacts related to timber management were not considered significant. Further evaluation of the watercourses occurred in the summer of 2000 from the *LaTour Demonstration State Forest Watershed Monitoring Project*, Stream Channel and Fish Habitat Assessment prepared by the Sacramento Watersheds Action Group (SWAG) under contract with the Department of Forestry and Fire Protection. In this report South Cow Creek, and Old Cow Creek and Atkins Creek were assessed within LDSF boundaries.

The SWAG report evaluated the Class I reaches of all three creeks and concluded nearly all of the watercourses are stable with some instability observed at the upper reaches in the meadows and the first 300 feet of Old Cow creek and the length of Atkins Creek where they exits LDSF. South Cow Creek and Old Cow Creek banks were stabilized primarily by large cobbles, boulders, and riparian vegetation. Atkins Creek's banks are predominately undercut and stabilized by shallow rooted vegetation.

Plan addendum # 14

Group Selection: pursuant to 14 CCR 933.2(a)(2)(B), group selection will occur on 763 acres of the plan area. The group selection method is designed to remove trees individually or in small groups sized from .25 to 2.5 acres. Three silvicultural considerations were observed within the existing stand (1) high stand density in the true fir stands (2) lack of regeneration, and (3) disease and mistletoe infection. The average basal area per acre in the group selection ranges from 100 to 325 square feet per acre. The stand was marked with the intention of opening it for release of vigorous conifers. Additionally, to assure the establishment of regeneration, "group clearings" (.25 - 2.5 acres) were marked. The "groups" are to be oriented such that the clearings are, where possible, constructed around or near large healthy "seed trees". No group clearings are within Watercourse and Lake Protection Zones (WLPZ's) or Equipment Limitation Zones (ELZ's).

Groups will not exceed 2.5 acres and will not exceed 20% of the area to be harvested under Group Selection.

The site classifications in the area to be harvested are Dunning Sites II and III. The post harvest stocking levels for group selection are, at least 80% of the stocked plots shall have a minimum of 75 square feet of basal area, and not more than 20% of the stocked plots will be used to meet the stocking standards utilizing the 300 point count. Group clearings are separated by logical logging areas.

Rehabilitation: Pursuant to 14 CCR 933.4 (b) Rehabilitation of Understocked Area Prescription will occur on 27 acres, for the purposes of restoring and enhancing the productivity of commercial timberlands which do not meet currently meet the stocking standards defined in 14 CCR 932.7.

The site classification within the rehabilitation unit is Dunning Site class III. The existing stand is declining in health and vigor. The overstory of Red fir and Western White Pine has a range in basal of 10 square feet to 100 square feet. Disease problems such as dwarf mistletoe, *cytospora spp*, and blister rust are infecting the vast majority of the overstory. The mistletoe and *cytospora spp*. have been transferred from the overstory to the understory which consists of pockets of advanced red fir regeneration. Portions of the unit do meet the basal area or point count totals to be considered stocked, but because of the disease problems the vast majority of the trees in both the overstory and understory do not meet the definition of a countable trees (defined in 14 CCR 895.1). Between the pockets of advanced regeneration the unit is dominated (greater than 80% cover) with manzanita and chinquapin brush.

The Rehabilitation Unit shall have site preparation, as per the Site Preparation Addendum, and will be artificially regenerated. The unit shall be planted with Group A species within three years following completion of operations. An average of 300 seedlings per acre shall be planted. The seedlings shall be from the appropriate seed zone and elevation band.

Fuel Break: CAL FIRE has a planned fuel break along the watershed boundaries within LDSF. The location of the planned fuel break is along the McMullen Road east to Table Mountain and along the Rim Road. A portion of this THP along the McMullen Road is within the planned fuel break and 10 acres will be treated with the fuel break prescription. The fuel break prescription is a width of 100 feet and approximately 4400 feet long. The fuel break will run adjacent to the McMullen Road, from the western edge of the THP to eastern edge of the brush field on the west side of McMullen Mountain.

As described in 14 CCR 933 (d), because fuel breaks are designated as defensible space areas, the wood production potential of these lands is compatible with the lowest site classifications and they shall be considered site IV timberland for stocking purposes. Upon completion of the THP the fuel break shall have a minimum stocking of 50 square feet of basal area as described in 14 CCR 932.7(b)(2). Sub-merchantable material shall be felled and chipped or piled to be burned when safe burning conditions exist. The Fuel Break is within the fire protection zone all logging slash shall be treated by lopping, piling and burning, chipping, or removal from the zone. This treatment shall be completed prior to April 1 following creation or within 30 days following climatic access.

Vegetation control: control of competing vegetation may be required to insure the survival of the regeneration within the Rehabilitation Unit and the groups within the Group Selection Silviculture. The primary competing vegetation with the regeneration is chinquapin, manzanita, and grasses. The competing vegetation may be controlled by manual, mechanical or chemical treatments.

Mechanical treatments: All equipment utilized for the control of competing vegetation shall adhere to the protection measures described within this THP including ELZs, Site Preparation Addendum, and the Winter Operations Plan.

Chemical treatments: Herbicide control of vegetation shall adhere to the Site Prep Addendum as to where and time of year application should occur. Treatments may be applied pre and/or post harvest. If preharvest application does not occur, then post harvest application may occur twice within five years following harvest. All herbicides used on this THP shall be registered for forestry applications and will likely be applied by a directed backpack spray by one of the following methods:

- Foliar backpack applications can be selective or non-selective, depending on the type of herbicide and the application method. The herbicide is sprayed by hand as a broadcast application across all vegetation or directly sprayed on target species. Even non-selective herbicides can be used for selective control through the use of low volume directed backpack applications or by timing the application so that the desired annual species have already produced seed.
- Basal stem treatments are another selective contact treatment. Basal stem treatments are usually made using backpack sprayers. Herbicide is mixed with an oil carrier to allow adequate bark penetration and is applied to the lower two feet of a woody plant. Basal stem applications have a longer application season and can provide good control through November. Dormant applications have less visual impact than other application methods since the target species never leafs out in the spring and there is no brownout.
- Cut-stump treatments are used to prevent woody species from resprouting. After trees and brush are cut with a chain saw or loppers, the stump is treated with herbicide.

The use, type and the timing of the herbicide shall be determined and recommended by a Licensed Pest Control Advisor (PCA) and the application shall adhere to the PCA's recommendation, the herbicide label instructions, and the Mitigated Negative Declaration, State Clearing House (SCH) # 2008062009 for LDSF Management Plan 2008.

The registration of herbicides in California is a CEQA equivalent process, and when applied according to the label instructions, PCA's recommendation, and with a licensed applicator, no significant adverse impacts to wildlife and water resources are likely to occur. Herbicides use is regulated by the Department of Pesticide Regulation (DPR) and enforced by the County Agricultural Commissioner.

Plan addendum #17 - Erosion Hazard Rating (EHR)

The Soil Survey of Shasta County California and field observations were used to determine the erosion hazard rating (EHR) for this THP area. The EHR areas were delineated according to soil type and ground observations with regard to slope, ground cover, and physical characteristics. The EHRs for the THP area are low and moderate. The EHR types are delineated on the EHR Map.

Plan addendum #26 - 936.9 (v) Site Specific Watercourse Protection Zone Widths

Site specific plans may be submitted when, in the judgment of the RPF, such measures or provisions offer a more effective or more feasible way of achieving the goals and objectives set forth in 14 CCR § 936.9, subsections (a) and (c), and would result in effects to the beneficial functions of the riparian zone equal to ... those expected to result from the application of the operational provisions required under 14 CCR § 936.9.

Pursuant to 936.9 (v)(2) ... "In the event of measures limited in applicability to specific sites, the submitter may instead of an evaluation, obtain written concurrence from DFG prior to plan submittal..." The WLPZ widths for

PART OF PLAN

Section 3

North McMullen Mountain THP

the protection of the watercourses within the Lee March Gulch drainage were developed in cooperation with DFG during a site preconsultation, conducted on July 13, 2010.

Lee March Gulch originates from springs on LDSF and flows approximately 1 mile north into Cutter Meadows where it joins Butcher Gulch and forms Atkins Creek. During the spring when snow is receding, Lee March Gulch shows evidence of modest flows with an average channel width of 4 feet and an average high water depth of 15 inches. After the snow is gone the flow becomes intermittent and surface flow does not even reach Cutter Meadows by mid July. During the July 13th preconsultation with DFG, the surface flow did not reach Cutter Meadows. By mid August the surface water is exclusively spring fed and does not leave the THP area.

Lee March Gulch is the only drainage within the THP that is within an ASP watershed (Atkins Creek) and is tributary to Atkins Creek. Several timber harvests have occurred within the Lee March Gulch drainage since the early 1960s. The historical harvests were for the development of LDSF road system and the timber was managed with un-evenaged prescriptions. During these previous harvests and on harvests outside of LDSF, Lee March Gulch was considered and protected as a non-fish bearing watercourse. The resulting stream side vegetation from these harvests is a multi-aged mixed conifer timberstand. The average canopy coverage exceeds 75%. Immediately around the springs, small meadows exist with dense patches of alder. The previous timber harvests within the watercourse protection zones were limited, as evidenced by very few stumps.

During the preconsultation with DFG, LDSF staff and DFG staff electro-shocked portions of Lee March Gulch. One 4 inch trout was located along the boundary of LDSF, where Lee March Gulch enters Cutter Meadows. There are no obvious fish barriers upstream from where the trout observed, so Lee March Gulch is now identified as a Class I watercourse from approximately 500 feet within the THP boundary north to the intersection with Atkins Creek.

The WLPZ widths and the protection measures for the watercourses within the Lee March Gulch drainage were developed in cooperation with DFG during a site preconsultation, conducted on July 13, 2010. During the site visit DFG and LDSF staff reviewed the in stream conditions of Lee March Gulch, available fish habitat, surrounding vegetation, and the previous watercourse protections measures for Lee march gulch. The WLPZ protections described within Section II, Item 26, ASP watersheds of the THP, are based upon DFG and LDSF observations, the proposed silviculture, and the previous management practices. The proposed protection measures shall provide effects to the beneficial functions of the riparian zone equal to those expected to result from the application of the operational provisions required under 14 CCR § 936.9. As Per 14 CCR 936.9(v)(2) DFG is in concurrence with the proposed protection measure for those watercourses within ASP watersheds. The DFG concurrence letter is located in Section 5, page 57.1.

As per 14 CCR 936.9(v)(4),

- (A) The WLPZ protection measures within the ASP watersheds were developed in consultation with DFG and are described in Section II, Item 26 of the THP. These protection measures were developed after DFG and LDSF staff electro-shocked a previously identified Class II watercourse, and assessed the instream and adjacent habitats.
- (B) As stated in the DFG concurrence letter "...the RPF's proposal for a site specific alternative provides equal protection to salmonids and their habitat as the provisions of 936.9.", thus no significant adverse impacts should occur to listed salmonids or the beneficial functions of the riparian zone.
- (C) As stated in (B) above and DFG consultation , no significant adverse impacts should occur to listed salmonids or the beneficial functions of the riparian zone.
- (D) The WLPZ protections are described within Section II, Item 26 of the THP and provide clear and enforceable for the timber operator.
- (E) As per 14 CCR 1035(d)(1), the plan submitter shall "retain an RPF who is available to provide

PART OF PLAN

Section 3

North McMullen Mountain THP

professional advice to the LTO and timberland owner upon request throughout the active timber operations..."

- (F) The proposed protection measures for the Class I watercourses within ASP watersheds differ from the prescriptive rules described in 14 CCR 936.9 (f)(4), as the overall WLPZ width has been reduced from 100 feet to 75 feet. Additionally no harvest is proposed within the Class I WLPZ and 14 CCR 936.9(f) (4) allows for harvest outside the 30 feet "core zone".

The proposed protections measures for Class II watercourses within ASP watersheds differ from the prescriptive rules described in 14 CCR 936.9 (g), as the existing Class II watercourses within Lee March Gulch are by definition Class II Large watercourses and these watercourses are provided Class II standard protections.

Plan addendum #27

Standard rule 14 CCR 936.3 (c) states that the timber operator shall not construct or reconstruct roads, construct or use tractor roads or landings in Class I, II, III, IV watercourses, in the WLPZ, marshes, wet meadows, and other wet areas unless when explained and justified in the THP by the RPF, and approved by the Director, except as follows:

- (1) At prepared tractor road crossings as described in 934.8 (b).
- (2) Crossings of Class III watercourses which are dry at the time of operations
- (3) At existing road crossings
- (4) At new tractor and road crossings approved as part of the Fish and Game Code process.

14 CCR 936.4(d) states, "Heavy equipment shall not be used in timber falling, yarding, or site preparation within the WLPZ unless such use is explained and justified in the THP and approved by the Director".

The proposed in-lieu practices, as described in Section II, item 27, of using existing skid trails, landings and roads within the WLPZ will provide equivalent, and possibly better, protection to the beneficial uses of water than would the standard rules. The proposed practice eliminates the need to relocate landings, skid trails, and road segments outside and adjacent to the WLPZ. Relocation and new construction is not feasible and would create an overall greater soil disturbance within the watershed. The existing skid trails, landings and roads are stable, and are not currently, and should not in the future; negatively impact the beneficial uses of water downstream. Measures to mitigate possible adverse effects from operations proposed under this plan are specified in Section II, Item 27.

Plan addendum #28 (b) – Notification requirements

An exemption to the Notification requirements for information on domestic water supplies is requested for the newspaper notice. Sierra Pacific Industries and lands managed W.M. Beaty & Associate are the only landowners within 1000 feet downstream that receive surface drainage for areas proposed for harvest. Both SPI and W.M. Beaty & Associates received letters requesting any information regarding domestic water uses within 1000 feet from the proposed project boundary. Verbal correspondence with W.M. Beaty & Associates, Staff Forester, Ross Brazil the absence of domestic water supplies downstream of the THP area was conveyed. Verbal correspondence with Sierra Pacific Industries, Forester, Jan Caster the absence of domestic water supplies downstream of the THP area was conveyed.

Plan addendum #31 - Piling and burning for hazard reduction

The standard rules 14 CCR 937.2(a) and 937.5(b) state slash to be treated by piling and burning shall be treated no later than April 1 of the year following creation, or within 30 days following climatic access, or as justified in the plan. The piles and concentrations shall be burned at a safe time during the first wet fall or winter weather or other safe period following piling and according to laws and regulations.

An alternative to the standard rule is proposed to allow treatment of landing slash accumulations that result from the use of chipping and/or de-limbing equipment created after September 1 of each year. This material may be burned the following fall, prior to December 15, when safe burning exist. This alternative practice shall be applied over the entire THP area.

This practice differs from the standard practice in that piles will remain in place over the spring and summer and will be treated in the fall, rather than in the winter or early spring following their creation.

This alternative will provide equal or greater hazard reduction. Slash will be concentrated in the landings so that it is no longer a fuel component of the forested stands. There will be protective space around the piles as specified in Section II, Item 31. Also, there have been several incidents of burnt piles rekindling and even escaping following spring burning in this general region. Allowing fall burning of these piles will assure better consumption of the material and a cooling off period through the winter months.

All other provisions of 14 CCR 937.5 will be complied with. Piles will be constructed so that they are sufficiently free of soil for effective burning. These piles will be burned at a safe time during wet fall or winter weather according to other applicable laws and regulations. Piles that fail to burn sufficiently to remove the fire hazard shall be further treated to eliminate the hazard. All necessary precautions shall be taken to confine such burning to the piles.

Although some scorching of surrounding trees may occur, the extent of this damage will not result in conditions that do not meet the silvicultural and stocking requirements of this THP. No excessive buildup of bark beetle populations is expected to occur as a result of this proposed alternative.

Plan addendum #33 - Snag Falling / Hazard Reduction

Felling of snags for hazard reduction within 100 feet of all public roads, seasonal roads, and landings will not result in the loss of habitat elements associated with late seral stage timber stands. There are standing dead trees in later stages of decay throughout the THP. All snags with visible nesting sites of eagles, hawks, owls, waterfowl, or any rare or endangered species will be left standing as prescribed under 14 CCR 939.1 and 939.2(d). Special attention will be focused on retaining snags within WLPZs that may be recruited as large woody debris (LWD).

Plan addendum #34 – Late Successional Forest Stands

LDSF has had multiple entries (4-5) since it became a State Forest in the late 1940s. The THP has been harvested with un-even aged silviculture 4 times. Though the THP has scattered mature trees, there is no Late Seral Forests or characteristic on the THP area.

DEMONSTRATIONS AND EXPERIMENTS

According to statute and Board policy, the purpose of the state forest program is to investigate and demonstrate the economic feasibility of artificial reforestation and the productive and economic possibilities of forest management practices which are designed to promote continuous forest production, with due regard to conservation of soil, watershed, scenic, wildlife, and recreational values. PRC 4645 authorizes the Department of Forestry and Fire Protection to manage State Forests and states, "The department, in accordance with plans approved by the board, may engage in the management, protection, and reforestation of state forests." The primary current use of state forests is to demonstrate economical silvicultural practices and timber harvesting procedures that protect environmental values.

State forests have been established to furnish land for needed investigation, demonstrations, and education in such things as the economic feasibility of artificial reforestation, good forest practices, maintenance of forest land in a productive condition, study of effects of improved cutting methods, proper management and harvesting methods, and economical forest management.

The following demonstrations are associated with this timber harvesting plan:

1. Continuous Forest Production and economical silvicultural practices.

Timber harvesting and forest production has occurred on LDSF since 1952. Approximately 150 million board feet of timber has been harvested from the Forest. Since the Forest's establishment, the estimated standing volume of timber has increased from 102 million board feet to 197 million board feet (based on TAI inventory conducted from 1994-2001). This harvest will continue to demonstrate forest production to achieve maximum sustained production of high quality forest products while giving consideration to other values relating to recreation, watershed, wildlife, range and forage, fisheries, and aesthetic enjoyment.

2. Evaluation of yarding systems in selection silvicultural systems

An on going demonstration project is being conducted by LDSF Staff. Three yarding systems, (tractor, cable and helicopter) are being evaluated in harvesting forest stands utilizing selection silviculture. Costs, feasibility, and residual stand damage are evaluated to determine applicability for the small forest landowner.

3. Implementation and Demonstration of LDSF Road Management Plan

SECTION IV

CUMMULATIVE IMPACTS

STATE OF CALIFORNIA
BOARD OF FORESTRY
CUMULATIVE IMPACTS ASSESSMENT

- (1) Do the assessment area(s) of resources that may be affected by the proposed project contain any past, present, or reasonably foreseeable probable future projects? ☒ Yes ☐ No
If the answer is yes, identify the project(s) and the effected resource subject(s).
- (2) Are there any continuing, significant adverse impacts from past land use activities that may add to the impacts of the proposed project? ☐ Yes ☒ No
If the answer is yes, identify the activities, describing their location, impacts, and the affected resource subject(s).
- (3) Will the proposed project, as presented, in combination with the past, present, or reasonably foreseeable probable future projects identified in items (1) and (2) above, have a reasonable potential to cause or add to significant cumulative impacts in any of the following resource subjects?

Impact Assessment	Yes After Mitigation (a)	No After Mitigation (b)	No Reasonably Potential Significant Effects (c)
1. Watershed			X
2. Soil Productivity			X
3. Biological			X
4. Recreation			X
5. Visual			X
6. Traffic			X
7. Other			
<p>a. Yes, means that potential significant adverse cumulative impact are left after application of the forest practice rules and mitigations or alternatives proposed by the plan submitter.</p> <p>b. No after mitigation means that any potential for the proposed timber operation to cause or add to significant adverse cumulative impacts by itself or in combination with other projects has been reduced to insignificance or avoided by mitigation measures or alternatives proposed in the THP and application of the forest practice rules.</p> <p>c. No reasonably potential significant cumulative effects means that the operations proposed under the THP do not have a reasonable potential to join with the impacts of any other project to cause, add to, or constitute significant adverse cumulative impacts.</p>			

- (4) If column (a) is checked in (3) above, describe why the expected impacts cannot be feasibly mitigated or avoided and what mitigation measures or alternatives were considered to reach this determination. If column (b) is checked in (3) above describe what mitigation measures have been selected which will substantially reduce or avoid reasonably potential cumulative impacts except for those mitigation measures or alternatives mandated by the application of the rules of the Board of Forestry.
- (5) Provide a brief description of the assessment area used for each resource subject.
- (6) List and briefly describe the individuals, organizations, and records consulted in the assessment of cumulative impacts for each resource subject. Records of the information used in the assessment shall be provided to the Director upon request.

Past and Future Activities

The assessment area for past and future activities consists of the Huckleberry (5507.320102), Atkins Creek (5507.310101) and Beal (5507.310103) Cal Water Planning Watersheds, version 2.2

For assessment purposes, the following is a table of past projects that have been approved within the Huckleberry Atkins Creek and Beal planning watersheds. The data was obtained from the CAL FIRE Cumulative Effects Database. Due to the limitations of the CDF database the acres listed below tend to be over estimates. If part of a THP is within the assessment area, then all of the acres of the THP are included in the database, unless noted otherwise.

Timber Harvest Plans in the Assessment Area

THP Number	yarding method	status	Acres by Prescription										Total
			NT	FB	AP	R/W	CC	SWR	SEL	SS	CT	GSEL	
2-02-033	tractor/skidder	completed					31						31
2-02-225	tractor/skidder	completed			70	3	44					557	674
2-03-172	tractor/skidder	completed							458				458
2-04-177	tractor/skidder	active		40					1133		11		1184
2-05-111	tractor/skidder	active				2	213		10				225
2-05-149	tractor/skidder	active	39	14					95	200		1914	2262
2-06-129	tractor/skidder	active			344	2							346
2-06-138	tractor/skidder	active			167		239						406
2-01-037	tractor/skidder	completed				1			300	50	1025		1376
2-03-188	tractor/skidder	completed		57			485	2			237		781
2-03-050	tractor/skidder	completed							1185				1185
2-02-214	tractor/skidder	completed	13	112			494	54	3		410		1086
2-02-187	cable, tractor/skidder	completed						344				1288	1632
2-01-161	tractor/skidder	completed									50	611	661
2-08-071	tractor/skidder	active				2		7				341	350
2-09-064	tractor/skidder	review				6	266		12				284
2-09-063	tractor/skidder	review							1768	64			1832
2-09-059	tractor/skidder	review	15			1			320	101			437
2-03-143	tractor/skidder	completed	24				11	95	1898				2020
2-09-084	tractor/skidder	active					58*		143				200
2-08-078	tractor/skidder	active						24	1676				1700
2-09-110	tractor/skidder	active				3	209	37	17				266
**SCH # 2008062009			9,033 acre LDSF management Plan										
***Total Acreage			81	223	581	20	2050	563	9018	415	1733	4711	19,376
***Percent of Assessment Area			<1%	<1%	2%	<1%	6%	2%	27%	1%	5%	14%	59%

CC	Clear Cut	SEL	Selection
SWS	Shelterwood Seed	SS	Sanitation-Salvage
SWP	Shelterwood Prep	CT	Commercial Thinning
SWR	Shelterwood Removal	Trans	Transition Method
STS	Seed Tree Seed	Rehab	Rehabilitation of Understocked Area
STR	Seed Tree Removal	GSEL	Group Selection
R/W	Right of Way	NT	Non Timberland

* 2-09-084 has 3 acres of meadow restoration and 55 acres of Variable Retention. These 58 acres are shown within the table as CC, because the amount of vegetation removed and ground disturbance is similar to a Clear Cut.

** This is a CEQA compliant Mitigated Negative Declaration of LaTour Demonstration State Forest's Management Plan 2008.

*** Acres and percentages shown within these tables may be increased are over actual acres harvested within the assessment area. Due to the limitations of CAL FIREs' database, if portion of a THP is within the assessment area, then all the acres of the THP are included in the data base.

Based on the CAL FIRE Database Check 16,927 acres (69%) of the assessment area has been harvested or planned for harvest. Of the total area harvested, 3184 acres (18% of the assessment area) were treated with evenaged silviculture methods. The majority of the assessment area that was harvested was treated using unevenaged and intermediate silvicultural methods (13,743 acres). No long-term site impacts have resulted from the harvesting with in the assessment area.

Present projects

For the purpose of assessing present projects the entire THP area is being treated with selection and Variable Retention silviculture methods and there is three acres of meadow restoration. There are no other known California Environmental Quality Act projects currently proposed within the assessment area.

Future Projects

Future projects include the ongoing production and removal of high quality forest products through scheduled periodic harvesting on the commercial timberlands. LDSF will continue to manage the State's timberlands on periodic entries (18 year re-entry cycle) using predominantly un-evenaged silviculture. Within the next 5 years LDSF has 1 additional THP planned within the Beal watershed and one within the Huckleberry watershed. No increased impacts are expected to result from these ongoing forest management activities.

A. ASSESMENT AREAS

Watershed Resources

The watershed assessment area consists of the Huckleberry, Atkins Creek and Beal watersheds Cal Water Planning Watersheds version 2.2 and is shown on the attached Watershed Assessment Map. The THP boundary lies within the headwaters of these watersheds. The watersheds are third order watersheds and are tributary to Cow Creek. Cow Creek is tributary to the Sacramento River. This assessment area was chosen because the key cumulative impact issues, related to timber harvest, typically express themselves at the scale of planning watersheds or a subset of the planning watershed area.

Beal watershed (planning watershed 5507.310103) is the headwaters of South Cow Creek and drains a basin of 11,598 acres, of which 5,928 acres are contained within the boundaries of LDSF. Elevation ranges from 6,740 at LaTour Butte to 2,920 feet at the junction with Atkins Creek. Major tributaries include Beaver, Bullhock and Beal Creeks. South Cow is a third order stream before the junction with Atkins Creek (and fourth order below Atkins). There are approximately 9 miles of Class I watercourses along the main channel of South Cow Creek. Ownership in the lower elevations of the watershed is predominately private commercial timberlands

Huckleberry (planning watershed 5507.320102) includes the headwaters portion of Old Cow Creek and drains a basin of 12,836 acres, of which 1,452 acres are contained within the boundaries of LDSF. Elevation ranges from 7,064 (Huckleberry Mountain) to 4,520 feet about 1/4 mile below the junction with Hunt Creek. Old Cow Creek originates from Huckleberry Lake in the Lassen National Forest. Additional major tributaries include Huckleberry Creek, Peavine Gulch, and White Fawn Gulch. Old Cow Creek below Hunt Creek is a fourth order stream. There are about 7.5 miles of Class I watercourse along the main channel of Old Cow Creek.

Atkins Creek (planning watershed 5507.310101) is a major tributary of the headwaters portion of South Cow Creek. The drainage basin is 8,646 acres in size, of which 1,211 acres are contained within the boundaries of LDSF. Elevation ranges from 6,500 feet at McMullen Mountain to 2,920 feet where it enters South Cow Creek. Major tributaries include Lee March, Butcher, and Sunset Gulches. Atkins Creek is a third order stream and there are approximately 7 miles of Class I watercourse along the main channel.

The beneficial uses of water within the Watershed Assessment Area include; domestic water use, crop irrigation and stock use, power generation, contact and noncontact recreation, cold fresh water habitat and wildlife habitat. The beneficial uses was created from RPF's local knowledge and the Sacramento River Basin Plan, Chapter 2, Table II (Cow Creek).

Soil Productivity

The assessment area will be the boundary of the THP. This will be adequate to cover impacts from timber operations.

Biological Resources

The biological assessment area (BAA) coincides with the watershed assessment area. The BAA has high biodiversity based on the elevation range, and multiple types of vegetation and habitat. Rational for selection of the BAA is that the watershed assessment area serves as a distinct boundary for collecting and observing wildlife data. This area provides a large enough area adjacent to the THP to assess cumulative impacts to wildlife.

Recreational Resources

The assessment area for recreational resources will be the harvest area plus 300 feet from the plan boundary. This area is appropriate due to the limited recreational use the area receives.

FEB 08 2018

Visual Resources

The visual assessment area is the plan area that is readily visible to significant numbers of people within 3 miles of the THP. This was selected due to the distance of the harvest area from communities and well traveled roads.

Vehicular Traffic Impacts

The assessment area includes the two main haul routes from the THP area.

- a) Cutter Road to the Tamarack Rd (Shasta County Rd.)
- b) Bateman Road from the harvest boundary to the end of the county road portion on the Bateman Road. The county road ends at the Atkins Creek watercourse crossing.

The extent of the assessment area was determined based on these routes are the most logical routes off the harvest area and the assessment area terminates at the first county road.

B. Watershed Impact Assessment

LDSF is located at the head waters of 5 California Water Planning Watersheds and contains the headwaters of South Cow Creek (principle drainage within the Beal watershed) and part of the headwaters of Old Cow Creek and Atkins Creek (principle drainages within the Huckleberry and Atkins Creek watersheds). Precipitation on LDSF and the assessment area averages 46 inches a year with most of it as snow (74%) between November and March. Summer rainfall in the form of thunderstorms is unpredictable with the more severe storms producing localized, but intense runoff.

The harvest area lies within the Huckleberry, Atkins Creek and Beal watersheds. There are no watercourses on the THP within the Beal watershed. Lee March Gulch is one of two tributaries to Atkins Creek and the headwaters of Lee March Gulch is located within the THP boundary. The two main drainages within the THP are Peavine Gulch and White Fawn Gulch, both of which are tributary to Old Cow Creek.

Lee March Gulch, Peavine Gulch and White Fawn Gulch are all second order watercourses within the THP area. The main watercourses within the assessment area (Old Cow Creek, Atkins Creek, and South Cow Creek) are all third order watercourses until the exit the assessment area.

A detailed evaluation of the South Cow Creek and Old Cow Creek and Atkins Creek occurred in the summer of 2000 for the LaTour Demonstration State Forest Watershed Monitoring Project, Stream Channel and Fish Habitat Assessment prepared by the Sacramento Watersheds Action Group (SWAG), under contract with the Department of Forestry and Fire Protection. In this report South Cow Creek, Atkins Creek, and Old Cow Creek were assessed within the LDSF boundaries. The SWAG report assessed 16,579 feet of South Cow Creek, 2,842 feet of Atkins Creek and 7,380 feet of Old Cow Creek within the LDSF Boundaries. The creeks appears to have good channel conditions in the lower portion of the planning watershed and impacts from timber operations were not significant to those portions of the planning watersheds.

The SWAG report concluded South Cow Creek is in good condition and contains generally complex habitat with deep pools, riffles, and boulders forming step pools. SWAG reports 91% of S. Cow Creek was stable with some instability noted at the upper reaches within South Cow Creek Meadow. The stream banks were stabilized primarily by large cobbles, boulders, and riparian vegetation. By length habitat within South Cow Creek is approximately 44% riffle, 44% flat-water and 5% pools. Average pool depth is 1.8 feet and the average canopy cover is 70%.

The SWAG report concluded Old Cow Creek is in good condition and contains generally complex habitat with deep pools, riffles, and boulders forming step pools. The SWAG reports that 99% of Old Cow Creek was stable with the first 300 feet of Old Cow Creek within Old Cow Creek Meadow, being rated as stability at risk. The stream banks were stabilized primarily by large cobbles, boulders, and riparian vegetation. By length

Section 4

North McMullen Mountain THP

habitat within Old Cow Creek is approximately 40% riffle, 40% flat-water and 20% pools. Mean pool depth of Old Cow Creek is 1.4 feet and the overall canopy cover of Old Cow Creek is 66 %.

The 4500-foot Class I segment of Bullhock Creek which is tributary to South Cow Creek was also rated as being stable. The channel of Bullhock Creek is steep with the banks being stabilized with large boulders and diverse woody riparian vegetation. By length habitat is 36% riffles, 58% flatwater, and 6% pools. The average canopy cover of Bullhock Creek is 62% and the mean pool depth is 1.4 feet.

Salmonid spawning habitat may be considered to be degraded when fine sediment levels reach 20 % or greater. Within LDSF Old Cow Creek has the lowest percentage of surface fines, at 6.3 %; South Cow Creek has 15.1%; and Bullhock Creek has 9.8%.

Approximately 70% of the Atkins Creek watershed was burned in the 1978 Whitmore Fire. The fire and the reforestation of the timberlands has resulted in the vegetation type within the watershed is predominately a 30 year old coniferous plantation. The average canopy cover of Atkins Creek located on LDSF is 55 %, with 51% being from deciduous trees. Atkins Creek is primarily located within meadows with a low gradient. Atkins Creek's habitat by length has 22% riffles, 70% flatwater, 4% pools and 55% dry, with the mean pool depth being 1.4 feet. The dominant instream cover is undercut banks. Bank erosion is evident throughout the reaches assessed. Observed impacts to Atkins Creek are all related to cattle grazing. Impacts from timber management are not considered significant

The SWAG reports that instream Large Woody Debris (LWD) on LDSF is primarily concentrated in debris jams and not scattered throughout the stream reaches. This is to be expected in steep headwater streams, such as those found on LDSF. LWD will accumulate over time in debris dams until a flooding event provides enough energy to dislodge the debris jam and transport the material downstream. Additionally, on LDSF some LWD and some large trees were removed in 1983, by a fly fishing club, after consultation with the Department of Fish and Game.

Various portions of the plan area were initially harvested in the early 1960's. A second entry occurred in the 1980s -1990s, which covered most of the plan area. Past harvests used the selection silvicultural system. There are numerous existing skid trails and landings that exist within the harvest area from the previous harvests. The existing skid trail pattern and existing landings are the primary yarding design for this harvest. There will be minor changes to the existing skidding pattern and the location of a couple landings. The alterations in the skid pattern, landing location or landing size are to accommodate modern mechanized harvesting methods. Slopes of the harvest area within the THP are variable and range from flat to slopes upwards of 55%.

All operations within or adjacent to watercourses

Sediment Effects

Sediment-induced cumulative watershed effects (CWE) occur when earth materials transported by surface or mass wasting erosion enter a stream or stream system at separate locations and are then combined at a downstream location to produce a change in water quality or channel condition. Sediment effects result from many factors such as weather, geology, soil erosion potential, road location, silviculture, vegetation retention, and heavy equipment operations adjacent to watercourses. Sedimentation has occurred to tributaries of the South Cow Creek during the winter storms of 1997, when rain-on-snow events caused significant runoff resulting in culvert crossing failures and road fill washing into the drainage system.

The management of LDSF has a goal of reducing sedimentation to watercourses. The LDSF has developed and implemented a Road Management Plan (RMP) in compliance with the California Environmental Quality Act (CEQA) that will reduce erosion and sediment from the permanent road system. Implementation of the RMP involves systematic survey of the road system and all watercourse crossings. Watercourse crossings are evaluated as to their potential to fail or contribute sediment from improper installation.

Through the implementation of the RMP 46 sites have been identified as problem locations within the

assessment area. Since 1999, 39 of the 46 sites have been corrected. Corrective measures have included: over 20 miles of have been treated to improve drainage and reduce erosion. This treatment has included outsloping and installing rolling dips and road rocking; approximately 1.5 miles of road have been abandoned; and 15 watercourse crossings have been upgraded. All of these actions have or will reduce potential sediment inputs into assessment area.

There are four additional sites within the RMP that will be corrected through the implementation of this THP. Three of the sites are associated with inadequate drainage and lack of ditch maintenance. The forth site is an improperly abandoned section of obsolete road.

1. A segment of the White Fawn Gulch road location between the two junctions with the Section Loop road has a heavily eroded inside ditch and poor road surface drainage. This segment of road has been identified to be abandoned in Item 25 of the THP.
2. Old Peavine road was improperly abandoned above the intersection with White Fawn Gulch road. This segment of road has been identified to be abandoned in Item 25 of the THP.
3. The segment of the White Fawn Gulch road east of the abandonment segment described in Item 25 of the THP and in number 1 above has very few drainage features and is inadequately drained. This site will be corrected through the routine maintenance of logging roads during operation, as is required by 14 CCR 943.4. The grading of the road and then installation of additional drainage features (waterbars, rolling dips and/or ditch relief culverts) will adequately drain this segment of road.
4. A quarter mile segment of the Section Loop road west of the abandoned segment of White Fawn Gulch road described in Item 25 of the THP and in number 1 above has eroding inside ditches, blocked inside ditches and is inadequately drained. This site will be corrected through the routine maintenance of logging roads during operation, as is required by 14 CCR 943.4. The grading of the road and then installation of additional drainage features (waterbars, rolling dips and/or ditch relief culverts) will adequately drain this segment of road.

Road Maintenance means activities used to maintain and repair roads involving minor manipulation of the road prism to produce a stable operating surface and to ensure road drainage facilities, structures, cutbanks and fillslopes are kept in a condition to protect the road, minimize erosion, and to prevent sediment discharge into a watercourse or lake. Examples of road maintenance include shaping and/or rocking a road surface; installation and maintenance of rolling and critical dips; restoring functional capacity of inboard ditches, cross drains, or culverts; and repairing water bars.

No cumulative sediment impacts are predicted with the implementation of the THP.

Water Temperature/Thermal Loading Effects

Water temperature related CWEs are changes in water chemistry or biological properties caused by the combination of solar warmed water from two or more locations (in contrast to an individual effect that results from impacts along a single stream segment) where natural cover has been removed. Due to the elevation of the plan area the two major factors that would affect water temperature are water source and canopy cover. The contribution of water from the plan area within both watersheds, during the summer months, is spring-fed watercourses from streams with gradients that result in high flow velocities. Stream reaches with low flow velocities and full solar exposure that would result in an increase in water temperature are uncommon on the LDSF within these watersheds. Past harvests have maintained canopy cover over watercourses. The SWAG report found that the Class I watercourses on LDSF within the Watershed Assessment Area had an average of 69% canopy cover, measured with a solar pathfinder, within the LDSF boundaries. Ninety four (94) percent of this cover consisted of coniferous vegetation.

This THP will maintain streamside vegetation that will continue to shade watercourses from solar radiation and prevent water temperature increases.

Organic Debris/LWD Effects

Large woody debris can have both positive and negative effects on a watercourse. Large woody debris is an important stabilizing agent in steep gradient channels. The sudden introduction of large, unstable volumes of bigger debris (such as logs, chunks, and larger limbs produced during a logging operation) can obstruct and divert stream flow against erodible banks, block fish migration, and may cause debris torrents during periods of high flow. Removing streamside vegetation can reduce the natural, annual inputs of litter to the stream (after decomposition of logging-related litter). This can cause both a drop in food supply, and resultant productivity, and a change in types of food available for organisms.

Based upon the California Department of Fish and Game's *California Salmonid Stream Habitat Restoration Manual –Third Edition*, the SWAG study found that on average there were 22 pieces of large woody debris per 100 feet of watercourse segment in the Class I watercourses on the LDSF. Watercourse protection provided in the plan will continue to provide both LWD for streamside habitat and prevent the sudden introduction of debris from harvesting practices.

Chemical Contamination Effects

Sources of chemical contamination include run-off from roads treated with oil or other dust-retarding materials, direct application or run-off from pesticide treatments, contamination by equipment fuels and oils, and the introduction of nutrients released during slash burning.

The use of oil or dust retarding materials is not planned for this THP, but may occur. The types of dust palliatives that have been used on LDSF have been hygroscopic salts and resins, these materials are considered to be non-hazardous as per MSDS information provided to LDSF. These materials are non-flammable, non-combustible and are considered to be low or non-toxic to aquatic organisms. When these materials are utilized on LDSF, they will be applied under ideal weather conditions to allow for rapid curing. Potential hazards associated with the proper delivery and application of these products is very unlikely. By controlling the application process, using only licensed applicators and adhering to the MSDS, product labels and application recommendations, accidental spills can be minimized, eliminated and controlled if they occur. Additionally 90 % plus of dust abatement on LDSF is accomplished by use of water and water trucks.

Accidental contamination of equipment fuel or oil is unlikely. Fuel is stored in an area where it cannot contaminate a watercourse if a leak occurs. Additionally, equipment shall be serviced outside the protection zone of watercourses.

FEB 08 2011

Herbicides have been used on LDSF for demonstration, research and for the establishment, survival and improved growth of new forest stands. The use, type and the timing of the herbicide shall be determined and recommended by a PCA. The application shall be made by a Licensed applicator and adhere to the DPR regulations, a PCA's recommendation, the herbicide label instructions, and the Mitigated Negative Declaration, State Clearing House (SCH) # 2008062009 for LDSF Management Plan 2008.

The use of herbicides as a tool to control vegetation is determined by the vegetation present on site, by the vegetation targeted for control and the level of control needed to accomplish the goals of the project. These factors, as well as local weather patterns, soil types, topography, and the presence of threatened or endangered species are used to determine if herbicides will be used. The specific recommendation for the type of herbicide, application rate, timing, and application method will be determined by the site specific conditions and made by a Licensed Pest Control Advisor (PCA).

The three main brush species targeted for control on LDSF are chinquapin, manzanita, and snow brush. Other species that may be targeted in specific situations are gooseberry, currant, bitter cherry and various grasses. Application methods have been typically a directed backpack application to target species and two aerial applications following the 1978 Whitmore Burn.

Individual herbicide applications are based on label and MSDS restrictions, and written recommendations by PCA, that provide CEQA equivalency. The recommendations build upon the pesticide, surfactant and adjuvant Labels and Material Safety Data Sheets, which provide information potential for movement and toxicity. The PCA Recommendations consider site specific information such as vegetation present on site, targeted species, restrictions on chemical use, current and forecasted weather, soil types, topography, and the presence of threatened or endangered species. These recommendations will also evaluate proximity to schools, apiaries, neighbors, domestic water systems, presence of wetlands, watercourses, amphibians, and fish. If necessary these recommendations will include mitigations to reduce the impacts to apiaries, humans or biological resources. Mitigation examples include but are not limited to drift control measures, buffers, avoidance, weather restrictions, and timing. Additionally, LDSF is open range and grazing cattle are periodically present. Each pest control recommendation will consider the probability that cattle could graze treated vegetation (location and timing) and select herbicides with appropriate grazing restrictions.

Specific herbicide use depends on the nature of the vegetation and site conditions and may change based on availability from the manufacturer, registration status, feasible treatment alternatives and the recommendations of the PCA. Active ingredients in previous herbicides used on LDSF include Glyphosate, Triclopyr, Imazapyr, 2-4D, Hexazinone and picloram. The Carbon Sequestration research project on LDSF is currently utilizing Glyphosate, Triclopyr, and Imazapyr.

- Glyphosate is a non selective, post emergent herbicide. Glyphosate's mode of action is to inhibit an enzyme involved in the synthesis of the aromatic amino acids: tyrosine, tryptophan and phenylalanine. It is absorbed through foliage and translocated to growing points. Glyphosate is registered for forestry applications under various product labels. Selective control of undesirable vegetation is obtained through low volume directed backpack applications.
- Triclopyr and 2-4D are highly selective herbicides and a target broadleaf weeds and woody brush. They are considered hormone weedkillers and are within the largest group of herbicides used worldwide. These herbicides have complex mechanisms of action against weeds, resembling those of growth hormones. Once absorbed they are translocated within the plant and accumulate at the growing points of roots and shoots where they inhibit growth. Both chemicals are registered for forestry applications under various product labels. 2-4D has following restrictions; it has a ground water advisory, and can not be applied through an irrigation system. 2-4D applications must be permitted by the Shasta County Agriculture Commissioner.

PART OF PLAN

Section 4

North McMullen Mountain THP

- Imazapyr is a non-selective broad-spectrum systemic herbicide, absorbed by the foliage & roots and causes disruption of protein synthesis. Imazapyr is registered for forestry applications. Selective control of undesirable vegetation is obtained through low volume directed backpack applications.
- Hexazinone is a non-selective broad spectrum herbicide which inhibits photosynthesis. It is registered for use in agriculture and forestry for selective weed control. It is a soil active herbicide and used to control grasses and broadleaf and woody plants. Selective control of undesirable vegetation is obtained through low volume directed backpack applications.
- Picloram is a systemic herbicide used for general woody plant control. It also controls a wide range of broad-leaved weeds. Selective control of undesirable vegetation is obtained through low volume directed backpack applications.

New products, formulations and application techniques may provide better control and improved environmental toxicology profiles than the chemicals previously utilized at LDSF. Additionally as part of LDSF's research and demonstration mission, small-scale herbicide trials or vegetation control studies are likely to occur. For this reason, in the future, there may be additions or deletions to the list of herbicides considered for use on LDSF.

Additional background on herbicide regulation and use is included as this is a topic of concern to some members of the public. The U.S. Environmental Protection Agency regulates pesticide use nationwide and has exclusive authority over pesticide labeling. Use of a pesticide is limited to the applications and restrictions on the label, and the label restrictions are legally enforceable. The California Department of Pesticide Regulation (DPR) regulates pesticides within the State of California and has legal authority to adopt restrictions on pesticide use going beyond the regulations of the U.S. Environmental Protection Agency (7 U.S.C.A. §136v). Under California law, pesticide products must be registered by DPR in order to be sold and used in California. Before a substance is registered as a pesticide for the first time, DPR conducts a thorough evaluation. After a pesticide is registered for use in this state, DPR has an ongoing obligation to review new information received about the pesticide that might show new problems beyond those identified in the registration process. DPR is the lead agency for regulating herbicide use under CEQA. Where the review of new information shows that a significant adverse impact has occurred, or is likely to occur, DPR is required to reevaluate the registration. The regulatory program of DPR and the county agricultural commissioners is thorough, detailed, and involved.

DPR's program for regulating pesticides was certified by the Secretary of the Resources Agency as a functional equivalent program under Public Resources Code (PRC) § 21080.5 in the same manner as the state's program of regulating timber harvesting was certified (14 CCR. § 15251(i)). Because the program is certified, DPR does not prepare environmental impact reports (EIRs) but prepares other documents in the place of EIRs (PRC § 21080.5(d)(3)). Because the registration evaluation process considers use of an herbicide in a broad area and in a variety of conditions, the documents are the functional equivalent of a program EIR for each pesticide. By the terms of its certification, the program is prevented from approving the registration as requested if there are feasible alternatives or mitigation measures available that could lessen any significant adverse effects on the environment (PRC § 21080.5(d)(2)(A)). By § 12825 of the Food and Agricultural Code, DPR may refuse to approve the registration of a new pesticide if its use would cause a significant adverse effect on the environment.

If DPR determines that further restrictions need to be placed on the use of a pesticide product to mitigate potential adverse effects, including human health effects and environmental effects, DPR classifies the pesticide as a restricted pesticide, and individual applications need a permit from the county agricultural commissioner. Site specific application and use of restricted pesticides is evaluated by the county agricultural commissioner during its review of applications for restricted materials permits. Not all pesticides are restricted, and only restricted pesticides require a permit from the county agricultural commissioner, except for a pesticide that DPR has not designated as restricted, the commissioner can require a permit for its use if the commissioner makes a finding that the pesticide will present an undue hazard when used under local conditions.

Because DPR is the CEQA lead agency, its determination the use will not have a significant effect on the environment is binding on all State agencies, including CAL FIRE (PRC § 21080.1, 14 CCR § 15050). Accordingly, if a DPR registered herbicide will be used in accordance with the directions and restrictions on the

PART OF PLAN

Section 4

North McMullen Mountain THP

pesticide product label and any other restrictions established by DPR, CAL FIRE is required to find that the use will not have a significant effect on the environment unless there is new information showing significant or potentially significant effects not analyzed by DPR. The significant new information must show that the use would cause a new significant effect on the environment that had not been analyzed previously, that a previously analyzed effect would be much more severe, or that a new feasible alternative or mitigation measure, considerably different from ones analyzed previously, would lessen the significant effect but the project proponents declined to adopt it (14 CCR § 15088.5(a)). If CAL FIRE receives comments on proposed herbicide use, CAL FIRE will need to determine whether the information qualifies as significant new information. CAL FIRE will consult with DPR and the county agricultural commissioner about the submitted information both to obtain the evaluation by the agencies with their expertise and to alert them about the issues. DPR could respond to the information with a decision to reevaluate the registration of the herbicide or it could advise CAL FIRE that the information is repetitive of what was evaluated during the registration decision.

The Shasta County Agricultural Commissioner has responsibility for compliance and enforcement actions, registration of businesses that perform pest control in Shasta County, issuing Restricted Materials Permits and Operator ID numbers and other regulatory responsibilities. The THP and the state forest does not lie in the Shasta County Groundwater Protection Areas. The Central Valley Water Quality Control Board does not require notification for herbicide application that is applied in accordance to the product labels.

LDSF staff will review the PCA's recommendation, the recommended herbicide's, surfactant's, and adjuvant's intended use and the possible environmental effects of each. LDSF will work with the PCA to determine whether the proposed use would be consistent with the label, the registration limitations, the THP and LDSF's management plan. LDSF will also check for significant new information showing changes in circumstances or available information that would require new environmental analysis. Significant new information should be referred to DPR for that department's analysis as part of its ongoing evaluation program.

Details of herbicide, surfactant and adjuvant chemistry, including mode of action and break down products as well as manufactures formulations are evaluated in depth by EPA and DPR during both the registration process and periodic reviews. In addition to the label and MSDS the following can be reviewed for information relevant to the project; National Pesticide Information Center <http://npic.orst.edu/>.

The registration of herbicides in California is a CEQA equivalent process, and the herbicide's label is a comprehensive document about the herbicide, any associated hazards, active and inactive agents, and the proper use and handling of the herbicide. When herbicides are applied according to the label instructions, PCA's recommendation, and with a licensed applicator, no significant adverse impacts to wildlife and water resources are likely to occur.

No cumulative watershed effect, with regards to chemical contamination, is predicted for this THP.

Peak Flow Effects

Peak flow increases may result from management activities that reduce vegetative water use or produce openings where snow can accumulate (such as clear-cutting and site preparation) or that change the timing of flows by producing more efficient runoff routing (such as insloped roads).

The assessment area has experienced high peak flows from rain-on-snow events. These events, such as occurred in 1997, are unpredictable. The proposed silvicultural prescriptions will maintain vegetation over the plan area that will enhance infiltration of precipitation and maintain peak flows. Groups within the selection area will be less than 2.5 acres and will be planted to establish vegetation in the opening. There are no new roads planned for this timber harvesting plan that would reroute and concentrate runoff. As stated above for sediments effects, the drainage of existing roads is being improved through implementation of LaTour's Road Management Plan. The potential for this plan to increase peak flows is insignificant.

This harvest will have no impact on water temperature, organic debris, chemical contamination, or peak flow cumulative watershed effects. Sediments effects from road use and harvesting activities may occur but will be insignificant. No new road construction is planned nor will large openings be created. Nearly all tractor roads needed for this harvest exist. All watercourses and springs within and adjacent to the harvest area will be protected. Post harvest streamside vegetation will continue to provide filter strip properties and shading. Water drafting is proposed at four locations. Drafting locations will be rocked to prevent the introduction of sediment into the watercourse during drafting operations. Additionally the vehicles will be inspected to ensure chemical contaminants are not introduced into the watercourses. The silvicultural systems being applied should have no effect on peak flow. The vigorous residual stand will continue to maintain infiltration capacities and hold soil in place.

303(d) Listing

South Cow Creek is 303(d) listed based on the pollutant of Fecal Coliform. The possible sources of fecal coliform include agriculture, grazing related sources and others. LDSF is not considered a highly desirable grazing area, due to steep slopes, dense timber cover and minimal meadow grazing potential. Additionally, weather conditions on LDSF also contribute to the loss of grazing potential (moderate to heavy snow loads in the winter and spring). Although LDSF has no grazing permits, it is located within open range and cattle do graze and travel through the property. This THP does not propose cattle grazing nor will timber harvesting increase or decrease fecal coliform potential.

C. Soil Productivity Assessment

The soil series within the harvest boundary are Windy - McCarthy stony sandy loam and Cohasset stoney loam. Cohasset stoney loams comprise about 80% of the plan area. Windy - McCarthy soils are made up the remaining portions of the THP. Both these soils are volcanic in origin and are stony to very stoney throughout the soil profile. They are well-drained soils with moderate to rapid permeability. Both soil series have soil depths up to 60 inches and are considered moderately productive timberland soils.

The primary factors influencing soil productivity to be assessed are:

1. Organic matter loss
2. Surface soil loss
3. Soil compaction
4. Growing space loss

Organic matter loss

The entire harvest area will be logged by tractor and disturbance of organic matter will occur. Throughout the harvest area there are many existing skid trails that will be utilized for this harvest. Few new skid trails will be constructed. When these skid trails are utilized organic matter will be displaced from them. To minimize disturbance, equipment will utilize designated skid trails and trees will be felled to these skid trails. Replacement of organic matter will occur through logging residue, tree tops and limbs that will be left behind after harvest and from natural needle fall. Any existing skid trails not pertinent to the harvest will not be utilized.

Existing down woody material throughout the harvest area will remain. Retaining unmerchantable material in the harvest area will recruit woody material. In addition to providing wildlife habitat, leaving woody material will add organic matter to the forest floor. Increases of organic matter to the forest floor will also occur from the planned lop and scatter slash treatment throughout the entire plan area.

Surface soil loss

Surface soil loss will occur by displacement of soil from skid trail construction and log skidding. There are many existing skid trails from past harvests and the need to construct new ones is minimal. Only one new landing is planned. The loss of surface soil from construction will be slight. Surface soil loss from erosion will be nominal due to the silvicultural systems being applied, lack of road construction, and installation of water breaks on skid trails and landings after completion of use.

Soil Compaction

Soil compaction will occur from the tractor skidding operation. Compaction will be greatest on main skid trails. To reduce compaction over the harvest area and eliminate random wandering by equipment operators, main skid trails will be kept to the minimum needed to carry out the harvest. Skid trails will be designated prior to timber operations and equipment will be required to use designated trails, which will reduce the impact from compaction to the harvest area. Harvest activities will occur when soil moisture is low. When soils are saturated timber operations will be suspended. Timber operations will not occur during the winter period.

Growing Space Loss

Growing space loss from skid trail construction will occur, however, it will be minimal. All roads, landings, and skid trails are considered permanent. New skid trails are constructed so that they can be utilized in future harvests. The use of existing skid trails will be required. There may be a need for the construction of a few new skid trails for this harvest. All roads needed for this harvest exist and no new roads are planned.

D. Biological Assessment**PART OF PLAN****Scoping**

The Natural Diversity Data Base (NDDDB) was used as a scoping tool to check if any rare, threatened, endangered, or special concern species and/or their habitat are located on or surrounding the THP area. A nine quadrangle query was conducted, which included Jacks Backbone 7.5 minute quad, its surrounding eight quads. The following is a list of rare, threatened, endangered species, and/or their habitat that occurs within the THP area. There are no recorded occurrences of threatened or endangered species on LDSF.

Anadromy

There are no known occurrences of anadromous salmonids within the biological assessment area. The Beal and Atkins Creek planning watersheds are listed as a threatened and impaired for Chinook salmon and Central Valley Steelhead. No anadromous salmonids occur on LaTour nor are there historical records of observations in the Beal Creek Watershed.

In the development of the THP there were no pre-plan adverse affects identified within the plan area or the watershed and biological assessment areas. Additionally the implementation of this THP will have no significant cumulative watershed effects on the populations and habitat of anadromous salmonids. The Watershed assessment (section B) addresses sediment, thermal loading, large woody debris, and peak flow. Mitigation in the water drafting plan will prevent a take, if Steelhead are present in Atkins Creek. Harvesting activities along watercourses have been conservative in the past resulting in timber stands that provide good shade cover. With the implementation of the THP, and the protection afforded to the watercourses within the THP coupled with the requirements of the Forest Practice Act and Board of Forestry rules there should be no adverse cumulative impact to anadromous fish or other aquatic species or habitat.

Chinook salmon (*Oncorhynchus tshawytscha*): Information within the *Cow Creek Watershed Assessment*, prepared by SHN Consulting Engineers & Geologists Inc., indicates that fall run Chinook have occurred in the lower reaches of South Cow Creek below Wagoner Canyon approximately 10 miles west of the Forest. Historical data indicates salmon above Wagoner Canyon were scarce due to a natural barrier in the Canyon and a dam constructed across South Cow Creek by PG&E in 1908. The barrier was removed by blasting and a fish ladder was constructed at the dam in the 1970's by the Department of Fish and Game. However, local residents state there was no significant increase in the number of fish above the dam. The Cow Creek report suggests one of the key limiting factors is adequate stream flow to provide passage of adult fish. Water is diverted from South Cow Creek for irrigation and power use during critical passage periods.

Central Valley steelhead (*Oncorhynchus mykiss*): Steelhead were reported at the crossing of South Cow Creek by Ponderosa Way, approximately 9.5 miles west of the plan boundary. No physical barriers exist on South Cow Creek upstream of the Ponderosa Way crossing; as such Steelhead could potentially migrate upstream into the Beal and Atkins Creek planning watersheds. It is unlikely they occur within Atkins creek due to low flows during the summer and fall. The Cow Creek report suggests one of the key limiting factors is adequate stream flow to provide passage of adult fish. Water is diverted from South Cow Creek for irrigation and power use during critical passage periods.

From dives performed in 2000 for the fish habitat assessment of the SWAG report, only rainbow trout were observed in South Cow Creek, Old Cow Creek and Atkins Creek on the LDSF.

FEB 08 2011

Northern Goshawk: As discussed in Item #32 of the THP, the harvest area contains habitat for the Northern Goshawk. Protection measures are discussed in Section III of the plan. The silvicultural prescriptions proposed will have a very low impact on the Northern Goshawk's habitat requirements. The type of silviculture being conducted may even improve forage habitat conditions for the goshawk where dense fir stands are thinned and the tree and tree crown spacing is improved by the harvest.

Sierra Red Fox: The assessment area and the THP do contain the vegetation types considered habitat for the Sierra Red Fox. Observations of the red fox have occurred within the scoping area and primarily around Lassen Volcanic National Park. The closest observation to the THP is near Highway 44 and Scharch Meadow. LDSF staff has been conducting forest carnivore surveys the last three years and the Sierra Red Fox has not been detected. The project will maintain habitat for the Sierra Red Fox.

FEB 03 2011

California Wolverine: The California wolverine has been detected within the scoping area. The assessment area and the THP do contain the vegetation types that are considered habitat for the wolverine. LDSF staff has been conducting forest carnivore surveys the last three years and the wolverine has not been detected. The project will maintain habitat for the California Wolverine.

Pine Marten: The assessment area and the THP do contain habitat the Pine Marten. Pine Marten were detected on LDSF in a 1990 furbearer presence survey. The Pine Marten has been detected in the southeastern portions of the forest, within the assessment area, during the forest carnivore surveys being conducted by LDSF staff in 2005 and 2006 and 2007. The THP will maintain habitat for both the Pine Marten and the Pacific Fisher.

Pacific Fisher: LDSF contains habitats for the Pacific Fishers and it was detected in a 1990 furbearer presence survey. No subsequent detections have occurred. The elevation of the plan is generally considered above the range of the pacific fisher, but contains habitat for the Pacific Fisher. The plan will maintain habitat post harvest. Protection measures are discussed in Section II of the plan.

Nodding vanilla grass, *Hierochloa odorata* (CNPS 2.3): The assessment area and the THP have the general habitat types associated with the known occurrences of vanilla grass. Vanilla grass is located within wet meadows and seeps above 5400 feet in elevation. The THP provides protection for all meadows and seeps.

Rayless mountain ragwort, *Packera indecora* (CNPS 2.2): Rayless mountain ragwort is located in meadows and seeps on mesic sites between 5200 and 6500 feet in elevation. The assessment area and the THP has the general habitat types associated with the known occurrences of Rayless mountain ragwort. The THP has potential habitat along the class II watercourses, meadows, springs and seeps. The THP provides protection for all meadows, seeps, and watercourses. The THP also restores potential habitat for Rayless mountain ragwort.

Scalloped moonwort, *Botrychium crenulatum* (CNPS 2.2): The assessment area and the THP have the general habitat types associated with the known occurrences of scalloped moonwort. Scalloped moonwort is located along moist meadows and near creeks of lower montane coniferous forests and freshwater marshes above 4500 feet in elevation. The THP provides protection for all meadows, seeps, and watercourses.

Long-stiped champion, *Silene occidentalis spp longistipitata* (CNPS 1B.2): CNPS identifies habitat as between 1000-2000 meters in Lower and Upper Montane coniferous forests and the NDDDB add no further information. In the non published *Conservation Assessment and Strategy for Long-stiped Champion...*, a USFS Forest Service, Pacific southwest Region and Lassen National Forest document, the key habitat an biological parameters are: 1) occurs in openings of mid elevation mixed conifer forests as well as on ridgetops in black oak, 2) low canopy closure 3) survives in disturbed habitats and disturbance may be a important factor, 4) occurs in thin soils with clay and have various amounts of sand and rock. This document was provided to LaTour Demonstration State Forest from DFG. The THP does have the clay soils and is above the elevation range.

FEB 08, 2011

The following table shows additional species scoped by the CNDDDB, (verified on September 22 2010). The THP area contains no habitat for these species.

Scientific Name	Common Name	Status	CNPS List	Comments
<i>Fritillaria eastwoodiae</i>	Butte County fritillary	None	3.2	THP is above elevation
<i>Cryptantha crinita</i>	silky cryptantha	None	1B.2	THP is above elevation
<i>Potentilla newberryi</i>	Newberry's cinquefoil	None	2.3	Marshes and swamps
<i>Potamogeton praelongus</i>	White-stemmed pondweed	None	2.3	Marshes and swamps
<i>Asplenium septentrionale</i>	Northern Spleenwort	none	2.3	Granite like outcrops
<i>Smelowskia ovalis</i> var <i>congesta</i>	Lassen Peak smelowskia	None	1B.2	Alpine bolder and rock field
<i>Silene suksdorfii</i>	Cascade alpine campion	None	2.3	Alpine bolder and rock field
<i>Astragalus pulsifera</i> var <i>suksdorfii</i>	Suksdorf's milk-vetch	None	1B.2	Lower Montane Coniferous
<i>Collomia larsenii</i>	Talus collomia	None	2.2	Loose volcanic material
<i>Botrychium virginianum</i>	Rattlesnake fern	None	2.2	THP is above elevation
<i>Hulsea nana</i>	Little hulsea	None	2.3	Rocky or gravely volcanic Sub-Alpine forests
<i>Eriogonum pyrolifolium</i>	Pyrola-leaved buckwheat	None	2.3	Alpine bolder and rock field
<i>Juncus digitatus</i>	Finger rush	None	1B.1	THP is above elevation
<i>Calochortus longebarbatus</i> var <i>longebarbatus</i>	Long haired star tulip	None	1B.2	Heavy clay soils
<i>Cryptantha crinita</i>	Silky cryptantha	None	1B.2	THP is above elevation
<i>Stachys palustris</i> ssp. <i>Pilosa</i>	Hairy marsh hedge-nettle	None	2.3	THP is above elevation
<i>Rana boylei</i>	Foothill yellow-legged	Special	N/A	THP is above elevation, outside range
<i>Pandion haliaetus</i>	Osprey	Special	N/A	No good fish producing body of water
<i>Haliaeetus leucocephalus</i>	Bald eagle	Endanger	N/A	No good body of water near
<i>Falco peregrinus anatum</i>	American peregrine falcon	Endanger	N/A	No habitat for nesting
<i>Oncorhynchus tshawytscha</i>	Spring run Chinook salmon	Threat	N/A	No occurrences in watershed.

There are numerous other wildlife species that exist on the THP and LDSF that are not listed as threatened, rare, or endangered. The South Cow Creek deer herd uses LDSF as summer range and fawning area. In the past, certain designated brush fields have been burned to improve forage habitat for the deer. There are other brush fields that may be burned in the future.

Habitat types

The forest inventory on LDSF indicates there are 7130 acres of merchantable sized timber stands and 677 acres of plantation (1978 Whitmore burn). The remainder of the Forest is brush, rocky areas, meadows, and open areas with scattered trees

Timber types and WHR habitat types for LDSF have been determined through aerial photo interpretation, vegetation inventory, and the use of a database program written by the Forest Staff which determines WHR types from forest inventory data. Plot data from the inventory represents a 2.5-acre area and the WHR type was determined for each plot. Within the plan area the tree size classes ranged from 3 to 5 and with a range of canopy closure from open to dense. The predominant WHR types were Sierra Mixed Conifer and White Fir 4D and 4M. Though the THP has scattered mature trees and WHR 5M, 5D types exist in the plan area, these stands are scattered and do not have the continuity to qualify as late succession forest stands per rule definition. LDSF has had multiple entries (4-5) since it became a State Forest in the late 1940s. The THP has been harvested with un-even aged silviculture 4 times. There are no Late Seral Forests or characteristic on the THP area. The desired forest structure on LDSF is described within *LDSF 2008 Management Plan*, "The overall goal is to maintain LDSF as a mid-seral forest type characteristic of the southern Cascades. Early and late seral stands will be represented but overall the Forest will maintain the characteristics of a mid-seral forest. This goal is not discretionary, but rather follows directly from the research and demonstration mandate for LDSF. Rather than a park or reserve, the legislated mandate for the Forest is that of a working forest property for demonstration and research purposes, serving a clientele of small to medium size land owners.

In order to remain relevant as a research forest, LDSF aims to create and maintain a wide range of forest types, ages, size classes, successional stages and structural characteristics. It is going to be very difficult to maintain pure stands of each of these characteristics on a Forest the size of LDSF. As a result, LDSF's approach will be to incorporate a continuum of types, age classes, successional stages and structures mixed within stands across the Forest as far as possible."

Snags and large down woody material are present on the THP and within the assessment area. Additional recruitment of snags and downed woody material will be accomplished through the retention of green cull trees and un-merchantable material in the forest stands.

Hardwoods

Hardwoods are not a large component of the stands on the LDSF, which is true for the THP area. The THP is located above 5400 feet in elevation, which is generally above the upper elevation limit at which oaks grow. Harvesting of oaks will not occur within the THP area.

Road density

Road densities, which can have a potential effect on wildlife, are moderate on LDSF and within the assessment area. The average density per section is 4 to 5 miles of seasonal and rocky seasonal roads on LDSF. Although accessible to the public, these roads receive little traffic most of the year. There is no new road construction proposed within the THP and there is .5 miles of roads being abandoned.

E. RECREATIONAL ASSESSMENT

The recreational activities that normally occur in the recreational assessment area is deer hunting, camping, fishing, snowmobile riding, and site seeing. Mountain bike riders occasionally use the forest but are rare and infrequent. Additionally, the forest is used by the public for fuelwood cutting. The rock pit harvest unit is will occur along the main forest access road, Bateman Road. The road may be blocked to traffic for short periods of time during active timber operations. A sign will be posted on the Bateman road at the west entrance to the LDSF to warn the public of logging activities in the area and the Licensed Timber Operator will be advised to watch for recreationists and to allow thru traffic on Bateman Road.

The primary use within the recreational assessment area is deer hunting. Impact to hunting may occur during any year the THP is operated since, for safety reasons, no hunting will be permitted in the vicinity of timber operations

An agreement exists with the Lassen National Forest to allow the grooming of approximately 30 miles of Forest roads during the winter for snowmobile use. This recreational activity will not be adversely affected by timber operations.

F. VISUAL RESOURCE ASSESSMENT

This timber harvest cannot be seen by significant numbers of people since the harvest area is not visible from any well-traveled roads or communities. The closest paved public road is the paved section of Bateman Road, 11 miles to the west of the LDSF boundary. Adjacent ownerships are accustomed to timber production, however, one home is approximately 1/4 mile west of LDSF boundary. The harvest area cannot be viewed from the home, however, logging traffic will likely travel by the home enroute to/from Redding. There will be no adverse effect on the visual resource. The prescribed silviculture will not adversely change the visual aspect of the assessment area. The greatest visual impact will be from within the stand after harvest.

G. VEHICULAR TRAFFIC IMPACTS

Forest products from the harvest area will be hauled out over two potential routes. This will cause a slight increase in vehicular traffic.

a. Cutter Road and Tamarack Rd (Shasta Co. Road)

This a seasonal road network with permanent culverts at watercourse crossings. The first 3miles of the tamarack road is chipped sealed or graveled and the remaining portions of the Tamarack road and the Cutter road are native soil surfaced roads that have a high coarse fragment content. These roads will not be used when soils are saturated. These roads will only be used during the non-winter months and a maintenance agreement and permit will be obtained prior to use for all privately owned roads. These roads will be graded as needed and watered during the operation (if used for log hauling).

b. Bateman Road.

This haul route will result in traveling down the Bateman Road. The Bateman Road is a private road with public access and is graveled from Atkins Creek (end of the county road) to the harvest boundary. The one homeowner on the graveled portion of the road has posted 10 MPH signs near his home. The LTO will be advised to comply with the 10 MPH limit when passing by the home. The primary use of the road is from logging operations, recreation and access to the residence. Eleven miles of dirt and gravel roads will be used following this route. Bateman road will be graded as needed and watered during the operation (if used for log hauling).

Since the main use of these haul routes is logging traffic the impact to people who use them on a regular basis will be almost non-existent. The greatest impact from the increase in traffic will be on recreationists using these roads. Since weekend operations are not planned the impact will be minor.

H. OTHER**Climate Change and Forestry Practice**

This THP complies with LDSF approved Management Plan, Mitigated Negative Declaration and Option A analysis. The following information is part of LDSF Mitigated Negative Declaration for LaTour Demonstration State Forest (SCH#2008062009) and the LDSF Management Plan:

In 2007 the State of California passed the Global Warming Solutions Act (AB 32), which set targets to reduce greenhouse gas emissions to 1990 levels by 2020 and 80 percent below 1990 levels by 2050. The California Air Resources Board was tasked with obtaining compliance with the cap through regulatory and market approaches. Planning is currently underway and definitive decisions by the Board have not yet been taken, however, it appears that forests will play a significant role in non-regulated strategies to meet targets. This is anticipated to occur both as offsets within a cap and trade system and through voluntary measures.

Recognized strategies to mitigate GHG emissions and enhance terrestrial sequestration include reforestation, forest management and fuels treatments to avoid catastrophic losses. LDSF will contribute to the targets of AB32 by increasing the resiliency of the Forest to catastrophic mortality by improving the general health of stands, pre-fire implementation of a shaded fuel break and maintenance of firefighting infrastructure such as roads, signage and water sources. The long-term carbon stocks of the Forest are anticipated to increase over time. For example, the Option A Plan indicates that the timber inventory on the Forest will increase from about 22.7 MBF per acre in 2005 to 34.4 MBF per acre in 2105.

Forest products produced from LDSF will sequester carbon during their life cycle. Biomass fuels produced on the Forest also provide an opportunity to replace fossil fuels with an alternative energy source that is close to carbon neutral.

This analysis evaluates whether climate change and greenhouse gas (GHG) issues related to management of LDSF have the potential to be a significant environmental effect, either on a project basis or cumulatively. Table 2 summarizes estimated net carbon dioxide sequestration levels under proposed management at LDSF over a 100-year planning interval¹. The analysis shows substantial positive carbon sequestration benefits. Proposed management at LDSF will sequester a net CO₂ equivalent of 3,773,000 tons of carbon at the end of 100 years.

Table 2. Estimated carbon sequestration at LDSF over the next 100 years.

1	2	3	4	5	6	7
Current standing inventory	CO ₂ stored in current standing timber ²	Standing inventory at end of 100-year planning interval	CO ₂ stored in standing timber at end of 100-year planning interval	Total harvest over 100-year planning interval	Total CO ₂ sequestered in forest products at end of 100-year planning interval	Total net CO ₂ sequestered at end of 100-year planning interval (4-2+6)
MBF*	M* tons	MBF	M tons	MBF	M tons	M tons
196,931	1,575	308,096	2,465	360,460	2,884	3,773

* MBF is thousand board feet and M is thousand.

² A conversion factor of 8.0 was used to convert thousand board feet to tons of CO₂ including soil root biomass, duff, litter, canopy and non-bole tree parts (Smith et al, 2002, GTR NE-298).

¹ A 100-year look-ahead period is necessary in forested ecosystems, where trees can take more than 50 years to reach maturity. The 100-year planning interval allows a minimum period necessary to evaluate long-term steady-state behavior of forested ecosystem while not exceeding the range of applicability of mathematical simulation models.

Accounting for emissions from the Forest includes vehicles and buildings used by the Department that are associated with management. It also includes emissions from harvesting and manufacturing. We chose to do the downstream accounting. This will be the most conservative accounting approach because we are not including the negative substitution effect that occurs when alternative higher-GHG-impact building materials such as steel and concrete are used instead of wood products. Emissions from vehicles and buildings are estimated as follows:

Vehicles: 0.02 thousand (M) tons per year x 100-year planning horizon = 2 M tons

Building: 0.00003 M tons per year x 100-year planning horizon = 0.003 M tons

This is a total of 2.003 M tons for the 100-year planning horizon.

Harvesting emissions include in-woods emissions from equipment and vehicles and transportation to a mill. Mill emissions estimates from processing are included because long-term storage of wood products is included in the analysis. Mill emissions include sawing, drying, energy generation, and planing. Also, transport to final destination is included. The entire life cycle for green-dried lumber is included (Puettmann and Wilson 2005). This results in a total emission estimate of 0.13 metric tons CO₂ equivalent per thousand board feet (MBF).

Given the total harvest of 360,460 MBF over the 100-year planning horizon in table 1, this equates to 46,859 tons of CO₂ equivalent from harvesting emissions. Including vehicle and building emissions, the total GHG emissions estimate for LDSF is 46,861 tons of CO₂ equivalents.

These emissions including full life-cycle of wood, vehicle, and building emissions, represent 1.24 percent of the total carbon sequestered (column 7 in Table 2). The conclusion from the above analysis is that there is a substantial positive carbon sequestration benefit and a net negative emission of GHGs at LDSF under the guidance of the Project. Orders of magnitude more biomass is being conserved than is being harvested. In other words, the management plan proposes to harvest less biomass (and to emit less CO₂) than growth.

Climate change science is still in its infancy. There are likely wide error bars around the above estimates, given the general level of the analysis and the relatively new estimation equations in the literature. The result that positive sequestration benefits exceed emissions by orders of magnitude however, lends validity to the general conclusion that sequestration will be much greater than emissions. Our conclusion is also supported by estimates from the Air Resources Board, which indicate that forest land use in California results in a net decrease in atmospheric carbon, not an increase (http://www.arb.ca.gov/cc/inventory/data/tables/net_co2_flux_2007-11-19.pdf).

Since the net amount of carbon that would be sequestered under the Project is greatly higher than the amount of carbon that will be released by LDSF management activities, there are no potential significant adverse environmental impacts, single or cumulative. In fact, significant beneficial impacts of net carbon sequestration will occur.

I. CONCLUSION

This harvest will not have any significant cumulative impacts to the resources.

J. REFERENCE MATERIAL

PERSONS

Eric Wertz, Forester
Sierra Pacific Industries
P.O. Box 496014
Redding, CA 96049

Jan Castor
Sierra Pacific Industries
P.O. Box 496014
Redding, CA 96049

Kelly Dreesmann, Division Chief
CAL FIRE
875 Cypress Ave
Redding, CA 96001, (530) 225-2418

Pete Johnson, Forester
W.M. Beatty and Associates
P.O. Box 898
Redding, CA 96099 Ph: (530) 243-2783

LITERATURE AND MODELS

California Wildlife Habitat Relationship System Version 7.0

Cow Creek Watershed Assessment, prepared by SHN Consulting Engineers & Geologist, Inc.

Conservation Assessment and Strategy for Long-stiped Campion ..., prepared by Colin Dillingham and Allison Sanger, USFS Lassen National Forest, 2007.

LaTour Demonstration State Forest Watershed Monitoring Project, Stream Channel and Fish Habitat Assessment, Final Report, prepared by Sacramento Watershed Action Group.

A Guide to Wildlife Habitats of California California Wildlife - Volumes II & III

Pine Marten - Pacific Fisher Study Phase II Report 1992

Dept. of Fish and Game Natural Diversity Data Base

Soil Survey of Shasta County., U. S. Dept. of Agriculture


CDF Timber Harvest Plan Records

Aerial Photographs - Latour Demonstration State Forest




LaTour Demonstration State Forest Option A



LaTour Demonstration State Forest Management Plan 2008

Mitigated Negative Dec. (SCH# 2008062009), LaTour Demonstration State Forest Management Plan 2008





AB 47 Cumulative Map

- ++ THP 09-084
- LDSF Boundary
- .- Watershed Assessment Area
-  THP 02-187
-  THP 01-161
-  THP 99-253

-  THP 09-059
-  THP 08-071

Scale: 1 mile

 THP Boundary



PART OF PLAN**Rowe, Benjamin**

From: Stacy Stanish [SSTANISH@dfg.ca.gov]
Sent: Thursday, September 30, 2010 10:03 AM
To: Rowe, Benjamin
Subject: Latour ASP Pre-Consultation


Ben,

This email serves to satisfy the requirement of Forest Practice Rule 936.9(v) which states in part that an RPF may propose site-specific measures in Anadromous Salmonid Protection (ASP) watersheds provided these measures would result in equal or more favorable than the operational provisions of 936.9 and with prior concurrence with DFG.

On July 13, 2010, DFG conducted a site visit of the proposed plan area with the intent to verify watercourse classification by electrofishing on Lee March Gulch which flows into Cutter Meadow. The watercourse receives the majority of water from spring flow. The stream had long low-gradient (<4%) riffles with shallow pools and runs. Stream width ranges from one to two feet with maximum depth at the pools at about four to six inches. Substrate ranges from gravel to small cobble. About 500 feet of stream was electrofished and one rainbow trout (~six inches) was found about 100 feet before the stream went subterranean before entering the meadow. The RPF agreed to map the watercourse as Class I up to the spring.

The plan area is located within a watershed identified by DFG as an ASP watershed due to the presence of Central Valley steelhead (*Oncorhynchus mykiss*) or restorable to the presence of steelhead within the watershed. As a result of the electrofishing, the RPF proposes changing the WLPZ width to 75 feet with a "no cut" zone. Class II watercourses will have a standard with salvage cut outside of the core. Given that the silviculture in the plan is Group Selection, the management within the zone, and the location of the plan within the watershed DFG believes that the RPF's proposal for a site specific alternative provides equal protection to salmonids and their habitat as the provisions of 936.9.

Please contact me if you have any questions.



<https://r1.dfg.ca.gov/Portal/itp>

10/25/2010

-57.1-

FEB 08 2011

I. SOIL FACTORS				PART OF PLAN			FACTOR RATING BY AREA		
A. SOIL TEXTURE	Fine	Medium	Coarse	A	B	C			
1. DETACHABILITY	Low	Moderate	High	23	20	23			
Rating	1-9	10-18	19-30						
2. PERMEABILITY	Slow	Moderate	Rapid	1	2	1			
Rating	5-4	3-2	1						

A –
Windy/McCarthy
> 30% slope

B – Cohasset
stoney Loam <30%

C - Rehab

B. DEPTH TO RESTRICTIVE LAYER OR BEDROCK

	Shallow	Moderate	Deep			
	1"-19"	20"-39"	40"-60 (+)			
Rating	10-6	5-3	3-1	2	2	3

C. PERCENT SURFACE COARSE FRAGMENTS GREATER THAN 2 MM IN SIZE INCLUDING ROCKS OR STONES cx

	Low	Moderate	High				FACTOR RATING BY AREA		
	(-)10-39%	40-70%	71-100%				A	B	C
Rating	10-6	5-3	2-1	5	5	5			
➡ SUBTOTAL							31	29	32

II. SLOPE FACTOR

Slope	5-15%	16-30%	31-40%	41-50%	51-70%	71-80%(+)			
Rating	1-3	4-6	7-10	11-15	16-25	26-35	10	5	10

III. PROTECTIVE VEGETATIVE COVER REMAINING AFTER DISTURBANCE

	Low	Moderate	High			
	0-40%	41-80%	81-100%			
Rating	15-8	7-4	3-1	3	3	7

IV. TWO-YEAR, ONE-HOUR RAINFALL INTENSITY (Hundredths Inch)

	Low	Moderate	High	Extreme			
	(-) 30-39	40-59	60-69	70-80 (+)			
Rating	1-3	4-7	8-11	12-15	12	12	12
TOTAL SUM OF FACTORS ➡					56	49	61

EROSION HAZARD RATING

<50	50-65	66-75	>75			
LOW (L)	MODERATE (M)	HIGH (H)	EXTREME (E)			
THE DETERMINATION IS ➡				M	L	M



DEPARTMENT OF FORESTRY AND FIRE PROTECTION

875 CYPRESS AVENUE
REDDING, CA 96001-
(530) 225-2508
Website: www.fire.ca.gov



September 22, 2010

Carl J. and Jo Ann Davis
P.O. Box 142
Whitmore, CA 96069

Dear Jack and Jo:

As part of LaTour's next timber harvesting plan that I am preparing, the licensed timber operator will once again, as many years in the past, be using Roaring Springs as a drafting location to maintain Bateman Road. The use of Roaring Springs is required for both dust abatement and maintaining the roads surface in a stable condition. The Forest Practice rules require you to be included as a timberland owner on LaTour Demonstration State Forests' "Rock Pit" timber harvesting plan. Your inclusion as a timberland owner assumes no responsibility for timber operations on your part and is for water drafting only at Roaring Springs along Bateman Road. Water drafting is considered timber operations per Public Resources Code 4527 and as such all timberland owners where water drafting will occur must be included in the plan.

Per Public Resources Code 4582, if the person filing the plan is not the owner of the timberland, the plan submitter shall notify the timberland owner by certified mail that the plan has been submitted and shall certify that mailing to the Department.

As the Registered Professional Forester preparing the plan I am required to inform you of your responsibilities as the timberland owner. The Department of Forestry and Fire Protection has a right-of-way agreement for the use of Bateman Road. This agreement requires the Department to maintain the road in good condition. As such, the Department will assume the erosion control maintenance for the use of the water drafting location used under the North McMullen Mt THP.

Carl J. and Jo Ann Davis
 September 22, 2010
 Page Two

All water drafting operations performed under this THP on your property will conform to the Forest Practice act and Board of Forestry rules. Note that the Department of Forestry and Fire Protection has adjudicated water rights to Roaring Springs under the Cow Creek Adjudication Decree No. 38577 of the Superior Court for Shasta County.

Thank you very much.

Sincerely,

Ben Rowe

BENJAMIN ROWE
 Forester I, RPF #2686
 Assistant Forest Manager
 LaTour Demonstration State Forest

7005 0390 0002 5404 6476

U.S. Postal Service	
CERTIFIED MAIL RECEIPT	
(Domestic Mail Only: No Insurance Coverage Provided)	
For delivery information visit our website at www.usps.com	
OFFICIAL USE	
Postage	\$.44
Certified Fee	2.30
Return Receipt Fee (Endorsement Required)	2.30
Restricted Delivery Fee (Endorsement Required)	
Total Postage & Fees	\$ 5.54
Sent to Carl J. and Joanne Davis Street, Apt. No., or PO Box No. D.O. Box 142 City, State, ZIP+4 Whitmore, CA 96069	

SENDER: COMPLETE THIS SECTION		COMPLETE THIS SECTION ON DELIVERY	
1. Article Addressed to: Carl J. and Joanne Davis P.O. Box 142 Whitmore, CA 96069		A. Signature <input checked="" type="checkbox"/> Agent B. Received by (Printed Name) <input type="checkbox"/> Addressee C. Date of Delivery D. Is delivery address different from item 1? <input type="checkbox"/> Yes <input type="checkbox"/> No If YES, enter delivery address below:	
2. Article Number (Transfer from service label) 7005 0390 0002 5404 6476		3. Service Type <input checked="" type="checkbox"/> Certified Mail <input type="checkbox"/> Express Mail <input type="checkbox"/> Registered <input type="checkbox"/> Return Receipt for Merchandise <input type="checkbox"/> Insured Mail <input type="checkbox"/> C.O.D. 4. Restricted Delivery? (Extra Fee) <input type="checkbox"/> Yes	
PS Form 3811, February 2004		102595-02-M-1540	

**DEPARTMENT OF FORESTRY AND FIRE PROTECTION**

875 CYPRESS AVE
REDDING, CA 96001
Website: www.fire.ca.gov
(530) 225-2506



September 7, 2010

Brooks Walker et. al
C/O WM Beaty & Associates
PO Box 990898
Redding, CA 96099-0898

To Whom It May Concern:

LaTour Demonstration State Forest is in the process of preparing a Timber Harvesting Plan (THP). The location of the THP is in Shasta County, Township 32 North, Range 2 East, including portions of Sections 1, 2, 3, 11, and 12, Mount Diablo Base and Meridian.

The California Code of Regulations, Title 14 Section 1032.10 requires that the THP Submitter provide notice by letter to all other landowners within 1000 feet downstream of the THP boundary whose ownership adjoins or includes a Class I, II, or IV watercourse which receives surface drainage from the proposed timber operations.

This notice is to request information about surface domestic water use from Butcher Gulch, Lee Marsh Gulch, White Fawn Gulch, and Peavine Gulch within 1000 feet of the State Forest boundary. If you have any information about domestic water use in the area specified, please contact Ben Rowe within 10 days of receipt of this notice at the address or phone number listed above.

Thank you very much.

Sincerely,

Benjamin Rowe, RPF# 2686
Assistant Forest Manager
LaTour Demonstration State Forest
875 Cypress Ave.
Redding, CA 96001
530-225-2508

**DEPARTMENT OF FORESTRY AND FIRE PROTECTION**

875 CYPRESS AVE
REDDING, CA 96001
Website: www.fire.ca.gov
(530) 225-2506



September 7, 2010

Sierra Pacific Industries
Sierra Pacific Holding Co
P.O. Box 496014
Redding, CA 96049

To Whom It May Concern:

LaTour Demonstration State Forest is in the process of preparing a Timber Harvesting Plan (THP). The location of the THP is in Shasta County, Township 32 North, Range 2 East, including portions of Sections 1, 2, 3, 11, and 12, Mount Diablo Base and Meridian.

The California Code of Regulations, Title 14 Section 1032.10 requires that the THP Submitter provide notice by letter to all other landowners within 1000 feet downstream of the THP boundary whose ownership adjoins or includes a Class I, II, or IV watercourse which receives surface drainage from the proposed timber operations.

This notice is to request information about surface domestic water use from Butcher Gulch, Lee Marsh Gulch, White Fawn Gulch, and Peavine Gulch within 1000 feet of the State Forest boundary. If you have any information about domestic water use in the area specified, please contact Ben Rowe within 10 days of receipt of this notice at the address or phone number listed above.

Thank you very much.

Sincerely,

Benjamin Rowe, RPF# 2686
Assistant Forest Manager
LaTour Demonstration State Forest
875 Cypress Ave.
Redding, CA 96001
530-225-2508



January 13, 2012

Sierra Nevada Conservancy

RE: Letter of Support for CAL FIRE Latour Demonstration State Forest Sierra Nevada Conservancy Grant Applications

The Cow Creek Watershed Management Group (CCWMG) is an organization comprised of local ranchers, timber companies, small landowners and other involved citizens interested in protecting and managing the Cow Creek drainage and other surrounding watersheds. As such our organization has a vested interest in activities that take place in and that may directly affect those watersheds.

As water issues are one of the major focuses of our members, proper management at the headwaters of these watersheds, which are located on Latour Demonstration State Forest (LDSF), is a key factor in maintaining the health of these drainage systems. A catastrophic fire in these watersheds, particularly at the headwaters, would negatively influence the quality and quantity of water received downstream. Such an event would result in direct, dramatic and long-lasting environmental as well as economic impacts to the watersheds and surrounding communities as a whole, harming stream channels, farmers, ranchers, fisheries and wildlife. As tributaries to the Sacramento River, impacts to these watersheds could also have far reaching implications downstream, resulting in increased flood potential during winter and spring run-off and less water availability during the summer and fall months in the Sacramento Basin.

We believe that both the Fuelbreak/Biomass and Brush Conversion projects proposed by CAL FIRE on LDSF would serve to protect and enhance these watersheds by reducing the potential for catastrophic fire. They would also serve to enhance the economic vitality of surrounding communities by improving the timber stands and providing essential raw materials for manufacturing and energy production. The CCWMG enthusiastically advocate and support such efforts and encourage the Sierra Nevada Conservancy to provide funding for these projects.

Sincerely,


A handwritten signature in black ink that reads "Susan Goodwin". The signature is fluid and cursive, with the first name "Susan" and last name "Goodwin" clearly distinguishable.

Susan Goodwin, President
Cow Creek Watershed Management Group


Vicinity Map

LaTour Demonstration State Forest









LaTour Demonstration State Forest
Shasta County Parcel Map



Legend

-  Shasta County Parcel
-  CA Dept of Forestry and Fire Protection
-  USDA Forest Service

LDSF Fuelbreak/Flat Top Biomass






Photo #1 - LDSF Fuelbreak/Table Top Biomass –
McMullen Mountain Road Fuelbreak Segment



Photo #2 - LDSF Fuelbreak/Table Top Biomass –
McMullen Mountain Road Fuelbreak Segment



Photo # 3 - LDSF Fuelbreak/Table Top Biomass –
McMullen Mountain Road Fuelbreak Segment



Photo # 4 - LDSF Fuelbreak/Table Top Biomass –
McMullen Mountain Road Fuelbreak Segment




Photo # 5 - LDSF Fuelbreak/Table Top Biomass – Rim Road Fuelbreak Segments
(Ground Photos Unavailable)




Photo # 6 - LDSF Fuelbreak/Table Top Biomass – Table Top Biomass Area



Photo # 7 - LDSF Fuelbreak/Table Top Biomass – Table Top Biomass Area



Photo # 8 - LDSF Fuelbreak/Table Top Biomass – Table Top Biomass Area



Photo # 9 - LDSF Fuelbreak/Table Top Biomass – Table Top Biomass Area



Photo # 10 - LDSF Fuelbreak/Table Top Biomass – Cutter Road Fuelbreak Segment



Photo # 11 - LDSF Fuelbreak/Table Top Biomass – Cutter Road Fuelbreak Segment



Photo # 12 - LDSF Fuelbreak/Table Top Biomass – Cutter Road Fuelbreak Segment



Photo # 13 - LDSF Fuelbreak/Table Top Biomass – Cutter Road Fuelbreak Segment

LATOUR
LAND
File 12. 200

4. 010
file

Document
Recorded under
Serial # 12253
Book 551
Page 231
Shasta
County
Dec 4. 1957
1045 am

original
recorded
document
forwarded
Sacts 12/9/57
or per AK-12-3

STATE OF CALIFORNIA



DEPARTMENT OF STATE

To all to whom these presents shall come, Greetings:

I, FRANK M. JORDAN, Secretary of State of the State of California, hereby certify:

That the annexed transcript has been compared with the RECORD on file in my office, of which it purports to be a copy, and that the same is full, true and correct.

In testimony whereof, I, FRANK M. JORDAN, Secretary of State, have hereunto caused the Great Seal of the State of California to be affixed and my name subscribed, at the City of Sacramento, in the State of California,
this DEC 2 - 1957

Frank M. Jordan
Secretary of State

By *Chas. J. [Signature]*
Assistant Secretary of State

93

Senate Bill No. 555

CHAPTER 1464

An act to provide for the transfer from the State Lands Commission to the Division of Forestry of the Latour Forest and making an appropriation.

[Approved by Governor July 17, 1945. Filed with Secretary of State July 17, 1945.]

The people of the State of California do enact as follows:

SECTION 1. The State Lands Commission is authorized and directed to sell to the Division of Forestry that certain real property in Shasta County known as the Latour Forest, comprising the portion of the public lands owned by the State, to be used by the Division of Forestry for such purposes as may now or hereafter be authorized by law.

SEC. 2. Upon the issuance of a patent for said lands to the Division of Forestry in the name of the State the agreed sale price of such lands shall be deposited in the School Fund in the State treasury from the appropriation made by this act.

SEC. 3. The sum of one hundred thousand dollars (\$100,000) or so much thereof as may be necessary is hereby appropriated out of any money in the State treasury not otherwise appropriated to be expended during the Ninety-seventh and Ninety-eighth Fiscal Years to carry out the provisions of this act.

STATE OF CALIFORNIA
SACRAMENTO 14

Inter-Departmental Communication

To: Frank M. Jordan,
Secretary of State,
Sacramento, California.

File No. AB-1-14

Date: January 14, 1946

Subject: LANDS
State Forest
La Tour State Forest

From: Division of Forestry

There is submitted for your disposition the patent to the State of California acting on behalf of the Department of Natural Resources, Division of Forestry, covering 9,173.35 acres of land in Shasta County known as the La Tour State Forest. This patent has been issued in accordance with the provisions of Chapter 1464, 1945, which authorizes this acquisition by the Division of Forestry upon the payment of \$100,000.00

STATE FORESTER

By *C. R. Glar*
C. R. Glar, Chief Deputy.

20
Encl.

RECEIVED
SACRAMENTO, CALIF.

1946 JAN 15 PM 2 31

FRANK M. JORDAN
SECRETARY OF STATE
STATE OF CALIFORNIA


STATE OF CALIFORNIA
STATE LANDS COMMISSION
DIVISION OF STATE LANDS
STATE CAPITOL, SACRAMENTO

I, J. STUART WATSON, Executive Officer of the State Lands Commission, hereby certify that the State of California, on January 8, 1946, issued Patent No. 19074 transferring jurisdiction of the area known as the "La Tour Forest" from the State Lands Commission to the Division of State Forestry; that in said patent the aggregate area of the lands patented was given as 9,173.35; that said aggregate area of said lands was the same as recited in the patents issued by the United States to the State of California; that a re-check of the areas as shown on the United States government plate of surveys shows the aggregate area of the lands described in said patent as 9,013.35 acres.

IN WITNESS WHEREOF, I hereto set my hand and affix

the seal of the State Lands

Commission this 29th day of July, 1947.



J. Stuart Watson
Executive Officer,
STATE LANDS COMMISSION.

RECEIVED

DEC 2 1957



STATE OF CALIFORNIA
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF FORESTRY
INTEROFFICE CORRESPONDENCE

TO: George Grogan, Deputy State Forester

DATE December 3, 1957

SUBJECT: LANDS - Latour State Forests
Shasta County
District II


Address Reply to STATE FORESTER

Refer to Number: AK-12-3

Attached is a certified copy of the Patent to the State of California acting on behalf of the Department of Natural Resources, Division of Forestry, covering 9,173.35 acres of land in Shasta County, known as the Latour State Forests. Will you please have this document recorded in the County of Shasta at your very earliest convenience and return the recorded document to this office.

Also attached are two copies of the Patent for your files and that of the Ranger.

F. H. RAYMOND
State Forester


By
Melvin Pomponio
Deputy State Forester

21
Att:

State of California

To All to whom these Presents shall come, Greeting:

WHEREAS, Under the provisions of an Act of the Congress of the United States, entitled "An act to provide for the survey of the public lands in California, the granting of preemption rights therein, and for other purposes," approved March third, eighteen hundred and fifty-three, there was granted to the State of California, the sixteenth and thirty-sixth sections of each township in said State and lands selected in lieu thereof under the provisions of said Act and also under the provisions of subsequent Acts of said Congress of the United States; and whereas, the Legislature of the State of California has provided for the sale and conveyance of said lands by statutes enacted from time to time; and whereas, it appears by the certificate of _____ Carlyle F. Lynton, Executive Officer _____ of the State Lands Commission No. — 19074 —, issued in accordance with the provisions of law, bearing date the _____ 26th _____ day of _____ December _____, 19 45, that the tracts of land hereinafter described have been duly and properly located in accordance with law, that the laws in relation thereto have been complied with, that payment in full has been made, and that _____ STATE OF CALIFORNIA _____

is entitled to receive a patent therefor;

Now, THEREFORE, The State of California hereby grants to the said _____

STATE OF CALIFORNIA _____

the said tracts of land located as aforesaid, and which are known and described as follows, to wit: _____

— Lots one, two, three and four, the east half of lot five, lots six and seven, the west half of lot nine, the east half of lot ten, lots eleven and twelve, and the south three hundred and twenty (320) acres (or the south half) of Section one (1), the east half of lot eight, the west half of lot nine, the west half of lot twelve, the southwest quarter of the southwest one hundred sixty (160) acres (or the southwest quarter of the southwest quarter), the east half of the southwest one hundred sixty (160) acres (or the east half of the southwest quarter), the southwest quarter of the southeast one hundred sixty (160) acres (or the southwest quarter of the southeast quarter), and the east half of the southeast one hundred sixty (160) acres (or the east half of the southeast quarter) of Section two (2), lots five, eight, nine, the east half of lot ten, lot twelve, the southwest one hundred sixty (160) acres (or the southwest quarter), the west half of the southeast one hundred sixty (160) acres (or the west half of the southeast quarter), and the southeast quarter of the southeast one hundred sixty (160) acres (or the southeast quarter of the southeast quarter) of Section three (3), Sections ten (10), eleven (11), twelve (12), and thirteen (13), the east half, the north half of the northwest quarter and the south half of the southwest quarter of Section fourteen (14), the north half of the northwest quarter, the north half of the northeast quarter, the south half of the southwest quarter, and the south half of the southeast quarter of Section fifteen (15), Sections twenty-two (22) and twenty-three (23), and the north half of Section twenty-four (24), Township thirty-two (32) north, Range two (2) east; Sections six (6) and seven (7), the west half of Section seventeen (17), and Section eighteen (18), Township thirty-two (32) north, Range three (3) east; and lot four and the southeast forty (40) acres of the southwest quarter (or the southeast quarter of the southwest quarter) of Section thirty-one (31), Township thirty-three (33) north, Range three (3) east, Mount Diablo Meridian, reserving to the State of California all oil, gas, oil shale, coal, phosphate, sodium, gold, silver, and all other mineral deposits contained in said lands, and further reserving to the State of California, and persons authorized by the State, the right to drill for and extract such deposits of oil and gas, or gas, and to prospect for, mine, and remove such deposits of other minerals from said lands, and to occupy and use so much of the surface of said lands as may be required therefor, upon compliance with the conditions and subject to the provisions and limitations of Chapter 5, Part I, Division 6 of the Public Resources Code, and further reserving in the people the absolute right to fish thereupon as provided by Section 25 of Article I of the Constitution of the State of California, _____

containing in the aggregate _____ 9,173.35 _____ acres.

IN TESTIMONY WHEREOF, I, _____ EARL WARREN _____

Governor of the State of California, have caused these Letters to be made Patent, and the Seal of the State of California to be hereunto affixed. Given under my hand at the City of Sacramento, this, the 8th day of January, in the year of our Lord one thousand nine hundred and forty-six.

_____ Earl Warren
Governor of State


Attest _____
Secretary of State

Countersigned: _____
Executive Officer,
STATE LANDS COMMISSION




STATE PRINTING OFFICE


Shasta County.




LaTour Demonstration State Forest
Cutter Fuelbreak




- Legend**
- Shasta County Parcel
 - CA Dept of Forestry and Fire Protection
 - USDA Forest Service
 - Cutter Fuelbreak




LaTour Demonstration State Forest
MM Fuelbreak




- Legend**
- Shasta County Parcel
 - CA Dept of Forestry and Fire Protection
 - USDA Forest Service
 - MM Fuelbreak




LaTour Demonstration State Forest
Rim Road Fuel Break 1




- Legend**
- Shasta County Parcel
 - CA Dept of Forestry and Fire Protection
 - USDA Forest Service
 - RimRoad Fuelbreak 1




LaTour Demonstration State Forest
Rim Road Fuel Break 2



- Legend**
- Shasta County Parcel
 - CA Dept of Forestry and Fire Protection
 - USDA Forest Service
 - RimRoad Fuelbreak 2



***LaTour Demonstration State Forest
Table Top Biomass & Rim Road
Brush Conversion***



- Legend**
- Shasta County Parcel
 - CA Dept of Forestry and Fire Protection
 - USDA Forest Service
 - TableTop_Biomass
 - RimRoad_Brush_Conversion